

30024056



Superfund

Site: MOUND ST. PCB
 ID #: MO0000093682
 Breaks: L5
 Other: N/A

SITE INSPECTION WORKSHEET

CERCLIS IDENTIFICATION NUMBER
MO0000093682

SITE LOCATION

SITE NAME: LEGAL, COMMON, OR DESCRIPTIVE NAME OF SITE
 Mound Street PCB Site (part of the Laclede Coal Gas Site MO981715980)

STREET ADDRESS, ROUTE, OR SPECIFIC LOCATION IDENTIFICATION

North on Broadway from Broadway Street exit off Interstate 64 or south on Broadway from the Salisbury Street exit off Interstate 70, to Mullanphy Street, turn east on Mullanphy then turn left onto a gravel roadway just past the Apex Oil facility on the left. Take the gravel roadway north to Mound Street. The site is encompassed by Mound Street, the gravel roadway, and the Petroleum, Fuel and Terminal-Apex Oil Facility (PFT-Apex Oil).

CITY St. Louis	STATE MO	ZIP CODE 63102	TELEPHONE N/A
--------------------------	--------------------	--------------------------	-------------------------

COORDINATES: LATITUDE & LONGITUDE 38° 38' 34.0" N Lat., 90° 10' 57.2" W Long.	TOWNSHIP, RANGE, AND SECTION T45N, R7E, Section
---	---

OWNER/OPERATOR IDENTIFICATION

OWNER McKinley Iron (Contact: Herman Gellman)	OPERATOR McKinley Iron (Contact: Herman Gellman)
---	--

OWNER ADDRESS 3620 North Hall Street	OPERATOR ADDRESS 3620 North Hall Street
--	---

CITY St. Louis	CITY St. Louis
--------------------------	--------------------------

STATE MO	ZIP CODE 63147	TELEPHONE (314) 231-6077	STATE MO	ZIP CODE 63147	TELEPHONE (314) 231-6077
--------------------	--------------------------	------------------------------------	--------------------	--------------------------	------------------------------------

SITE EVALUATION

AGENCY/ORGANIZATION Sverdrup Corporation	EPA REGION VII
--	--------------------------

INVESTIGATOR Michael W. McCurdy, CHMM	
---	--

CONTACT Michael W. McCurdy, CHMM	EPA CONTACT Dr. Pete Culver, PE
--	---

ADDRESS 4400 College Blvd., Suite 160	ADDRESS 726 Minnesota Avenue
---	--

CITY Overland Park	CITY Kansas City
------------------------------	----------------------------

STATE KS	ZIP CODE 66211	TELEPHONE (913) 663-2101	STATE KS	ZIP CODE 66101	TELEPHONE (913) 551-7707
--------------------	--------------------------	------------------------------------	--------------------	--------------------------	------------------------------------

GENERAL INFORMATION

Site Description and Operational History: Provide a brief description of the site and its operational history. State the site name, owner, operator, type of facility and operations, size of property, active or inactive status, and years of waste generation. Summarize waste treatment, storage, and disposal activities that have or may have occurred at the site; note whether these activities are documented or alleged. Identify all source types and prior spills, floods, or fires. Summarize highlights of the PA and other investigations. Cite references.

The Mound Street PCB Site is part of the Laclede Coal Gas Site (MOD981715980). The Laclede Coal Gas Site also includes the PFT-Apex Oil facility located west and south of the Mound Street PCB Site. The total area of the Mound Street PCB Site is estimated at approximately 1.5 acres (References 15 and 23). The buildings on the site were demolished in 1991, and the property currently has no structures upon it. The property is owned by McKinley Iron, Inc. located at 3620 North Hall Street, St. Louis, Missouri. Mr Gellman was interviewed during the site reconnaissance. He did not know if the basement walls and floor were removed during building demolition. He did state that the basement area was probably filled with demolition debris. He was not aware of any unusual observations made, such as stained soil or odors, during the building demolition. He estimated the basement depth to be between 12 and 14 feet. Mr. Gellman stated the property was originally purchased from Union Electric to salvage power plant equipment. The site is roughly rectangular in shape and is bordered on three sides by industrial property. Gravel roads are located along the property perimeter, with Mound Street being the northern boundary. An east-west dirt path has been made across the property. No fencing or other barrier exists around the property. Bricks, rock, wood, metal, brush, and concrete debris are located on the southern portion of the property. Several small soil piles were observed along the southeastern edge of the property. Two 55-gallon drums were also observed adjacent to the debris. The contents of the drums are unknown. The northern portion is overgrown with grass and weeds and other vegetation. The general surface runoff is toward the east and south. To the east is vacant property with railroad tracks, the concrete flood wall, and then the Mississippi River (Reference 23).

The St. Louis Metropolitan Sewer District (MSD), Brooklyn Street pump station is located approximately 575 feet north-northeast of the site. The pump station is located on the west side of the flood wall. Two wells sampled in 1991 by E&E/FIT and three manholes sampled by MSD in 1993 were identified. An abandoned pump house, once part of the Mound Street Power Plant, is located on the east side of the flood wall. The abandoned pump house is in poor condition. At the time of the site reconnaissance visit, the water level of the Mississippi River was at the bottom of the pump house. The abandoned pump house was deeded to the City of St. Louis for the construction of a bike path along the river (Reference 23).

The site is part of the Laclede Gas and Light Company former manufactured gas plant (FMGP), which operated in the late 1800s to the mid-1940s. Laclede Gas used a retort process for coal carbonization in the generation of gas. Approximately 930 million gallons of coal tar waste were produced at this facility. It is estimated that approximately 76 percent of the waste was sold, with the remaining 24 percent being buried on-site (Reference 4). This equates to approximately 224 million gallons of coal tar waste potentially buried at the site. On-site burial was typically conducted in unlined pits. In 1940, operations were split between Laclede Gas Light Company (Laclede Gas) and Laclede Power and Light Company (Laclede Electric) (References 3 and 4). In 1945, Union Electric (UE) purchased the entire coal gas facility and operated the Mound Street Power Plant from 1945 to 1973. UE did not manufacture coal gas at this site. In 1969, the Apex Oil Company purchased the former coal gas works (Laclede Gas) from UE. UE, however, continued to operate its electrical facility from the former Laclede Electric works. The Apex Oil Company utilized the site as a tank farm for the storage of petroleum fuels until the mid-1980s, when it became an asphalt product terminal (References 3 and 4). The PFT-Apex Oil facility is currently still operating at this location. In 1973, the UE property (Laclede Electric works) was transferred to the Tenlis Company. Tenlis dismantled the power generation and transmission equipment. Transformer oil was reportedly disposed by Midwest Oil Company. The dismantled equipment was sold as scrap metal (Reference 4). In 1981, Tenlis transferred the property to AZCON (Reference 3). The operations of AZCON are unknown; however, it was reported in the MDNR PA report that AZCON could have been a metal recycling company (Reference 15). In 1985, Mound Street Corporation became the property owner and leased the building to an individual for an electric motor stripping operation (Reference 3). An oil fire occurred in the basement of the building in 1989, and the building was demolished in the spring of 1991 (Reference 15). McKinley Iron became the owner of the property in 1993 (Reference 15). The property does not have any buildings or other structures, and is currently vacant (References 7 and 23).

References: 3, 4, 7, 15, 23

The Mound Street PCB Site has had numerous investigations conducted since 1976.

- The U.S. Coast Guard investigated oil slicks in the Mississippi River, in the vicinity of the Mound Street PCB Site, three times between 1976 to 1987. The oil slicks were reportedly originating from the Mound Street Power Plant. The basement of the Mound Street Power Plant was the suspected source of oil; however, no specific source was identified. No samples were collected during any of the Coast Guard investigations (References 3 and 4).
- The St. Louis City Division of Health conducted an investigation of the Mound Street Power Plant on April 8, 1987. Six oil samples were collected from the basement of the Mound Street building and analyzed for PCBs. No PCB contamination was identified; however, detection limits were not recorded (References 3 and 4).
- The The Ecology and Environment/Field Investigation Team (E&E/FIT) submitted a PA report of the Mound Street Power Plant Site on June 23, 1988 (Reference 4). The field activities were conducted on September 17, 1987. Six oil, water and oil/water mixture samples were collected from the Mound Street building basement and two from manholes in Mound Street during the PA site reconnaissance. The samples were analyzed for PCBs. No PCB contamination was detected at a 1 mg/kg detection limit in any of the samples. The source of oil in the basement of the Mound Street Power Plant building (Mound Street PCB Site) was potentially identified as the adjacent PFT-Apex Oil terminal. It was stated in the report that PFT-Apex Oil had numerous spills, some of which entered the Mound Street building basement. Transformers and hydraulic oil tanks, located in the Mound Street building basement, were supposedly drained and removed in the 1970s; however, no records confirming the proper disposal of oil were available.
- The E&E/FIT conducted a site reconnaissance of the Laclede Gas and Light FMGP on November 20, 1990 for the preparation of the SSI work plan. Seepage was observed emanating from the foundation and piping system of an abandoned pump house, formerly part of the Mound Street Power Plant. The pipes were reportedly plugged with concrete; however, seepage was leaching through the concrete. The pump house is located on the eastern side of the flood wall, therefore, the seepage was going directly into the Mississippi River. No samples were collected and no description of the seepage material was made during the site reconnaissance (Reference 3).
- The E&E/FIT submitted an SSI report on the Laclede Gas and Light FMGP Site on October 29, 1991 (Reference 3). Field activities for the SSI occurred March 3-9, 1991. Subsurface soil, surface soil, sediment, surface water and groundwater samples were collected on and around the PFT-Apex Oil property. No samples were collected from the basement of the Mound Street Power Plant Building (Mound Street PCB Site), as originally planned, since the building was being demolished at the time of the SSI field activities. Numerous samples were collected in the vicinity of the Mound Street PCB Site. Only these sample results will be discussed below. Five borehole screening locations, four surface soil sample locations, three groundwater sample locations, three surface water sample locations, and three sediment sample locations are in the vicinity of the Mound Street PCB Site. Screening results indicated the presence of benzene, toluene, xylene and PAHs in the surface and subsurface soil in the vicinity of the Mound Street PCB Site (borings B01, B02, B03, B17 and B18). Boring B23 was utilized as a background location, and the results showed nondetect for volatiles, metals, and semivolatiles. Screening values for surface water samples were nondetect for the same parameters. Screening analysis of sediment samples indicated the presence of xylene and PAHs. Surface soil samples submitted for CLP analysis were collected from the 0 - 2 foot interval. Samples were analyzed for semivolatiles, total metals and cyanide. Cyanide and PAHs were detected above the background detection limits. Metal concentrations were negligible when compared to background levels. Sediment samples submitted for CLP analysis were analyzed for total petroleum hydrocarbons, volatiles, semivolatiles, cyanide and total metals. The extreme upgradient sample (Sample 402) exhibited the highest concentrations; however results are comparable between sediment sample locations. No background sediment sample was collected.

Five groundwater samples were collected (Sample 201, 202, 203, 204 and 206) and analyzed for volatiles, semivolatiles, cyanide and total metals. Groundwater sample analysis showed 65 ug/L acenaphthalene, 25 ug/L fluorene, 46 ug/L phenanthene, 93 ug/L benzene and 1600 ug/L cyanide in Well 204. Well 203 sample analysis did not show any contamination except for 590 ug/L cyanide. Both cyanide results are "J" coded because the data did not strictly meet all QC criteria. Well 206 (background) did not show any contamination above detection limits.

Arsenic, barium, copper, chromium, nickel, selenium, vanadium, and zinc were not detected in four surface water samples (Sample 301, 302, 303 and 304), except as indicated. Surface water sample analysis showed lead levels at 7.0 ug/L for 301, 7.2ug/L for 301D, 9.7 ug/L for 302, <24 ug/L for 303, 18 ug/L for 304, and 15ug/L for 304D. Sample location 303 also showed barium at 280 ug/L, vanadium at 62 ug/L, zinc at <89 ug/L and an invalid selenium result of 11 ug/L. Sample location 304 and 304D showed chromium at 14 ug/L and 12 ug/L, respectively. Sample location 304 also had a result of 54 ug/L for zinc. Sample 304 was collected from the Illinois-American Water Company surface intake located across the Mississippi River from the site. Sample locations are shown in Figure 6. Surface water samples were analyzed for total petroleum hydrocarbons, volatiles, semivolatiles, cyanide and total metals. None of the samples collected during the Laclede Coal Gas SSI were analyzed for PCBs.

In the E&E/FIT SSI report, it is stated that a mixed source is present since BETX compounds "are not considered abundant in coal tar." The PAHs and cyanide were attributed to the former coal gas operations. It was also stated that some PAH contamination may be attributed to the adjacent PFT-Apex Facility, which stores oil and asphalt.

- On July 8, 1993 St. Louis MSD personnel discovered oil seeping into the Brooklyn Street storm water pump station, located at the eastern end of Brooklyn Street and approximately 400 feet north of the Mound Street PCB Site (Reference 7). This pump station is only operational during heavy precipitation or if the Mississippi River level is above flood stage. In July, 1993, the Mississippi River was above flood stage. A waste oil sample from the pump station wet well was collected and analyzed for PCBs by the MSD. A PCB concentration of 47 mg/L was detected (Reference 12). The possible source was identified as an underground storage tank (UST) on the adjacent property (Reference 20). On August 9, 1993, waste oil samples from three manholes located along the flood wall were collected and analyzed for PCBs by the MSD. These three manholes are part of the underdrain system for the flood wall and are not part of the storm sewer system. The concentrations of PCBs were 25.4 mg/L in Manhole F-GA1 (#12), 11.7 mg/L in Manhole F-GA1 (#13), 36.6 mg/L in Manhole F-GA1 (#14) (Reference 13). Five 55-gallon drums of waste oil were pumped out of the storm sewer by REACT Environmental Engineers and disposed of by Tipton Environmental Services (References 5 and 7). In the conclusion of the Special Problem Investigation report completed by MSD, it is stated the UST appears to be the source of the oil in the pump station. It is further stated that ground saturation of oil from an old Union Electric facility is another possibility (Reference 20).

A 12,000-gallon UST (10.5 foot diameter by 18.5 feet long) containing petroleum products was discovered during an investigation to identify the potential source of the PCBs in the pump station (Reference 9). The UST was located on Terminal Railroad Association (TRRA) property, southwest of the Brooklyn Street pump station. The TRRA property is located on the north side of Mound Street, directly across from the Mound Street PCB Site. A sample was collected from the UST on July 14, 1993 by MSD. Sample analysis showed PCBs in the UST at 39 mg/L (Reference 12). The existence of the UST was unknown to TRRA prior to notification by the St. Louis Fire Marshall. The tank contents were removed on August 4, 1993 by Environmental Operations, under supervision by GEHM Corporation. Sixteen 55-gallon drums of sludge/liquid were removed from the UST. Sample analysis of the tank contents showed PCBs at less than 10 mg/kg (Reference 9). Analysis of soil samples collected from the UST excavation showed PCBs at less than 0.05 mg/kg (Reference 10). Approximately 30 cubic yards of soil were removed during excavation of a 16 foot wide, 25 foot long and 12 foot deep UST pit. It is estimated that less than 50 gallons of water was in the UST pit after excavation activities (Reference 10); however, no sample of the water was collected. On August 17, 1993 EnTech Engineering, under supervision by GEHM Corporation, conducted an Infrared Thermograph (IR/T) survey of the TRRA Site. No evidence of a leak plume was identified during this study. An anomaly was discovered, approximately 10 foot square, on the Mound Street PCB property. Boreholes were attempted at the location of the anomaly; however, they were abandoned after auger refusal at a depth of 5 feet due to encountering solid rock debris (Reference 9). The foundation or basement of the demolished Mound Street Site buildings could explain the presence of the IR/T anomaly (Reference 7).

A letter from Randel Lewis, Terminal Manager for the Petroleum Fuel and Terminal Facility, to Charles Gay, St. Louis City Fire Inspector, was written in response to a September 8, 1993 telephone conversation (Reference 11). In the letter, Mr. Lewis stated that a leak in a 6-inch pipeline was discovered at the facility. Repairs to the pipeline were made with approximately 2.5 barrels of oil/soil being disposed of. It is further stated that the pipeline was taken out-of-service. The letter does not indicate where the pipeline was located.


- The Missouri Department of Natural Resources (MDNR) submitted a PA report on the Mound Street PCB Site on March 21, 1994 (Reference 15). Field activities for the PA occurred on November 11, 1993. No samples were collected during the PA. The conclusions of the PA report indicate that a threat from the groundwater pathway is very unlikely, a release to the Mississippi River appears likely, an exposure through the soil pathway is low and an exposure through the air pathway is also low.

No further incidences of oil in the Brooklyn Street pump station or manholes along the flood wall have occurred since the 1993 spill (Reference 6).

References: 3, 4, 5, 6, 7, 9, 10, 11, 12, 13, 15, 20

GENERAL INFORMATION (continued)

Site Sketch: Provide a sketch of the site. Indicate all pertinent features of the site and nearby environments including sources of waste, areas of visible and buried wastes, buildings, residences, access roads, parking areas, fences, fields, drainage patterns, water bodies, vegetation, wells, sensitive environments, and other features.



GENERAL INFORMATION (continued)

Source Description: Describe all sources at the site. Identify source type and relate to waste disposal operations. Provide source dimensions and the best available waste quantity information. Describe the condition of sources and all containment structures. Cite references.

SOURCE TYPES

Landfill: A man-made (by excavating or construction) or natural hole in the ground into which wastes have come to be disposed by backfilling, or by contemporaneous soil deposition with waste disposal.

Surface Impoundment: A natural topographic depression, man-made excavation, or dike area, primarily formed from earthen materials (lined or unlined) and designed to hold an accumulation of liquid wastes, wastes containing free liquid, or sludge nor backfilled or otherwise covered; depression may be wet with exposed liquid or dry if deposited liquid has evaporated, volatilized, or leached; structures that may be described as lagoon, pond, tailings pond, sludge pit; also a surface impoundment that has been covered with soil after the final deposition of waste materials (i.e., buried or backfilled).

Drum: A portable container designed to hold a standard 55-gallon volume of waste.

Tank and Non-Drum Containers: Any device, other than a drum, designed to contain an accumulation of waste that provides structural support and is constructed primarily of fabricated materials (such as wood, concrete, steel, or plastic); any portable or mobile device in which waste is stored or otherwise handled.

Contaminated Soil: An area or volume of soil onto which hazardous substances have been spilled, spread, disposed, or deposited.

Pile: Any non-containerized accumulation above the ground surface of solid, non-flowing waste; includes open drums. Some types of waste piles are:

- **Chemical Waste Pile:** A pile consisting primarily of discarded chemical products, by-products, radioactive wastes, or used or unused feedstocks.
- **Scrap Metal or Junk Pile** A pile consisting of scrap metal or discarded durable goods (such as appliances, automobiles, auto parts, batteries, etc.) composed of materials containing hazardous substances.
- **Tailing Pile:** A pile consisting primarily of any combination of overburden from a mining operation and tailings from a mineral mining, beneficiation, or processing operation.
- **Trash Pile** A pile consisting primarily of paper, garbage, or discarded non-durable goods containing hazardous substances.

Land Treatment: Landfarming or other method of waste management in which liquid wastes or sludges are spread over land and tilled, or liquids are injected at shallow depths into soil.

Other: Sources not in categories listed above.

GENERAL INFORMATION (continued)

Source Description: Include description of containment per pathway for groundwater (see HRS Table 3-2), surface water (see HRS Table 4-2), and air (see HRS Tables 6-3 and 6-9).

The contaminants of concern at the Mound Street PCB Site originate from at least two separate sources; 1) coal gas operations, and 2) electrical power generation and transmission operations. The former is a source for coal tar wastes and spent oxides, while the latter is a potential source for PCBs. Coal tar wastes include polynuclear aromatic hydrocarbons (PAHs) and phenolic compounds resulting from combustion processes, and spent iron oxides resulting from gas purification processes. Benzene, ethylbenzene, toluene and xylene are possible constituents of coal tar wastes. Iron oxides may contain sulphur, cyanide and small quantities of coal tar. PCBs are found in transformer and hydraulic oil. It is estimated that approximately 223,680,000 gallons of coal tar wastes may be buried on the former Laclede Coal Gas Site, which includes the Mound Street PCB Site (Reference 3). The quantity, if any, of PCB contaminated oil in the subsurface is not known.

No confining layer is known to exist between the alluvium and bedrock. Also, no aquifer discontinuity exists within the 4-mile target distance limit (Reference 21). Based on Geoprobe borings conducted during the April, 1996, field activities, the location of the former Mound Street Building is underlain by rock, concrete, bricks and other debris. On the vacant property east of the site, native silt material was encountered to a depth of 27 feet (Reference 25). The depth to bedrock is estimated to be from 20 to 30 feet (Reference 3). The shallowest aquitard in the area is the Maquoketa Shale at the top of the Ordovician System (Reference 21). The depth to groundwater is generally approximately two feet above the Mississippi River and is estimated at 20 feet (Reference 3). Groundwater movement is toward the river, to the east and southeast of the site (References 21 and 22). The groundwater depth was measured at 25 feet below the ground surface during the field activities for this SSI.

The site is essentially flat, with a gentle slope to the east and south. A 500-year concrete flood wall was constructed by the Corps of Engineers and separates the site from the Mississippi River (Reference 23). The runoff from the site is collected in the storm sewer. The storm sewer is connected to the sanitary sewer system, with the wastewater flowing to the Bissle Point Treatment Plant located approximately 2.5 miles upstream (Reference 3).

The site has no structures, fencing, or other obstructions prohibiting access to the site.

References: 3, 21, 22, 23, 25

Hazardous Waste Quantity (HWQ) Calculation: SI Tables 1 and 2 (see HRS Tables 2-5, 2-6, and 5-2).

Single-source for Coal Tar Waste:

Coal Tar Waste potentially disposed of on-site = 223,680,000 gallons

From SI Table 1, Tier C-Volume, HWQ = 10,000 for Coal Tar Wastes

Single-source for PCB waste:

The quantity of PCB wastes is unknown. Therefore, for an unallocated source, based on Section 2.4.2.2 of the Federal Register dated December 14, 1990 and SI Table 1, The HWQ is assigned a default value of 10 for PCB wastes.

Single-source for Oil waste:

The quantity of PCB wastes is unknown. Therefore, for an unallocated source, based on Section 2.4.2.2 of the Federal Register dated December 14, 1990 and SI Table 1, The HWQ is assigned a default value of 10 for oil wastes.

Total Site Waste Quantity is 10,000 (Coal Tar) + 10 (PCB) + 10 (Oil) = 10,020

From SI Table 2, for Total Site WQ of 10,020, the HWQ is 10,000.

Attach additional pages, if necessary

HWQ = 10,000

References: 3

SI TABLE 1: HAZARDOUS WASTE QUANTITY (HWQ) SCORES FOR SINGLE SOURCE SITES AND FORMULAS FOR MULTIPLE SOURCE SITES

		Single Source Sites (assigned HWQ scores)	
(Column 1) TIER	(Column 2) Source Type	(Column 3) HWQ = 10	(Column 4) HWQ = 100
A Hazardous Constituent Quantity	N/A	HWQ = 1 if Hazardous Constituent Quantity data are complete HWQ = 10 if Hazardous Constituent Quantity data are not complete	>100 to 10,000 lbs
B Hazardous Wastestream Quantity	N/A	≤ 500,000 lbs	>500,000 to 50 million lbs
C Volume	Landfill	≤ 6.75 million ft ³ ≤ 250,000 yd ³	> 6.75 million to 675 million ft ³ > 250,000 to 25 million yd ³
	Surface Impoundment	≤ 6,750 ft ³ ≤ 250 yd ³	> 6,750 to 675,000 ft ³ > 250 to 25,000 yd ³
	Drums	≤ 1,000 drums	> 1,000 to 100,000 drums
	Tanks and Non-drum Containers	≤ 50,000 gallons	> 50,000 to 5 million gallons
	Contaminated Soil	≤ 6.75 million ft ³ ≤ 250,000 yd ³	> 6.75 million to 675 million ft ³ > 250,000 to 25 million yd ³
	Pile	≤ 6,750 ft ³ ≤ 250 yd ³	> 6,750 to 675,000 ft ³ > 250 to 25,000 yd ³
	Other	≤ 6,750 ft ³ ≤ 250 yd ³	> 6,750 to 675,000 ft ³ > 250 to 25,000 yd ³
D Area	Landfill	≤ 340,000 ft ² ≤ 7.8 acres	> 340,000 to 34 million ft ² > 7.8 to 780 acres
	Surface Impoundment	≤ 1,300 ft ² ≤ 0.029 acres	> 1,300 to 130,000 ft ² > 0.029 to 2.9 acres
	Contaminated Soil	≤ 3.4 million ft ² ≤ 78 acres	> 3.4 million to 340 million ft ² > 78 to 7,800 acres
	Pile	≤ 1,300 ft ² ≤ 0.029 acres	> 1,300 to 130,000 ft ² > 0.029 to 2.9 acres
	Land Treatment	≤ 27,000 ft ² ≤ 0.62 acres	> 27,000 to 2.7 million ft ² > 0.62 to 62 acres

I TABLE 1 (CONTINUED)

Single Source Sites (assigned HWQ scores)		Multiple Source Sites		
(Column 5) HWQ = 10,000	(Column 6) HWQ = 1,000,000	(Column 7) Divisors for Assigning Source WQ Value	(Column 2) Source Type	(Column 1) TIER
> 10,000 to 1 million lbs	> 1 million lbs	lbs ÷ 1	N/A	A Hazardous Constituent Quantity
> 50 million to 5 billion lbs	> 5 billion lbs	lbs ÷ 5,000	N/A	B Hazardous Wastestream Quantity
> 675 million to 67.5 billion ft ³ > 25 million to 2.5 billion yd ³	> 67.5 billion ft ³ > 2.5 billion yd ³	ft ³ ÷ 67,500 yd ³ ÷ 2,500	Landfill	C Volume
> 675,000 to 67.5 million ft ³ > 25,000 to 2.5 million yd ³	> 67.5 million ft ³ > 2.5 million yd ³	ft ³ ÷ 67.5 yd ³ ÷ 2.5	Surface Impoundment	
> 100,000 to 10 million drums	> 10 million drums	drums ÷ 10	Drums	
> 5 million to 500 million gal.	> 500 million gal.	gallons ÷ 500	Tanks and Non- drum containers	
> 675 million to 67.5 million ft ³ > 25 million to 2.5 billion yd ³	> 67.5 billion ft ³ > 2.5 billion yd ³	ft ³ ÷ 67,500 yd ³ ÷ 2,500	Contaminated Soil	
> 675,000 to 67.5 million ft ³ > 25,000 to 2.5 million yd ³	> 67.5 million ft ³ > 2.5 million yd ³	ft ³ ÷ 67.5 yd ³ ÷ 2.5	Pile	
> 675,000 to 67.5 million yd ³ > 25,000 to 2.5 million yd ³	> 67.5 million ft ³ > 2.5 million yd ³	ft ³ ÷ 67.5 yd ³ ÷ 2.5	Other	
> 34 million to 3.4 billion ft ² > 780 to 78,000 acres	> 3.4 billion ft ² > 78,000 acres	ft ² ÷ 3,400 acres ÷ 0.078	Landfill	D Area
> 130,000 to 13 million ft ² > 2.9 to 290 acres	> 13 million ft ² > 290 acres	ft ² ÷ 13 acres ÷ 0.00029	Surface Impoundment	
> 340 million to 34 billion ft ² > 7,800 to 780,000 acres	> 34 billion ft ² > 780,000 acres	ft ² ÷ 34,000 acres ÷ 0.78	Contaminated Soil	
> 130,000 to 13 million ft ² > 2.9 to 290 acres	> 13 million ft ² > 290 acres	ft ² ÷ 13 acres ÷ 0.00029	Pile	
> 2.7 million to 270 million ft ² > 62 to 6,200 acres	> 270 million ft ² > 6,200 acres	ft ² ÷ 270 acres ÷ 0.0062	Land Treatment	

HAZARDOUS WASTE QUANTITY (HWQ) CALCULATION

For each migration pathway, evaluate HWQ associated with sources that are available (i.e., incompletely contained) to migrate to that pathway. (Note: If *Actual Contamination Targets* exist for groundwater, surface water, or air migration pathways, assign the calculated HWQ score or 100, whichever is greater, as the HWQ score for that pathway). For each source, evaluate HWQ for one or more of the four tiers (SI Table 1, HRS Table 2-5) for which data exist: constituent quantity, wastestream quantity, source volume, and source area. Select the tier that gives the highest value as the source HWQ. Select the source volume HWQ rather than source area HWQ if data for both tiers are available.

Column 1 of SI table 1 indicates the quantity tier. Column 2 lists source types for the four tiers. Columns 3, 4, 5, and 6 provide ranges of waste amount for sites with only one source, corresponding to HWQ scores at the tops of the columns. Column 7 provides formulas to obtain source waste quantity values at sites with multiple sources.

1. Identify each source type.
2. Examine all waste quantity data available for each source. Record constituent quantity and wastestream mass or volume. Record dimensions of each source.
3. Convert source measurements to appropriate units for each tier to be evaluated.
4. For each source, use the formulas in the last column of SI Table 1 to determine the waste quantity value for each tier that can be evaluated. Use the waste quantity value obtained from the highest tier as the quantity value for the source.
5. Sum the values assigned to each source to determine the total site waste quantity.
6. Assign HWQ score from SI Table 2 (HRS Table 2-6).

Note these exceptions to evaluate soil exposure pathway HWQ (see HRS Table 5-2):

- The divisor for the area (square feet) of a landfill is 34,000.
- The divisor for the area (square feet) of a pile is 34.
- Wet surface impoundments and tanks and non-drum containers are the only sources for which volume measurements are evaluated for the soil exposure pathway.

SI TABLE 2: HWQ SCORES FOR SITES

Site WQ Total	HWQ Score
0	0
1 ^a to 100	1 ^b
> 100 to 10,000	100
> 10,000 to 1 million	10,000
> 1 million	1,000,000

^a If the WQ total is between 0 and 1, round it to 1.

^b If the hazardous constituent quantity data are not complete, assign the score of 10.

Site Name: Mound Street PCB Site

Potential Sources: 1. Unallocated PCB source
2. Coal Tar Waste
3. Unallocated Oil source

References: 3, 30, 32, 33, 35

SOURCE	HAZARDOUS SUBSTANCE	Toxicity (Col 1)	GROUNDWATER PATHWAY		SURFACE WATER PATHWAY												
					OVERLAND/FLOOD MIGRATION								GROUNDWATER TO SURFACE WATER				
			(Col 2) GW Mobility HRS Table 3-8 or SCDM*	(Col 3) Tox/Mob Value HRS Table 3-9 (C1xC2)	(Col 4) Per HRS Table 4-10 & 4- 11 or (SCDM)	(Col 5) Tox/Per Value HRS Table 4-12 (C1xC4)	(Col 6) Bioacc "Food Chain" HRS Table 4-15 or (SCDM)	(Col 7) Tox/Pers /Bioacc (C5xC6)	(Col 8) Ecotox HRS Table 4-19 or (SCDM)	(Col 9) Ecotox/Pers HRS Table 4-20 (C4xC8)	(Col 10) Eco Bioacc "Environ" or (SCDM)	(Col 11) Ecotox/Pers/ Bioacc Value HRS Table 4-21 (C9xC10)	(Col 12) Tox/Mob/ PersValue HRS Table 4-26 (C3xC4)	(Col 13) Tox/Mob/ Pers/Bioacc Value HRS Table 4-28 (C6xC12)	(Col 14) Ecotox/Mob Value (C2xC8)	(Col 15) Ecotox/Mob/ Pers Value HRS Table 4-29 (C4xC14)	(Col 16) Ecotox/Mob/ Pers/Bioacc Value HRS Table 4-30 (C10xC15)
1	PCB	10,000	1	10,000	1	10,000	50,000	5 x E8	10,000	10,000	50,000	5 x E8	10,000	5 x E8	10,000	10,000	5 x E8
2,3	benzene	100	1	100	0.4	40	5,000	2 E5	100	40	500	20,000	40	2 E5	100	40	20,000
2,3	toluene	10	1	10	0.4	4	50	200	100	40	50	2,000	4	200	100	40	2,000
2,3	ethylbenzene	10	1	10	0.4	4	50	200	100	40	50	2,000	4	200	100	40	2,000
2,3	xylene	10	1	10	0.4	4	50	200	100	40	50	2,000	4	200	100	40	2,000
2	fluoranthene	100	1	100	1	100	5,000	5 E5	10,000	10,000	500	5 E6	100	5 E6	10,000	10,000	5 E6
2	pyrene	100	1	100	1	100	50	5,000	10,000	10,000	50	5 E5	100	5,000	10,000	10,000	5 E5
2	naphthalene	100	1	100	0.4	40	500	20,000	1,000	400	500	2 E5	100	50,000	1,000	400	2 E5
2	benzo(k)fluor anthene	100	1	100	1	100	50,000	5 E6	**	**	50,000	**	100	5 E6	**	**	**
2	benzo(a)pyrene	10,000	1	10,000	1	10,000	50,000	5 E8	10,000	10,000	50,000	5 E8	10,000	5 E8	10,000	10,000	5 E8
2	benzo(b)fluor anthene	10,000	1	10,000	1	10,000	50,000	5 E8	**	**	50,000	**	10,000	5 E8	**	**	**
2	benzo(a)anthra cene	10,000	1	10,000	1	10,000	50,000	5 E8	10,000	10,000	50,000	5 E8	10,000	5 E8	10,000	10,000	5 E8
2	chrysene	10	1	10	1	10	500	5,000	1,000	1,000	5,000	5 E7	10	5,000	1,000	1,000	5 E7
2	anthracene	10	1	10	1	10	0.5	5	100	100	0.5	50	10	5	100	100	50
2	ideno(123-cd) pyrene	1,000	1	1,000	1	1,000	50,000	5 E7	**	**	50,000	**	1,000	5 E7	**	**	**
2	phenanthrene	**	1	**	1	**	50	**	10,000	10,000	5,000	5 E8	**	**	10,000	10,000	5 E8
2	acenaphthalene	**	1	**	0.4	**	50	**	**	**	50	**	**	**	**	**	**
2	benzo(ghi)per ylene	**	1	**	1	**	50,000	**	**	**	50,000	**	**	**	**	**	**

SOURCE	HAZARDOUS SUBSTANCE	(Col 1) Toxicity	GROUNDWATER PATHWAY		SURFACE WATER PATHWAY												
			(Col 2) GW Mobility HRS Table 3-8 or SCDM*	(Col 3) Tox/Mob Value HRS Table 3-9 (C1xC2)	OVERLAND/FLOOD MIGRATION								GROUNDWATER TO SURFACE WATER				
					(Col 4) Per HRS Table 4-10 & 4- 11 or (SCDM)	(Col 5) Tox/Per Value HRS Table 4-12 (C1xC4)	(Col 6) Bioacc "Food Chain" HRS Table 4-15 or (SCDM)	(Col 7) Tox/Pers /Bioacc (C5xC6)	(Col 8) Ecotox HRS Table 4-19 or (SCDM)	(Col 9) Ecotox/Pers HRS Table 4-20 (C4xC8)	(Col 10) Eco Bioacc "Environ" or (SCDM)	(Col 11) Ecotox/Pers/ Bioacc Value HRS Table 4-21 (C9xC10)	(Col 12) Tox/Mob/ Pers Value HRS Table 4-26 (C3xC4)	(Col 13) Tox/Mob/ Pers/Bioacc Value HRS Table 4-28 (C6xC12)	(Col 14) Ecotox/Mob Value (C2xC8)	(Col 15) Ecotox/Mob/ Pers Value HRS Table 4-29 (C4xC14)	(Col 16) Ecotox/Mob/ Pers/Bioacc Value HRS Table 4-30 (C10xC15)
2	2-methyl naphthalene	**	1	**	0.4	**	5,000	**	1,000	400	5,000	2 E6	**	**	1,000	400	2 E6
2	fluorene	100	1	100	1	100	50,000	5 E6	1,000	1,000	50,000	5 E7	100	5 E6	1,000	1,000	5 E7
2	bis(2- ethylhexyl) phthalate	100	1	100	1	100	5,000	5 E5	1,000	1,000	5,000	5 E6	100	5 E5	1,000	1,000	5 E6
2	acenaphthalene	10	1	10	0.4	4	500	2,000	10,000	4,000	500	2 E6	4	2,000	10,000	4,000	2 E6
2	cyanide	100	1	100	0.4	40	0.5	20	1,000	400	0.5	200	40	20	1,000	400	200

*Superfund Chemical Data Matrix, June 1994.

** = No Calculated Value

Groundwater Observed Release Substances Summary Table

On SI Table 4, list the hazardous substances associated with the site detected in groundwater samples for that aquifer. Include only those substances directly observed or with concentrations significantly greater than background. Obtain toxicity values from the Superfund Chemical Data Matrix (SCDM). Assign mobility a value of 1 for all observed release substances regardless of the aquifer being evaluated. For each substance, multiply the toxicity by the mobility to obtain the toxicity/mobility factor value; enter the highest toxicity/mobility value for the aquifer in the space provided.

Groundwater Actual Contamination Targets Summary Table

If there is an observed release at a drinking water well, enter each hazardous substance meeting the requirements for the observed release by well and sample ID on SI Table 5 and record the detected concentration. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals 100%, evaluate the population using the well as a Level I target. If these percentages are less than 100% or all are N/A, evaluate the population using the well as a Level II target for that aquifer.

SI TABLE 4: GROUND WATER OBSERVED RELEASE SUBSTANCES (BY AQUIFER)

Sample ID	Hazardous Substance	Background Concentration	Toxicity/Mobility	References
DC1CY-002	benzene	< 6 ug/L	100	30, 32
DC1CY-002	acenaphthene	< 1.1 ug/L	10	30, 32
DC1CY-002	fluorene	< 5 ug/L	100	30, 32
DC1CY-002	phenanthrene	< 1.1 ug/L	N/A	30, 32
DC1CY-002	bis (2-ethylhexyl) phthalate	< 10 ug/L	100	30, 32
DC1CY-002	cyanide	< 17 ug/L	100	3, 32
Highest Toxicity/Mobility			100	

SI TABLE 5: GROUND WATER ACTUAL CONTAMINATION TARGETS

Well ID: _____ Level I _____ Level II _____ Population Served _____ References _____

Sample ID	Hazardous Substance	Conc. (ug/L)	Benchmark Concentration (MCL or MCLG)	% of Benchmark	Cancer Risk	% of Cancer Risk Conc.	RfD	% of RfD
								References
	NO DRINKING WATER TARGETS							
	No Drinking Water Targets							
Highest Percent					Sum of Percents		Sum of Percents	

GROUNDWATER PATHWAY

GROUNDWATER USE DESCRIPTION

Describe Groundwater Use within 4 miles of the site: Describe generalized stratigraphy, aquifers, municipal and private wells

The Mound Street PCB Site is located on a "narrow strip of alluvium" between the Mississippi River and limestone bedrock located in the area. Fill material, estimated at 15 to 18 feet thick, overlays the alluvium at the site (Reference 10). Stratified river alluvium consists of silt, clay, and silty clay which becomes coarser with depth and includes gravel lenses. The alluvium can be up to 80 feet thick, with clay and silty clay at shallow depths and silty sand and sand in the deeper portions (Reference 21). Prior to construction of the concrete flood wall, several borings were conducted in the vicinity of the site (Reference 26). Cinders, concrete, rock, and bricks may be up to 26 feet thick, with silt, clay or a mixture of silt and clay underlying the cinders to the limestone bedrock (Reference 26). No confining layer is known to exist between the alluvium and bedrock. Also, no aquifer discontinuity exists within the 4-mile target distance limit (Reference 21). Based on Geoprobe borings conducted during the April, 1996, field activities, the location of the former Mound Street Building is underlain by rock, concrete, bricks and other debris. On the vacant property east of the site, native silt material was encountered to a depth of 27 feet (Reference 25). The bedrock consists of upper Mississippian limestone formations which are, in descending order, Ste. Genevieve Limestone, St. Louis Limestone, shaley limestones of the Salem Formation and Warsaw Formation, Burlington-Keokuk Limestone, and Fern Glen Formation (References 3 and 21). These formations are approximately 600 feet thick (Reference 3). The depth to bedrock is estimated to be from 20 to 30 feet (Reference 3). The shallowest aquitard in the area is the Maquoketa Shale at the top of the Ordovician System (Reference 21). The depth to groundwater is generally approximately two feet above the Mississippi River and is estimated at 20 feet (Reference 3). Groundwater movement is toward the river, to the east and southeast of the site (References 21 and 22). The groundwater depth was measured at 25 feet below the ground surface during the field activities for this SSI. Sinkholes and caves are found in the Mississippian bedrock within the target area. The karst aquifer probably does not directly underlie the site and probably does not affect contaminant transport from the site (Reference 22).

References: 3, 10, 21, 22, 25, 26

Show Calculations of Groundwater Drinking Water Populations for each aquifer: Provide apportionment calculations for blended supply systems.

County average number of persons per household: 2.57 Reference: 28

The City of St. Louis has an average of 2.34 persons per household (Reference 28).

Groundwater within a 4-mile radius of the site is not used for drinking water (References 4, 17 and 21). Irrigation of agricultural crops is possibly conducted via groundwater. The site is not located within a wellhead protection area (Reference 21).

The Mississippi River is located approximately 100 feet east of the sampled monitoring wells and the groundwater level fluctuates with the river level (Reference 3, 21 and 22). Therefore, the groundwater to surface water migration route is a potential exposure pathway.

References: 3, 4, 17, 21, 22, 28

GROUNDWATER PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE	Score	Data Type	Refs
1. OBSERVED RELEASE: If sampling data or direct observation support a release to the aquifer, assign a score of 550. Record observed release substances on SI Table 4.	550	H	3, 30
2. POTENTIAL TO RELEASE: Depth to aquifer: <u>20</u> feet. If sampling data do not support a release to the aquifer, and the site is in karst terrain or the depth to aquifer is 70 feet or less, assign a score of 500; otherwise, assign a score of 340. Optionally, evaluate potential to release according to HRS Section 3.			
LR =	550		

TARGETS

<p>Are any well part of a blended system? Yes___ No___ If yes, attach a page to show apportionment calculations.</p> <p>3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates that any target drinking water well for the aquifer has been exposed to a hazardous substance from the site, evaluate the factor score for the number of people served (SI Table 5).</p> <p>Level I: _____ people x 10 = _____ Level II: _____ people x 1 = _____ Total = _____</p>	0	H	3,4,15,17, 21
4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water wells for the aquifer or overlying aquifers that are not exposed to a hazardous substance from the site; record the population for each distance category in SI Table 6a or 6b. Sum the population values and multiply by 0.1.	0	H	3,4,15,17,21
5. NEAREST WELL: Assign a score of 50 for any Level I Actual Contamination Targets for the aquifer or overlying aquifer. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Targets exist, assign the Nearest Well score from SI Table 6a or 6b. If no drinking water wells exist within 4 miles, assign 0.	0	H	3,4,15,21,34
6. WELLHEAD PROTECTION AREA (WHPA): In any source lies within or above a WHPA for the aquifer, or if a groundwater observed release has occurred within a WHPA, assign a score of 20; assign 5 if neither condition applies but a WHPA is within 4 miles; otherwise assign 0.	0	H	21
<p>7. RESOURCES: Assign a score of 5 if one or more groundwater resources applies; assign 0 if none applies:</p> <ul style="list-style-type: none"> ● Irrigation (5 acre minimum) of commercial food crops or commercial forage crops. ● Watering of commercial livestock. ● Ingredient in commercial food preparation. ● Supply for commercial aquaculture. ● Supply for a major or designated water recreation area, excluding drinking water use. 	5	H	21
Sum of Targets T =	5		

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER TARGET POPULATIONS

SI Table 6a: Other Than Karst aquifers

Distance from site	Population	Nearest Well (Choose highest)	Population served by Wells within Distance Category												Population Value	References
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1000	1001 to 3,000	3001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000		
0 to ¼ mile		20	4	7	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455		
>¼ to ½ mile		18	2	1	33	102	324	1,013	3,233	10,122	32,325	101,213	323,243	1,012,122		
½ to 1 mile		9	1	3	17	52	167	523	1,669	5,224	16,684	52,239	166,835	522,385		
>1 to 2 miles		5	0.7	3	10	30	94	294	939	2,939	9,385	29,384	93,845	293,842		
>2 to 3 miles		3	0.5	2	7	21	68	212	678	2,122	6,778	21,222	67,777	212,219		
>3 to 4 miles		2	0.3	1	4	13	42	131	417	1,306	4,171	13,060	41,709	130,596		
Nearest Well=															Sum =	

SI TABLE 6 (From HRS TABLE 3-12): VALUES FOR POTENTIAL CONTAMINATION GROUND WATER TARGET POPULATIONS

SI Table 6b: Karst aquifers

Distance from site	Population	Nearest Well (Choose highest)	Population served by Wells within Distance Category												Population Value	References
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1000	1001 to 3,000	3001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000		
0 to ¼ mile		20	4	7	53	164	522	633	5,214	6,325	52,137	163,246	521,360	1,632,455		
>¼ to ½ mile		20	2	1	33	102	324	1,013	3,233	10,122	32,325	101,213	323,243	1,012,122		
½ to 1 mile		20	2	3	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
>1 to 2 miles		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
>2 to 3 miles		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
>3 to 4 miles		20	2	9	26	82	261	817	2,607	8,163	26,068	81,623	260,680	816,227		
Nearest															Sum =	

GROUNDWATER PATHWAY WORKSHEET (continued)

WASTE CHARACTERISTICS		Score	Data Type	Does Not Apply																						
8.	If any Actual Contamination Targets exist for the aquifer or overlying aquifer, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if no Actual Contamination Targets exist, assign the hazardous waste quantity score calculated for sources available to migrate to groundwater	10,000	H																							
9.	Assign the highest groundwater toxicity/mobility value from SI Tables 3 or 4	10,000	H																							
10.	Multiply the groundwater toxicity/mobility and the hazardous waste quantity scores. Assign the Waste Characteristic score from the table below: (from HRS Table 2-7)	100																								
<table border="1"> <thead> <tr> <th>Product</th> <th>WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td>0</td></tr> <tr><td>> 0 to < 10</td><td>1</td></tr> <tr><td>10 to < 100</td><td>2</td></tr> <tr><td>100 to < 1,000</td><td>3</td></tr> <tr><td>1,000 to < 10,000</td><td>6</td></tr> <tr><td>10,000 to < 1E+05</td><td>10</td></tr> <tr><td>1E+05 to < 1E+06</td><td>18</td></tr> <tr><td>1E+06 to < 1E+07</td><td>32</td></tr> <tr><td>1E+07 to < 1E+08</td><td>56</td></tr> <tr><td>1E+08 or greater</td><td>100</td></tr> </tbody> </table>					Product	WC Score	0	0	> 0 to < 10	1	10 to < 100	2	100 to < 1,000	3	1,000 to < 10,000	6	10,000 to < 1E+05	10	1E+05 to < 1E+06	18	1E+06 to < 1E+07	32	1E+07 to < 1E+08	56	1E+08 or greater	100
Product	WC Score																									
0	0																									
> 0 to < 10	1																									
10 to < 100	2																									
100 to < 1,000	3																									
1,000 to < 10,000	6																									
10,000 to < 1E+05	10																									
1E+05 to < 1E+06	18																									
1E+06 to < 1E+07	32																									
1E+07 to < 1E+08	56																									
1E+08 or greater	100																									
WC =		100																								

Multiply LR by T and by WC. Divide the product by 82,500 to obtain the groundwater pathway score for each aquifer. Select the highest aquifer score. If the pathway score is greater than 100, assign 100.

3.33
(Maximum of 100)

GROUNDWATER PATHWAY SCORE:

$$\frac{LR \times T \times WC}{82,500}$$

$$\frac{550 \times 5 \times 100}{82,500} = 3.33$$

SURFACE WATER PATHWAY

Sketch of the Surface Water Migration Route: Label all surface water bodies. Include runoff and drainage direction, probable point of entry, and 15-mile target distance limit. Mark sample locations, intakes, fisheries, and sensitive environments. Indicate flow directions, tidal influences, and rate.



References: 14, 15, 23, 25, 34

SURFACE WATER PATHWAY

Surface Water Observed Release Substances Summary Table

On SI Table 7, list the hazardous substances detected in surface water samples for the watershed, which can be attributed to the site. Include only those substances in observed releases (direct observation) or with concentration levels significantly above background levels. Obtain toxicity, persistence, bioaccumulation potential, and ecotoxicity values from SCDM. Enter the highest toxicity/persistence, toxicity/persistence/bioaccumulation, and ecotoxicity/persistence/ecobioaccumulation values in the spaces provided.

- TP = Toxicity x Persistence
- TPB = TP x Bioaccumulation
- ETPB = EP x Bioaccumulation (EP = Ecotoxicity x Persistence)

Drinking Water Actual Contamination Targets Summary Table

For an observed release at or beyond a drinking water intake, on SI Table 8 enter each hazardous substance by sample ID and the detected concentration. For surface water sediment samples detecting a hazardous substance at or beyond an intake, evaluate the intake as Level II contamination. Obtain benchmark, cancer risk, and reference dose concentrations for each substance from SCDM. For MCL and MCLG benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages of the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate the population served by the intake as a Level I target. If the percentages are less than 100% or all N/A, evaluate the population served by the intake as a Level II target.

SI TABLE 7:

SURFACE WATER OBSERVED RELEASE SUBSTANCES

Sample ID	Hazardous Substance	Backgrd. Conc.	Toxicity/ Persistence	Toxicity/ persist./ Bioaccum	Ecotoxicity/ Persis/ Ecobioaccum	References
DSX44-402/403	pyrene	< 0.53 mg/kg	100	5,000	5 E5	3,32
DSX44-402/403	benzo(k)fluoranthene	< 0.4 mg/kg	100	5 E6	N/A	3,32
DSX44-402/403	benzo(a)pyrene	< 0.4 mg/kg	10,000	5 E8	5 E8	3,32
DSX44-402/403	benzo(a)anthracene	< 0.4 mg/kg	1,000	5 E7	5 E8	3,32
DSX44-402/403	benzo(g,h,i)perylene	< 0.4 mg/kg	N/A	N/A	N/A	3,32
DSX44-402/403	phenanthrene	< 0.4 mg/kg	N/A	N/A	5 E7	3,32
DSX44-402/403	fluoranthene	< 0.52 mg/kg	100	5 E5	5 E6	3,32
DSX44-402/403	di-n-octyl phthalate	< 0.4 mg/kg	N/A	N/A	N/A	3,32
DSX44-402/403	cyanide	< 24 mg/kg	40	20	200	3,32
Highest Values			10,000	5 E8	5 E8	

SI TABLE 8: SURFACE WATER DRINKING WATER ACTUAL CONTAMINATION TARGETS

Intake ID _____ Sample Type _____ Level I _____ Level II _____ Population Served _____ References _____

Sample ID	Hazardous Substance	Conc. (u g/L)	Benchmark Conc. (MCL or MCLG)	% of Benchmark	Cancer Risk	% of Cancer Risk Conc.	RfD	% of RfD
NO TARGETS								
Highest percent					Sum of Percents		Sum of Percents	

- This page was intentionally left blank -

SURFACE WATER PATHWAY

LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET

LIKELIHOOD OF RELEASE - OVERLAND/FLOOD MIGRATION

LIKELIHOOD OF RELEASE - OVERLAND/FLOOD MIGRATION		Score	Data Type	Refs												
1.	OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7.	550	H	3,4												
2.	POTENTIAL TO RELEASE: Distance to surface water: <u>300</u> feet. If sampling data do not support a release to surface water in the watershed, use the table below to assign a score from the table below based on distance to surface water and flood potential. <table border="1"><tr><td>Distance to surface water body <2500 feet</td><td>500</td></tr><tr><td>Distance to surface water body >2500 feet, and</td><td></td></tr><tr><td> Site in annual or 10-yr floodplain</td><td>500</td></tr><tr><td> Site in 100-yr floodplain</td><td>400</td></tr><tr><td> Site in 500-yr floodplain</td><td>300</td></tr><tr><td> Site outside 500-yr floodplain</td><td>100</td></tr></table> Optionally, evaluate potential to release according to HRS Section 4.1.2.1.2.	Distance to surface water body <2500 feet	500	Distance to surface water body >2500 feet, and		Site in annual or 10-yr floodplain	500	Site in 100-yr floodplain	400	Site in 500-yr floodplain	300	Site outside 500-yr floodplain	100			
Distance to surface water body <2500 feet	500															
Distance to surface water body >2500 feet, and																
Site in annual or 10-yr floodplain	500															
Site in 100-yr floodplain	400															
Site in 500-yr floodplain	300															
Site outside 500-yr floodplain	100															

LR =

550

LIKELIHOOD OF RELEASE GROUNDWATER TO SURFACE WATER MIGRATION

		Score	Data Type	Refs
1.	OBSERVED RELEASE: If sampling data or direct observation support a release to surface water in the watershed, assign a score of 550. Record observed release substances on SI Table 7. NOTE: Evaluate groundwater to surface water migration only for a surface water body that meets all of the following conditions: <ol style="list-style-type: none"> 1) A portion of the surface water is within 1 mile of site sources having a containment factor greater than 0. 2) No aquifer discontinuity is established between the source and the above portion of the surface water body. 3) The top of the uppermost aquifer is at or above the bottom of the surface water. Elevation of top of uppermost aquifer: <u>20-25 feet below ground surface</u> Elevation of bottom of surface water body: <u>> 20-25 feet below ground surface</u>	550	H	21,22
2.	POTENTIAL TO RELEASE: Use the groundwater potential to release. Optionally, evaluate surface water potential to release according to HRS Section 3.1.2.			

LR =

550

SURFACE WATER PATHWAY

LIKELIHOOD OF RELEASE AND DRINKING WATER THREAT WORKSHEET

(CONTINUED)

DRINKING WATER THREAT TARGETS

				Score	Data Type	Refs
Record the water body type, flow, and number of people served by each drinking water intake within the target distance limit in the watershed. If there is no drinking water intake within the target distance limit, assign 0 to factors 3, 4, and 5.						
Intake Name	Water Body Type	Flow	People Served			
IL-American Water Company	Very Large River	>100,000	180,000			
				0	H	17,19 21
Are any intake part of a blended system? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> If yes, attach a page to show apportionment calculations.						
3. ACTUAL CONTAMINATION TARGETS: If analytical evidence indicates a drinking water intake has been exposed to a hazardous substance from the site, list the intake name and evaluate the factor score for the drinking water population (SI Table 8). Level I: _____ people x 10 = _____ Level II: _____ people x 1 = _____ Total = _____						
4. POTENTIAL CONTAMINATION TARGETS: Determine the number of people served by drinking water intakes for the watershed that have not been exposed to a hazardous substance from the site. Assign the population values from SI Table 9. Sum the values and multiply by 0.1.				0.2	H	3,15
5. NEAREST INTAKE: Assign a score of 50 for any Level I Actual Contamination Drinking Water Target for the watershed. Assign a score of 45 if there are Level II targets for the watershed, but no Level I targets. If no Actual Contamination Drinking Water Targets exist, assign a score for the intake nearest the PPE from SI Table 9. If no drinking water intakes exist, assign 0.				0	H	15,17
6. RESOURCES: Assign a score of 5 if one or more surface water resources applies; assign 0 if none applies: • Irrigation (5 acre minimum) of commercial food crops or commercial forage crops. • Watering of commercial livestock. • Ingredient in commercial food preparation. • Major or designated water recreation area, excluding drinking water use.				5	H	21,34
SUM OF TARGETS				T =	5.2	

SI TABLE 9 (From HRS TABLE 4-14): DILUTION-WEIGHTED POPULATION VALUES FOR POTENTIAL CONTAMINATION FOR SURFACE WATER MIGRATION PATHWAY

Type of Surface Water Body	Pop.	Nearest Intake	Nuner of People									Population Value
			0	1 to 10	11 to	31 to 100	101 to 300	301 to 1000	1001 to 3,000	3001 to 10,000	10,001 to 30,000	
Minimal Stream (<10 cfs)		20	0	4	17	53	164	522	1,633	5,214	16,325	
Small to moderate stream (10 to 100 cfs)		2	0	0.4	2	5	16	52	163	521	1,633	
Moderate to large stream (100 - 1,000 cfs)		0	0	0.04	0.2	0.5	2	5	16	52	163	
Large Stream to river (>1,000 to 10,000 cfs)		0	0	0.004	0.02	0.05	0.2	0.5	2	5	16	
Large River (>10,000 to 100,000 cfs)		0	0	0	0.002	0.005	0.02	0.05	0.02	0.05	16	
Very Large River (>100,000 cfs)		0	0	0	0	0.001	0.002	0.005	0.02	0.05	0.02	
Shallow ocean zone or Great Lake (Depth < 20 feet)		0	0	0	0.002	0.005	0.02	0.05	0.2	0.5	2	
Moderate ocean zone or Great Lake (Depth 20 to 200 feet)		0	0	0	0	0.001	0.002	0.005	0.02	0.05	0.2	
Deep ocean zone or Great Lake (Depth > 200 feet)		0	0	0	0	0	0.001	0.003	0.008	0.03	0.08	
3-mile mixing zone in quiet flowing river (≥ 10 cfs)		10	0	2	9	26	82	261	817	2,607	8,163	
Nearest Intake =			Sum =									

References _____

Type of Surface Water Body	Pop.	Nearest Intake						Population Value
			30,001 to 100,00	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000	3,000,001 to 10,000,000	
Minimal Stream (<10 cfs)		20	52,137	163,246	521,360	1,632,455	5,213,590	
Small to moderate stream (10 to 100 cfs)		2	5,214	16,235	52,136	163,245	521,359	
Moderate to large stream (100 - 1,000 cfs)		0	521	1,633	5,214	16,325	52,136	
Large Stream to river (>1,000 to 10,000 cfs)		0	52	163	521	1,632	5,214	
Large River (>10,000 to 100,000 cfs)		0	5	16	52	163	521	
Very Large River (>100,000 cfs)	180,000	0	0.5	2	5	16	52	2
Shallow ocean zone or Great Lake (Depth < 20 feet)		0	5	16	52	163	521	
Moderate ocean zone or Great Lake (Depth 20 to 200 feet)		0	0.5	2	5	16	52	
Deep ocean zone or Great Lake (Depth > 200 feet)		0	0.3	1	3	8	26	
3-mile mixing zone in quiet flowing river (≥ 10 cfs)		10	26,068	81,623	260,680	816,227	2,606,795	
Nearest Intake =		0	Sum =					2

References: 15, 17, 21

SURFACE WATER PATHWAY

Human Food Chain Actual Contamination Targets Summary Table

On SI Table 10, list the hazardous substances detected in sediment, aqueous, sessile benthic organism tissue, or fish samples (taken from fish caught within the boundaries of the observed release) by sample ID and concentration. Evaluate fisheries within the boundaries of observed releases detected by sediment or aqueous samples as Level II, if at least one observed release substance has a bioaccumulation potential factor value of 500 or greater (see SI Table 7). Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For FDAAL benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate this portion of the fishery as subject to Level I concentrations. If the percentages are less than 100% or all are N/A, evaluate the fishery as a Level II target.

Sensitive Environment Actual Contamination Targets Summary Table

On SI Table 11, list each hazardous substance detected in aqueous or sediment sample at or beyond wetlands or a surface water sensitive environment by sample ID. Record the concentration. If contaminated sediments or tissues are detected at or beyond a sensitive environment, evaluate the sensitive environment as Level II. Obtain benchmark concentrations from SCDM. For AWQC/AALAC benchmarks, determine the highest percentage of benchmark of the substances detected in aqueous samples. If benchmark concentrations are not available for a particular substance, enter N/A for the percentage. If the benchmark percentage equals or exceeds 100%, evaluate that part of the sensitive environment subject to Level I concentrations. If the percentage is less than 100%, or all are N/A, evaluate the sensitive environment as Level II.

SI TABLE 10: HUMAN FOOD CHAIN ACTUAL CONTAMINATION TARGETS FOR WATERSHED

Fishery ID Mississippi River Sample Type Sediment Level I _____ Level II X References 3, 15, 32

Sample ID	Hazardous Substance	Conc. (mg/kg)	Benchmark Concentration (FDAAL)	% of Benchmark	Cancer Risk Concentration	% of Cancer Risk Concentration	RfD	% of RfD
DSX44-402/403	pyrene	8	N/A	N/A	N/A	N/A	41	19.5
DSX44-402/403	benzo(k)fluoranthene	3.1	N/A	N/A	4.3 E-3	72093	N/A	N/A
DSX44-402/403	benzo(a)pyrene	5.6	N/A	N/A	4.3 E-4	1302336	N/A	N/A
DSX44-402/403	benzo(a)anthracene	4.2	N/A	N/A	4.3 E-3	97674	N/A	N/A
DSX44-402/403	benzo(g,h,i)perylene	4.2	N/A	N/A	N/A	N/A	N/A	N/A
DSX44-402/403	phenanthrene	4.4	N/A	N/A	N/A	N/A	N/A	N/A
DSX44-402/403	fluoranthene	5.1	N/A	N/A	N/A	N/A	54	9.4
DSX44-402/403	di-n-octyl phthalate	4.9	N/A	N/A	N/A	N/A	N/A	N/A
DSX44-402/403	cyanide	1.6	N/A	N/A	N/A	N/A	27	5.9
Highest Percent				N/A	Sum of Percents	1472093	Sum of Percents	34.8

SI TABLE 11 : SENSITIVE ENVIRONMENT ACTUAL CONTAMINATION TARGETS FOR WATERSHED

Environmental ID Mississippi River Sample Type Direct Observation Level I _____ Level II X References 3

Sample ID	Hazardous Substance	Conc. (ug/L)	Benchmark Conc. (AWQC OR AALAC)	% of Benchmark	References
	NO CHEMICAL DATA AVAILABLE				
Highest percent					

SURFACE WATER PATHWAY (continued)

HUMAN FOOD CHAIN THREAT WORKSHEET

HUMAN FOOD CHAIN THREAT TARGETS

Data
Type Refs

Record the water body type and flow for each fishery within the target distance limit. If there is no fishery within the target distance limit, assign a score of 0 at the bottom of this page.

Fishery Name: Mississippi River Water Body: Very Large River Flow: >100,000 cfs

Species <u>paddlefish</u>	Production <u>175</u> lbs/yr
Species <u>gar</u>	Production <u>34</u> lbs/yr
Species <u>carp</u>	Production <u>960</u> lbs/yr
Species <u>sturgeon</u>	Production <u>60</u> lbs/yr
Species <u>blue catfish</u>	Production <u>801</u> lbs/yr
Species <u>channel catfish</u>	Production <u>2703</u> lbs/yr
Species <u>flathead catfish</u>	Production <u>694</u> lbs/yr
Species <u>drum</u>	Production <u>170</u> lbs/yr
Species <u>buffalo</u>	Production <u>2171</u> lbs/yr

FOOD CHAIN INDIVIDUAL

7. ACTUAL CONTAMINATION FISHERIES:

If analytical evidence indicates that a fishery has been exposed to a hazardous substance with a bioaccumulation factor greater than or equal to 500 (SI Table 10), assign a score of 50 if there is a Level I fishery. Assign 45 if there is a Level II fishery, but no Level I fishery.

8. POTENTIAL CONTAMINATION FISHERIES:

If there is a release of a substance with a bioaccumulation factor greater than or equal to 500 to a watershed containing fisheries within the target distance limit, but there are no Level I or Level II fisheries, assign a score of 20.

If there is no observed release to the watershed, assign a value for potential contamination fisheries from the table below using the lowest flow at all fisheries within the target distance limit:

Lowest Flow	FCI Value
< 10 cfs	20
10 to 100 cfs	2
> 100 cfs, coastal tidal waters, oceans, or Great Lakes	0
3-mile mixing zone in quiet flowing river	10

FCI Value =

SUM OF TARGETS

T =

45

SURFACE WATER PATHWAY (continued)

ENVIRONMENTAL THREAT WORKSHEET

When measuring length of wetlands that are located on both sides of a surface water body, sum both frontage lengths. For a sensitive environment that is more than one type, assign a value for each type.

ENVIRONMENTAL THREAT TARGETS					Score	Data Type	Refs			
Record the water body type and flow for each surface water sensitive environment within the target distance (see SI Table 12). If there is no sensitive environment within the target distance limit, assign a score of 0 at the bottom of the page.					75	H	2,3, 15			
Environment Name	Water Body Type	Flow cfs								
Mississippi River	Very Large River	>100,000								
9. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: If sampling data or direct observation indicate any sensitive environment has been exposed to a hazardous substance from the site, record this information on SI Table 11, and assign a factor value for the environment (SI Tables 13 and 14).					75	H	2,3, 15			
Environment Name	Environment Type and Value (SI Tables 13 and 14)	Multiplier (10 for Level I, 1 for Level II)	Product							
Miss. River	75 (habitat known to be used by ...)	x 1	= 75							
		x	=							
		x	=							
		x	=							
Sum =										
10. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS:								2.25 E-3	H	1,3, 21, 34
Flow (cfs)	Dilution Weight (SI Table 12)	Environment Type and Value (SI Tables 13 & 14)	Potential Contamination	Product						
100000	0.00001	x 25 (wetlands - 0.7 miles in IL)	x 0.1	=2.5 E-4						
100000	0.00001	x 100 (Jefferson Nat'l Exp. Mem. Park)	x 0.1	=1 E-3						
100000	0.00001	x 100 (Jefferson Barracks Park)	x 0.1	=1 E-3						
Sum =										
T =					75					

**SI TABLE 12 (HRS TABLE 4-13):
SURFACE WATER DILUTION WEIGHTS**

TYPE OF SURFACE WATER BODY		Assigned Dilution Weight
Description	Flow Characteristics	
Minimal stream	< 10 cfs	1
Small to moderate stream	10 to 100 cfs	0.1
Moderate to large stream	> 100 to 1,000 cfs	0.01
Large stream to river	> 1,000 to 10,000 cfs	0.001
Large river	> 10,000 to 100,000 cfs	0.0001
Very large river	> 100,000 cfs	0.00001
Coastal tidal waters	Flow not applicable, depth not applicable	0.0001
Shallow ocean zone or Great Lakes	Flow not applicable, depth less than 20 feet	0.0001
Moderate depth ocean zone or Great Lakes	Flow not applicable, depth 20 to 200 feet	0.00001
Deep ocean zone or Great Lakes	Flow not applicable, depth greater than 200 feet	0.000005
3-mile mixing zone in quiet flowing river	10 cfs or greater	0.5

SI TABLE 13 (HRS TABLE 4-23)
SURFACE WATER AND AIR SENSITIVE ENVIRONMENTS VALUES

SENSITIVE ENVIRONMENT	ASSIGNED VALUE
Critical habitat for Federal designated endangered or threatened species Marine Sanctuary National Park Designated Federal Wilderness Area Ecologically important area identified under the Coastal Zone Wilderness Act Sensitive Areas identified under the National Estuary Program or Near Coastal Water Program of the Clean Water Act Critical Areas identified under the Clean Lakes Program of the Clean Water Act (subareas in lakes or entire small lakes) National Monument (air pathway only) National Seashore Recreation Area National Lakeshore Recreation Area	100
Habitat known to be used by Federal designated or proposed endangered or threatened species National Preserve National or State Wildlife Refuge Unit of Coastal Barrier Resources System Coastal Barrier (undeveloped) Federal land designated for the protection of natural ecosystems Administratively Proposed Federal Wilderness Area Spawning areas critical for the maintenance of fish/shellfish species within a river system, bay, or estuary Migratory pathway and feeding areas critical for the maintenance of anadromous fish species within river reaches or areas in lakes or coastal tidal waters in which the fish spend extended periods of time Terrestrial areas utilized by large or dense aggregations of vertebrate animals (semi-aquatic foragers) for breeding National river reach designated as recreation	75
Habitat known to be used by State designated endangered or threatened species Habitat known to be used by a species under review as to its Federal endangered or threatened status Coastal Barrier (partially developed) Federally designated Scenic or Wild River	50
State land designated for wildlife or game management State designated Scenic or Wild River State designated Natural Area Particular areas, relatively small in size, important to maintenance of unique biotic communities	25
State designated areas for the protection of maintenance of aquatic life under the Clean Water Act	5
Wetlands See SI table 14 (Surface Water Pathway) or SI Table 23 (Air Pathway)	

SI TABLE 14 (HRS TABLE 4-24): SURFACE WATER WETLANDS FRONTAGE VALUES

TOTAL LENGTH OF WETLANDS	ASSIGNED VALUE
Less than 0.1 mile	0
0.1 to 1 mile	25
Greater than 1 to 2 miles	50
Greater than 2 to 3 miles	75
Greater than 3 to 4 miles	100
Greater than 4 to 8 miles	150
Greater than 8 to 12 miles	250
Greater than 12 to 16 miles	350
Greater than 16 to 20 miles	450
Greater than 20 miles	500

- This page was intentionally left blank -

SURFACE WATER PATHWAY (concluded)

WASTE CHARACTERISTICS, THREAT, AND PATHWAY SCORE SUMMARY

WASTE CHARACTERISTICS				Score
11.	If an Actual Contamination Target (drinking water, human food chain, or environmental threat) exists for the watershed, assign the calculated hazardous waste quantity score, or a score of 100, whichever is great.			10,000
12.	Assign the highest value from SI Table 7 (observed release) or SI Table 3 (no observed release) for the hazardous substance waste characterization factors below. Multiply each by the surface water hazardous waste quantity score and determine the waste characteristics score for each threat.			WC Score (from Table)
	Substance Value	HWQ	Product	
Drinking Water Threat Toxicity/Persistence	10,000	x 10,000	= 1 E8	100
Food Chain Threat Toxicity/Persistence/ Bioaccumulation	5 E8	x 10,000	= 1 E12	1000
Environment Threat Ecotoxicity/Persistence /Ecobioaccumulation	5 E8	x 10,000	= 1 E12	1000
	Product	WC Score		
	0	0		
	> 0 to < 10	1		
	10 to < 100	2		
	100 to < 1,000	3		
	1,000 to < 10,000	6		
	10,000 to < 1E+05	10		
	1E+05 to < 1E+06	18		
	1E+06 to < 1E+07	32		
	1E+07 to < 1E+08	56		
	1E+08 to < 1E+09	100		
	1E+09 to < 1E+10	180		
	1E+10 to < 1E+11	320		
	1E+11 to < 1E+12	560		
	1E+12 or greater	1000		

SURFACE WATER PATHWAY THREAT SCORES

Threat	Likelihood of Release (LR) Score	Target (T) Score	Pathway Waste Characteristic (WC) Score (determined above)	$LR \times T \times WC$ 82,500
Drinking Water	550	5.2	100	(maximum of 100) 3.47
Human Food Chain	550	45	1000	(maximum of 100) 100
Environment	550	75	1000	(maximum of 60) 60

SURFACE WATER PATHWAY SCORE

(Drinking Water Threat + Human Food Chain Threat + Environmental Threat)

(maximum of 100) 100

SOIL EXPOSURE PATHWAY

If there is no observed contamination (e.g., groundwater plume with no known surface source), do not evaluate the soil exposure pathway. Discuss evidence for no soil exposure pathway.

Soil Exposure Resident Population Targets Summary

For each property (duplicate page 35 if necessary):

If there is an area of observed contamination on the property and within 200 feet of a residence, school, or day care center, enter on Table 15 each hazardous substance by sample ID. Record the detected concentration. Obtain cancer risk, and reference dose concentrations from SCDM. Sum the cancer risk and reference dose percentages for the substances listed. If cancer risk or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the percentage sum calculated for cancer risk or reference dose equals 100%, evaluate the residents and students as Level I. If both percentages are less than 100% or all are N/A, evaluate the targets as Level II.

SI TABLE 15: SOIL EXPOSURE RESIDENT POPULATION TARGETS

 Residence ID No Resident Population Level I Level II Population N/A

Sample ID	Hazardous Substance	Conc. (mg/kg)	Cancer Risk Concentration	% of Cancer Risk Conc	RfD	% of RfD.	Toxicity Value	References
DSX44-102	pyrene	21	N/A	N/A	2.3 E3	0.91	100	3, 32
DSX44-107	naphthalene	60	N/A	N/A	N/A	N/A	100	3, 32
DSX44-107	2-methylnaphthalene	13	N/A	N/A	N/A	N/A	N/A	3, 32
DSX44-108	acenaphthylene	2.4	N/A	N/A	N/A	N/A	N/A	3, 32
DSX44-108	acenaphthene	0.69	N/A	N/A	4.7 E3	1.5 E-2	10	3, 32
DSX44-108	fluorene	3.1	N/A	N/A	3.1 E3	0.1	100	3, 32
DSX44-108	cyanide	98	N/A	N/A	1600	6.1	100	3, 32
DSX44-109	phenanthene	2.2	N/A	N/A	N/A	N/A	N/A	3, 32
DSX44-109	anthracene	0.78	N/A	N/A	2.3 E4	3.4 E-3	10	3, 32
DSX44-109	fluoranthene	2.8	N/A	N/A	3.1 E3	0.09	100	3, 32
DSX44-109	benzo(a)anthracene	4.5	8.8 E-1	511.4	N/A	N/A	1000	3, 32
DSX44-109	chrysene	4.3	8.8 E1	4.9	N/A	N/A	10	3, 32
DSX44-109	benzo(b)fluoranthene	4.9	8.8 E-1	556.8	N/A	N/A	10,000	3, 32
DSX44-109	benzo(k)fluoranthene	3.4	8.8	38.6	N/A	N/A	100	3, 32
DSX44-109	benzo(a)pyrene	4.2	8.8 E-2	4772.7	N/A	N/A	10,000	3, 32
DSX44-109	ideno(1,2,3-cd)pyrene	2.7	8.8 E-1	306.8	N/A	N/A	1000	3, 32
DSX44-109	benzo(g,h,i)perylene	2.6	N/A	N/A	N/A	N/A	N/A	3, 32
Highest percent				4772.7	Sum of Percents	7.22		

SOIL EXPOSURE PATHWAY WORKSHEET

RESIDENT POPULATION THREAT

LIKELIHOOD OF RELEASE		Score	Data Type	Refs
1.	OBSERVED CONTAMINATION: If evidence indicates presence of observed contamination (depth of 2 feet or less), assign a score of 550; otherwise, assign a 0. Note that a likelihood of exposure score of 0 results in a soil exposure pathway score of 0.	550	H	3,32

LE =

550

TARGETS

2.	RESIDENT POPULATION: Determine the number of people occupying residences or attending school or day care on the property and within 200 feet of areas of observed contamination (HRS Section 5.1.3). Level I: _____ people x 10 = _____ Level II: _____ people x 1 = _____ Sum = _____	0	H	3,15										
3.	RESIDENT INDIVIDUAL: Assign a score of 50 if any Level I resident population exists. Assign a score of 45 if there are Level II targets but no Level I targets. If no resident population exists (i.e., no Level I or Level II targets), assign 0 (HRS Section 5.1.3).	0	H	3,15										
4.	WORKERS: Assign a score from the table below for the total number of workers at the site and nearby facilities and within 200 feet of areas of observed contamination associated with the site. <table><tr><th>Number of Workers</th><th>Score</th></tr><tr><td>0</td><td>0</td></tr><tr><td>1 to 100</td><td>5</td></tr><tr><td>101 to 1,000</td><td>10</td></tr><tr><td>> 1,000</td><td>15</td></tr></table>	Number of Workers	Score	0	0	1 to 100	5	101 to 1,000	10	> 1,000	15	5	H	15
Number of Workers	Score													
0	0													
1 to 100	5													
101 to 1,000	10													
> 1,000	15													
5.	TERRESTRIAL SENSITIVE ENVIRONMENTS: Assign a value for each terrestrial sensitive environment (SI Table 16) in an area of observed contamination. <table><tr><th>Terrestrial Sensitive Environmental Type</th><th>Value</th></tr><tr><td>_____</td><td>_____</td></tr><tr><td>_____</td><td>_____</td></tr><tr><td>_____</td><td>_____</td></tr></table> Sum = _____	Terrestrial Sensitive Environmental Type	Value	_____	_____	_____	_____	_____	_____	0	H	15		
Terrestrial Sensitive Environmental Type	Value													
_____	_____													
_____	_____													
_____	_____													
6.	RESOURCES: Assign a score of 5 if one or more of the following resources is present on an area of observed contamination at the site; assign 0 if none applies: ● Commercial agriculture. ● Commercial silviculture. ● Commercial livestock production or commercial livestock grazing.	0	H	34										

Sum of Targets

T =

5

**SI TABLE 16 (HRS TABLE 5-5): SOIL EXPOSURE PATHWAY
TERRESTRIAL SENSITIVE ENVIRONMENT VALUES**

TERRESTRIAL SENSITIVE ENVIRONMENT	ASSIGNED VALUE
Terrestrial critical habitat for Federal designated endangered or threatened species National Park Designated Federal Wilderness Area National Monument	100
Terrestrial habitat known to be used by Federal designated or proposed threatened or endangered species National Preserve (terrestrial) National or State terrestrial Wildlife Refuge Federal land designated for protection of natural ecosystems Administratively proposed Federal Wilderness Area Terrestrial areas utilized by large or dense aggregations of animals (vertebrate species) for breeding	75
Terrestrial habitat used by State designated endangered or threatened species Terrestrial habitat used by species under review for Federal designated endangered or threatened status	50
State lands designated for wildlife or game management State designated Natural Areas Particular areas, relatively small in size, important to maintenance of unique biotic communities	25

SOIL EXPOSURE PATHWAY WORKSHEET

NEARBY POPULATION THREAT

LIKELIHOOD OF RELEASE			Score	Data Type	Refs
7.	Attractiveness/Accessibility (from SI Table 17 or HRS Table 5-6)	Value <u>10</u>	5	H	3,15 23,25
	Area of Contamination (from SI Table 18 or HRS Table 5-7)	Value <u>20</u>			
	Likelihood of Exposure (from SI Table 19 or HRS Table 5-8)				
LE =			5		

TARGETS		Score	Data Type	Refs
8.	Assign a score of 0 if Level I or Level II resident individual has been evaluated or if no individuals live within ¼ mile travel distance of an area of observed contamination. Assign a score of 1 if nearby population is within ¼ mile travel distance and no Level I or Level II resident population has been evaluated.	1	H	3,15
9.	Determine the population within 1 mile travel distance that is not exposed to a hazardous substance from the site (i.e., properties that are not determined to be Level I or Level II); record the population for each distance category in SI table 20 (HRS Table 5-10). Sum the population values and multiply by 0.1.	6.6	H	3,15
Sum of Targets T =		7.6		

**SI TABLE 17 (HRS TABLE 5-6):
ATTRACTIVENESS / ACCESSIBILITY VALUES**

AREA OF OBSERVED CONTAMINATION	ASSIGNED VALUE
Designated recreational area	100
Regularly used for public recreation (for example, vacant lots in urban area)	75
Accessible and unique recreational area (for example, vacant lots in urban area)	75
Moderately accessible (may have some access improvements - for example, gravel road) with some public recreation use	50
Slightly accessible (for example, extremely rural area with no road improvement) with some public recreation use	25
Accessible with no public recreation use	10
Surrounded by maintained fence or combination of maintained fence and natural barriers	5
Physically inaccessible to public, with no evidence of public recreation use	0

**SI TABLE 18 (HRS TABLE 5-7):
AREA OF CONTAMINATION FACTOR VALUES**

TOTAL AREA OF THE AREAS OF OBSERVED CONTAMINATION (SQUARE FEET)	ASSIGNED VALUE
≤ to 5,000	5
> 5,000 to 125,000	20
> 125,000 to 250,000	40
> 250,000 to 375,000	60
> 375,000 to 500,000	80
> 500,000	100

SI TABLE 19 (HRS TABLE 5-8): NEARBY POPULATION LIKELIHOOD OF EXPOSURE FACTOR VALUES

AREA OF CONTAMINATION FACTOR VALUE	ATTRACTIVENESS/ACCESSIBILITY FACTOR VALUE						
	100	75	50	25	10	5	0
100	500	500	375	250	125	50	0
80	500	375	250	125	50	25	0
60	375	250	125	50	25	5	0
40	250	125	50	25	5	5	0
20	125	50	25	5	5	5	0
5	50	25	5	5	5	5	0

SI TABLE 20 (HRS TABLE 5-10): DISTANCE-WEIGHTED POPULATION VALUES FOR NEARBY POPULATION THREAT

Travel Distance Category (Miles)	Pop.	Number of people within the travel distance category												Pop. Value
		0	1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	
Greater than 0 to ¼	828	0	0.1	0.4	1.0	4	13	41	130	408	1,303	4,081	13,034	13
Greater than ¼ to ½	2423	0	0.05	0.2	0.7	2	7	20	65	204	652	2,041	6,517	20
Greater than ½ to 1	9672	0	0.02	0.1	0.3	1	3	10	33	102	326	1,020	3,258	33
Reference(s) <u>3, 15, 34</u> Sum=														66

SOIL EXPOSURE PATHWAY WORKSHEET (concluded)

WASTE CHARACTERISTICS

10.	Assign the hazardous waste quantity score calculated for soil exposure	10,000																						
11.	Assign the highest toxicity value from SI Table 15 or SI Table 3	10,000																						
12.	Multiply the toxicity and hazardous waste quantity score. Assign the Waste Characteristic score from the table below: <table border="1" style="margin: 10px auto; width: 60%; border-collapse: collapse;"> <thead> <tr> <th style="width: 50%;">Product</th> <th style="width: 50%;">WC Score</th> </tr> </thead> <tbody> <tr><td>0</td><td>0</td></tr> <tr><td>> 0 to < 10</td><td>1</td></tr> <tr><td>10 to < 100</td><td>2</td></tr> <tr><td>100 to < 1,000</td><td>3</td></tr> <tr><td>1,000 to < 10,000</td><td>6</td></tr> <tr><td>10,000 to < 1E+05</td><td>10</td></tr> <tr><td>1E+05 to < 1E+06</td><td>18</td></tr> <tr><td>1E+06 to < 1E+07</td><td>32</td></tr> <tr><td>1E+07 to < 1E+08</td><td>56</td></tr> <tr><td>1E+08 or greater</td><td>100</td></tr> </tbody> </table>	Product	WC Score	0	0	> 0 to < 10	1	10 to < 100	2	100 to < 1,000	3	1,000 to < 10,000	6	10,000 to < 1E+05	10	1E+05 to < 1E+06	18	1E+06 to < 1E+07	32	1E+07 to < 1E+08	56	1E+08 or greater	100	WC = 100
Product	WC Score																							
0	0																							
> 0 to < 10	1																							
10 to < 100	2																							
100 to < 1,000	3																							
1,000 to < 10,000	6																							
10,000 to < 1E+05	10																							
1E+05 to < 1E+06	18																							
1E+06 to < 1E+07	32																							
1E+07 to < 1E+08	56																							
1E+08 or greater	100																							

RESIDENT POPULATION THREAT SCORE

(Likelihood of Exposure, Question 1;
Target = Sum of Questions 2, 3, 4, 5, 6)

$$\frac{LE \times T \times WC}{82,500}$$

82,500

3.33

NEARBY POPULATION THREAT SCORE:

(Likelihood of Exposure, Question 7;
Targets = Sum of Questions 8, 9)

$$\frac{LE \times T \times WC}{82,500}$$

82,500

0.05

SOIL EXPOSURE PATHWAY SCORE:

Resident Population Threat + Nearby Population
Threat

3.38

Maximum of 100

AIR PATHWAY

Air Pathway Observed Substances Summary Table

On SI Table 21, list the hazardous substances detected in air samples of a release from the site (also see HRS Sections 6.2.1.1 through 6.2.1.3). Include only those substances significantly greater than background levels. Obtain benchmark, cancer risk, and reference dose concentrations from SCDM. For NAAQS/NESHAPS benchmarks, determine the highest percentage of benchmark obtained for any substance. For cancer risk and reference dose, sum the percentages for the substances listed. If benchmark, cancer risk, or reference dose concentrations are not available for a particular substance, enter N/A for the percentage. If the highest benchmark percentage or the percentage sum calculated for cancer risk or reference dose equals or exceeds 100%, evaluate targets in the distance category from which the sample was taken and any close distance categories as Level I. If the percentages are less than 100% or all are N/A, evaluate targets in that distance category and any closer distance category that are not Level I as Level II.

AIR PATHWAY
NOT EVALUATED

SI TABLE 21: AIR PATHWAY OBSERVED RELEASE SUBSTANCES

Sample ID _____ Level I _____ Level II _____ Distance from Source(s) _____ References _____

Hazardous Substance	Conc. (ug/m ³)	Gaseous Particles	Benchmark Conc. (NAAQS OR NESHAPS)	% Of Benchmark	Cancer Risk Concentration	% of Cancer Risk Concentration	RfD	% of RfD
Highest Toxicity/ Mobility			Highest Percents		Sum of Percents		Sum of Percents	

Sample ID _____ Level I _____ Level II _____ Distance from Source(s) _____ References _____

Hazardous Substance	Conc. (ug/m ³)	Toxicity / Mobility	Benchmark Conc. (NAAQS OR NESHAPS)	% Of Benchmark	Cancer Risk Concentration	% of Cancer Risk Concentration	RfD	% of RfD
Highest Toxicity/ Mobility			Highest Percents		Sum of Percents		Sum of Percents	

Sample ID _____ Level I _____ Level II _____ Distance from Source(s) _____ References _____

Hazardous Substance	Conc. (ug/m ³)	Toxicity / Mobility	Benchmark Conc. (NAAQS OR NESHAPS)	% Of Benchmark	Cancer Risk Concentration	% of Cancer Risk Concentration	RfD	% of RfD
Highest Toxicity/ Mobility			Highest Percents		Sum of Percents		Sum of Percents	

AIR PATHWAY WORKSHEET

LIKELIHOOD OF RELEASE		Score	Data Type	Refs
1.	OBSERVED CONTAMINATION: If sampling data or direct observation support a release to air, assign a score of 550. Record observed release substances on SI table 21.			
2.	POTENTIAL TO RELEASE: If sampling data do not support a release to air, assign a score of 500. Optionally, evaluate air migration gaseous and particulate potential to release (HRS Section 6.1.2).			

LE =

TARGETS

<p>3. ACTUAL CONTAMINATION POPULATION: Determine the number of people within the target distance limit subject to exposure from a release of a hazardous substance to the air.</p> <p>Level I: _____ people x 10 = _____</p> <p>Level II: _____ people x 1 = _____ Total = _____</p>																			
<p>4. POTENTIAL TARGET POPULATION: Determine the number of people within the target distance limit not subject to exposure from a release of a hazardous substance to the air and assign a total population score from SI Table 22. Sum the values and multiply the sum by 0.1.</p>																			
<p>5. NEAREST INDIVIDUAL: Assign a score of 50 if there are any Level I targets. Assign a score of 45 if there are Level II targets but no Level I targets. If no Actual Contamination Population exists, assign the Nearest Individual score from SI Table 22.</p>																			
<p>6. ACTUAL CONTAMINATION SENSITIVE ENVIRONMENTS: Sum the sensitive environment values (SI table 13) and wetland acreage values (SI table 23) for environments subject to exposure from the release of a hazardous substance to the air.</p> <table border="1" style="width: 100%; border-collapse: collapse; margin: 10px 0;"> <tr> <td style="width: 50%; text-align: center;">Terrestrial Sensitive Environmental Type</td><td style="width: 50%; text-align: center;">Value</td></tr> <tr><td>_____</td><td>_____</td></tr> <tr><td>_____</td><td>_____</td></tr> <tr><td>_____</td><td>_____</td></tr> </table> <table border="1" style="width: 100%; border-collapse: collapse; margin: 10px 0;"> <tr> <td style="width: 50%; text-align: center;">Wetland Acreage</td><td style="width: 50%; text-align: center;">Value</td></tr> <tr><td>_____</td><td>_____</td></tr> <tr><td>_____</td><td>_____</td></tr> <tr><td>_____</td><td>_____</td></tr> </table>	Terrestrial Sensitive Environmental Type	Value	_____	_____	_____	_____	_____	_____	Wetland Acreage	Value	_____	_____	_____	_____	_____	_____			
Terrestrial Sensitive Environmental Type	Value																		
_____	_____																		
_____	_____																		
_____	_____																		
Wetland Acreage	Value																		
_____	_____																		
_____	_____																		
_____	_____																		
<p>7. POTENTIAL CONTAMINATION SENSITIVE ENVIRONMENTS: Use SI Table 24 to evaluate sensitive environments not subject to exposure from a release.</p>																			
<p>8. RESOURCES: Assign a score of 5 if one or more resources apply within 1/2 mile of the source; assign a 0 if none applies.</p> <ul style="list-style-type: none"> • Commercial agriculture. • Commercial silviculture. • Major or designated recreation area. 																			

T =

SI TABLE 22 (From HRS TABLE 6-17): VALUES FOR POTENTIAL CONTAMINATION AIR TARGET POPULATIONS

Distance from site	Pop.	Nearest Individual (choose highest)	Number of People within the Distance Category												Pop. Value
			1 to 10	11 to 30	31 to 100	101 to 300	301 to 1,000	1,001 to 3,000	3,001 to 10,000	10,001 to 30,000	30,001 to 100,000	100,001 to 300,000	300,001 to 1,000,000	1,000,000 to 3,000,000	
On a source		20	4	17	53	164	522	1,633	5,214	16,325	52,137	163,246	521,360	1,632,455	
0 to ¼ mile		*	1	4	13	41	131	408	1,304	4,081	13,034	40,812	130,340	408,114	
> ¼ to ½ mile		2	0.2	0.9	3	9	28	88	282	882	2,815	8,815	28,153	88,153	
> ½ to 1 mile		1	0.06	0.3	0.9	3	8	26	83	261	834	2,612	8,342	26,119	
> 1 to 2 miles		0	0.02	0.09	0.3	0.8	3	8	27	83	266	833	2,659	8,326	
> 2 to 3 miles		0	0.009	0.04	0.1	0.4	1	4	12	38	120	375	1,199	3,755	
> 3 to 4 miles		0	0.005	0.02	0.07	0.2	0.7	2	7	28	73	229	730	2,285	
Nearest Individual =			Sum =												

AIR PATIWAY
NOT EVALUATED

References _____

* Score = 20 if the Nearest Individual is within 1/8 mile of a source; score = 7 if the Nearest Individual is between 1/8 and 1/4 mile of a source.

**SI TABLE 23 (HRS TABLE 6-18):
AIR PATHWAY VALUES FOR WETLAND AREA**

WETLAND AREA	ASSIGNED VALUE
< 1 acre	0
1 to 50 acres	25
> 50 to 100 acres	75
> 100 to 150 acres	125
> 150 to 200 acres	175
> 200 to 300 acres	250
> 300 to 400 acres	350
> 400 to 500 acres	450
> 500 acres	500

**SI TABLE 24:
DISTANCE WEIGHTS AND CALCULATIONS FOR AIR PATHWAY POTENTIAL
CONTAMINATION SENSITIVE ENVIRONMENTS**

Distance	Distance Weight	Sensitive Environment Type and Value (from SI tables 13 and 20)	Product
On A Source	0.10	x	
0 - ¼ mile	0.025	x	
¼- ½ mile	0.0054	x	
½- 1 mile	0.0016	x	
1 - 2 miles	0.0005	x	
2 - 3 miles	0.00023	x	
3 - 4 miles	0.00014	x	
> 4 miles	0	x	
Total Environments Score =			

AIR PATHWAY (concluded)

WASTE CHARACTERISTICS

9.	If any Actual Contamination Targets exist for the air pathway, assign the calculated hazardous waste quantity score or a score of 100, whichever is greater; if there are no Actual Contamination Targets for the air pathway, assign the calculated HWQ score for sources available to air migration.																						
10.	Assign the highest toxicity/mobility value from SI Table 21 and HRS Sections 6.2.1.1 through 6.2.1.3.																						
11.	Multiply the air pathway toxicity/mobility value from SI Table 21.	WC =																					
<table border="1"> <thead> <tr> <th>Product</th> <th>WC Score</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>0</td> </tr> <tr> <td>> 0 to < 10</td> <td>1</td> </tr> <tr> <td>10 to < 100</td> <td>2</td> </tr> <tr> <td>100 to < 1,000</td> <td>3</td> </tr> <tr> <td>1,000 to < 10,000</td> <td>6</td> </tr> <tr> <td>10,000 to < 1E+05</td> <td>10</td> </tr> <tr> <td>1E+05 to < 1E+06</td> <td>18</td> </tr> <tr> <td>1E+06 to < 1E+07</td> <td>32</td> </tr> <tr> <td>1E+07 to < 1E+08</td> <td>56</td> </tr> <tr> <td>1E+08 or greater</td> <td>100</td> </tr> </tbody> </table>			Product	WC Score	0	0	> 0 to < 10	1	10 to < 100	2	100 to < 1,000	3	1,000 to < 10,000	6	10,000 to < 1E+05	10	1E+05 to < 1E+06	18	1E+06 to < 1E+07	32	1E+07 to < 1E+08	56	1E+08 or greater
Product	WC Score																						
0	0																						
> 0 to < 10	1																						
10 to < 100	2																						
100 to < 1,000	3																						
1,000 to < 10,000	6																						
10,000 to < 1E+05	10																						
1E+05 to < 1E+06	18																						
1E+06 to < 1E+07	32																						
1E+07 to < 1E+08	56																						
1E+08 or greater	100																						
<div style="display: flex; justify-content: space-between;"> <div>AIR PATHWAY SCORE</div> <div> $\frac{LE \times T \times WC}{82,500}$ </div> </div>																							

maximum of 100

SITE SCORE CALCULATION	S	S ²
GROUNDWATER PATHWAY SCORE (S _{GW})	3.33	11.11
SURFACE WATER PATHWAY SCORE (S _{SW})	100	10,000
SOIL EXPOSURE SCORE (S _S)	3.38	11.42
AIR PATHWAY SCORE (S _A)	NOT EVALUATED	NOT EVALUATED
SITE SCORE $\sqrt{\frac{S_{GW}^2 + S_{SW}^2 + S_S^2 + S_A^2}{4}}$		= 50.1

COMMENTS

Based on analytical data collected during this SSI and from previous investigations, an observed release to soil, groundwater, and surface water has been identified for benzene and PAHs. Due to the lack of targets for the soil and groundwater pathways, they are of low concern. The surface water pathway is of primary concern and could be considered a "target" of the soil and groundwater pathways.

PCB contamination was not identified during this SSI or from previous investigations.

The potential sources of benzene and PAH contamination are the FMGP and/or the Petroleum, Fuel and Terminal-Apex Oil facility.

SI SCORESHEET REFERENCES

- 1 Barra, Louise. National Park Service, Gateway Arch. March 15, 1994. Telephone conversation with Don Falls, MDNR. Subject: Park acreage and attendance.
- 2 Brabander, Jerry. U.S. Fish and Wildlife Service. June 14, 1993. Correspondence to Edwin Knight, MDNR. Subject: sensitive environments near the subject site.
- 3 Ecology and Environment/Field Investigation Team (E&E/FIT). October 29, 1991. Screening Site Inspection, Laclede Coal Gas, St. Louis, Missouri.
- 4 Ecology and Environment/Field Investigation Team (E&E/FIT). June 23, 1988. Preliminary Assessment, Mound Street Power Plant, St. Louis, Missouri.
- 5 Edmond, Howard. Metropolitan Sewer District. December 13, 1993. Telephone conversation with Don Falls, MDNR Hazardous Waste Program, Superfund Section.
- 6 Edmond, Howard. Metropolitan Sewer District. November 21, 1995. Telephone conversation with Mike May, Sverdrup.
- 7 Falls, Don. MDNR Hazardous Waste Program, Superfund Section. November 22, 1993a. Mound Street PCB Site Reconnaissance Memorandum.
- 8 Falls, Don. MDNR Hazardous Waste Program, Superfund Section. December 13, 1993b. Latitude/Longitude Calculation Worksheet.
- 9 GEHM Corporation (GEHM). September 1, 1993a. Activities Report, TRRA of St. Louis, First and Mound Streets Site, MDNR Spill Report #07143-KB-1331.
- 10 GEHM Corporation (GEHM). October 26, 1993b. UST Removal Closure Report.
- 11 Lewis, R.H., Petroleum Fuel and Terminal. Letter to Charles Gay, Fire Inspector. Subject: Identification of pipeline leak per a September 8, 1993 telephone conversation. (Received by Howard Edmond, MSD, on September 30, 1993).
- 12 Metropolitan Sewer District, Environmental Compliance Laboratory (MSD). July 19, 1993a. Sample analysis of Brooklyn Street pump station wet well and UST at Brooklyn and Mound.
- 13 Metropolitan Sewer District, Environmental Compliance Laboratory (MSD). August 13, 1993b. Sample analysis of Manhole F-GA1 (#12), (#13), and (#14).
- 14 Missouri State Highway Map. 1993.
- 15 Missouri Department of Natural Resources (MDNR). March 21, 1994a. Preliminary Assessment. Mound Street PCB Site, St. Louis, Missouri.
- 16 Missouri Department of Natural Resources (MDNR). March 30, 1994b. Missouri Water Quality Standards, 10 CSR 20-7.031.
- 17 Reed, Richard, Illinois American Water Company. December 29, 1993. Telephone conversation with Don Falls, MDNR Hazardous Waste Program, Superfund Section.
- 18 Robinson, J., MDC. March 15, 1994. Telephone conversation with Don Falls, MDNR Hazardous Waste Program, Superfund Section.
- 19 Schiermann, J. June 3, 1996. Water Quality Supervisor, Illinois-American Water Company. Personal interview with and correspondence to Michael McCurdy, Sverdrup. Subject: Raw water sampling analysis of the East St. Louis water intake.

- 20 Smith, S.I., St. Louis MSD. July 8, 1993. Special Problem Investigation of Brooklyn Street Pump Station.
- 21 Starbuck, Edith. Missouri Department of Natural Resources, Division of Geology and Land Survey. December 29, 1993. PA/SI Report for the Mound Street Site, St. Louis, City.
- 22 Starbuck, Edith. Missouri Department of Natural Resources, Division of Geology and Land Survey. January 5, 1994. Existence of karst near the Mound Street Site.
- 23 Sverdrup Corporation. December 11, 1995. Field Log Book and Trip Report for Site Reconnaissance Activities at the Mound Street PCB Site, St. Louis, Missouri.
- 24 Sverdrup Corporation. March 4, 1996a. Field Sampling Plan, Mound Street PCB Site, St. Louis, Missouri.
- 25 Sverdrup Corporation. April 2, 1996b. Field Log Book and Trip Report for Site Sampling Activities at the Mound Street PCB Site, St. Louis, Missouri.
- 26 U.S. Army Corps of Engineers, St. Louis District, (USACE). August 30, 1962. Flood Protection Reach 3, Floodwall and General Contract Items. Station 352+00 to Station 369+00 drawing and Soil Exploration Data.
- 27 U.S. Department of Agriculture, Soil Conservation Service (USDA). April 1982. Soil Survey of St. Louis County and St. Louis City, Missouri.
- 28 U.S. Department of Commerce, Bureau of Census (Census). 1990. 1990 Census of Population and Housing, Summary of Population and Housing Characteristics, Missouri.
- 29 U.S. Department of Commerce (USDC). 1983. The Climatic Atlas of the United States.
- 30 U.S. Environmental Protection Agency (U.S. EPA). May 3, 1996. Data Transmittal for Activity DC1CY, Mound Street PCB Site.
- 31 U.S. Environmental Protection Agency (U.S. EPA). 1992. Guidance for Performing Site Inspections under CERCLA. EPA 540-R-92-021.
- 32 U.S. Environmental Protection Agency (U.S. EPA). 1995. Hazard Ranking System. Superfund Chemical Data Matrix Table.
- 33 U.S. Environmental Protection Agency (USEPA). November 1992. The Hazard Ranking System Guidance Manual. Publication 9345.1-07. Washington, DC.
- 34 U. S. Geological Survey (USGS). 7.5 Minute Series Topographic Map. Granite City, Missouri-Illinois 1954 (photorevised 1974), Cahokia, Illinois-Missouri 1954 (photorevised 1974), Clayton, Missouri 1954 (photorevised 1974), French Village, Illinois 1954 (photorevised 1982), Monks Mound, Illinois 1954 (photorevised 1993), Webster Groves, Missouri 1954 (photorevised 1974).
- 35 U.S. Government Printing Office, Environmental Protection Agency, Hazard Ranking System Final Rule. December 14, 1990. 40 CFR Part 300. Federal Register/Volume 55/no. 241.

DEPARTMENT OF NATURAL RESOURCES
Division of Environmental Quality
Hazardous Waste Program

Reference 1

TELEPHONE OR CONFERENCE RECORD

File: Mound Street PCBs

Date: March 15, 1994

TELEPHONE (314) 425-4468

CONFERENCE

Incoming ()
Outgoing (X)

Field ()
Office ()

SUBJECT: Jefferson National Expansion Memorial - Gateway Arch

PERSONS INVOLVED

Name

Ms. Louise Barra
Don Falls

Representing

National Park Service, Gateway Arch
MDNR, Hazardous Waste Program

SUMMARY OF CONVERSATION:

I phoned the public affairs office of the Jefferson National Expansion Memorial in St. Louis and spoke with a Ms. Louise Barra. Ms. Barra is a public affairs officer with the National Park Service. I asked Ms. Barra if she could tell me the exact acreage of the park and the total annual attendance. Ms. Barra informed me that the park encompasses just over 90 acres and the total annual attendance for all the park property, including the parking structure, is approximately 2.7 million people.

FINAL RESULTS:

This information will be incorporated into the Mound Street PCB Preliminary Assessment.

Don Falls

Don Falls
Environmental Specialist
Hazardous Waste Program

DF:so

Final Report
Screening Site Inspection
Laclede Coal Gas
St. Louis, Missouri
EPA ID# MOD981715980
TDD #F-07-9008-020 PAN #FM00579SA
Site #Y33 Project #002
Prepared by E & E/FIT for the
Region VII EPA RPO
Project Manager: Keith Brown
Superfund Contact: Greg Reesor
Date: October 29, 1991




HAZARDOUS
SITE
EVALUATION
DIVISION

RECEIVED

FEB 18 1992

HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RESOURCES

Field Investigation Team Zone II



CONTRACT NO.
68-01-7347

ecology and environment, inc.

Reference 4



Preliminary Assessment
Mound Street Power Plant
St. Louis, Missouri
TDD #F-07-8708-29 PAN #FM00579PA
Site #Y33 Project #001
Prepared by: E & E/FIT for Region VII EPA
Task Leader: Eric Hess, E & E/FIT
Superfund Contact: Pauletta R. France-Isetts
Date: June 23, 1988

DEPARTMENT OF NATURAL RESOURCES
Division of Environmental Quality
Hazardous Waste Program

TELEPHONE OR CONFERENCE RECORD

File: Mound Street PCB Site

Date: December 13, 1993

TELEPHONE (314) 436-8735

CONFERENCE

Incoming ()
Outgoing (X)

Field ()
Office (X)

SUBJECT: Mound Street PCB Site

PERSONS INVOLVED

Name

Don Falls
Howard Edmond
Anne Olberding
Bob Jackson

Representing

MDNR/HWP
Metropolitan Sewer District
USEPA, Region VII (913) 551-7718
USEPA, Region VII (913) 551-7020

SUMMARY OF CONVERSATION:

I phoned Mr. Howard Edmond of the MSD (Metropolitan Sewer District) to find out exactly how the waste oil was seeping into the Brooklyn Street pump station. Mr. Howard explained that sometime around the middle of July 1993, oil was noticed seeping from the storm sewer into the wet well of the pump station. Mr. Howard said that the Brooklyn Street pump station only pumps storm water, and therefore only operates during periods of rain. Mr. Howard said that the oil stayed on top of the wet well, and was later pumped off by React Environmental. He said that it was possible that some of the oil made it out to the river. Mr. Howard said that the MSD laboratory did the analysis on the samples that he collected. The results indicate Aroclor 1254 in the oil at 47 parts per million.

I then asked Mr. Howard if he was familiar with the history of the Mound Street site. He related that there was a rumor that the basement of the former Union Electric building, which occupied part of the site, was said to be full of old transformers, and was claimed to be an EPA (U.S. Environmental Protection Agency) Superfund site where a "poor cleanup" was performed before the building was demolished.

Mr. Howard further said that he believes that the City of St Louis may now own the former Union Electric property, and Inspector Charles Gay with the St. Louis Fire Department would know more about the site, because he has been working on the site for some time.

Mound Street PCB
December 13, 1993
Page 2

ACTION TAKEN:

I phoned the St. Louis City Fire Department (314/298-1900) and asked to speak with Mr. Charles Gay. The secretary there said that Mr. Gay was out of the office, but would leave a message for him to call me. I then called Ms. Anne Olberding, EPA Region VII, and asked if she was aware of an EPA cleanup in the vicinity of the Mound and First Streets in St. Louis. Ms. Olberding said that location did not ring a bell, but she would search Cerclis according to site latitude and then send me the results.

In addition, I also spoke with Mr. Bob Krager, MDNR, Hazardous Waste Program, and asked if he was aware of any Superfund activities at the former Union Electric property at Mound Street. Mr. Krager said that he was unaware of any activities at that particular location and suggested that I contact Mr. Bob Jackson at EPA Region VII. I phoned Mr. Jackson who said that he would check the TOSCA records. Mr. Jackson called back and informed me that he could find nothing in the records about an EPA cleanup at the Union Electric power plant near Mound Street.

FINAL RESULTS:

This information will be used in the Mound Street PCB preliminary assessment.

Don Falls
Don Falls
Environmental Specialist

DF:so

Memo No. 1Job No. 10865-370303Date Nov 21 19 95Time 9:00 A m - 9:25Between (S v C) Mike Man Placed ☒ Rec'd ☐And Howard Edmond Tel (314) 436-8735Of St. Louis Metropolitan Sewer District (MSD)Subject Mound Street PCBs / USTs / Manhole Sampling

- ① - old granary building south end - found on old UST, got in manhole & floodwalls
TRRA
- never could really determine exact source
 - Removal was turned over to city of St. Louis & Railroad - was on railroad property
 - Chief Horne - Fire Inspector
(may have city Block & Lot #s) 289-1900
(worked with fire marshall - Railroad
↳ NW on E.H. Central
 - little street between granary & pump station
↳ operates only during rain
 - floodwall manholes - not sewerage
↳ but underground drainage keeps
 - no seepage of oil from 1993 that he knows of - no complaints
DNR & EPA taken care back then
 - [Samples on identifying source: 768-6200 permit dept. MSD
City - permit office Hampton Ave
- City Block & Lot #]
 - F - G A I (12) (13) (14)
floodwall → manhole nothing to do with MSD
- Corp of Engineers need to check

Memo No. 1 Job No. 10865-370303
Date Nov. 21 19 95 Time 9:00 m
Between (SVC) Mike May Placed _____ Rec'd _____
And Howard Edmond Tel (314) 436-8735
Of St. Louis M.S.D.
Subject Mound Street PCBs / USTs & other sources / pump system

Summary

- reiterated that the manholes were not "storm drainage" related. The pump station only pumps under circumstances of exceedingly heavy precipitation or if the river level is at or exceeding flood stage. Manholes are for protection of the flood wall (underground H₂O) not storm sewer.
- If there would have been oil recognized since 1993 then Howard's crews would have definitely reported the oil in the manholes or pumping station
- call chief Horne first, before calling city for lot & block #'s - they have this information already.

STATE OF MISSOURI
DEPARTMENT OF NATURAL RESOURCES
MEMORANDUM

DATE: November 22, 1993

TO: Mound Street PCB Site

FROM: Don Falls, Environmental Specialist
Site Evaluation Unit, Superfund Section
Hazardous Waste Program

SUBJECT: Mound Street PCB Site Reconnaissance

On November 11, 1993, I traveled to the Mound Street PCB site to conduct a site reconnaissance and meet with Mr. Daryl Bowles and Mr. David Gehm of the GEHM Corporation. The site is located at Mound and Brooklyn Streets, on the Riverfront, in downtown St Louis. I arrived at the site at 8:35 a.m. and first made a vehicle reconnaissance of the area within 1/4 mile of the site. The weather was clear and sunny with a temperature of approximately 55 degrees.

At 9:00 a.m., I met with Mr. Bowles and Mr. Gehm at the old terminal building. They were at the site to oversee the removal of waste oil that had been temporarily stored on-site from an earlier underground storage tank removal. I first asked Mr. Bowles if he could show me where the Metropolitan Sewer District pump station was located. He directed me to the pump station located at the end of Brooklyn Street, approximately 400 feet from the old terminal building. The pump station is located next to the flood wall and is surrounded by a security fence. I noted that five 55-gallon drums marked as waste oil and PCBs (Polychlorinated Biphenyl) were stored against the pump station south wall.

I then asked Mr. Bowles if he would show me exactly where the boring attempts were made that he had referred to in his activities report. We walked across Mound Street to an area immediately east of the old terminal building. This area appeared as an anomaly on the IR/T (Infrared Thermograph) survey completed in August 1993 by Entech Engineering as part of GEHM Inc.'s investigation of the site. Mr. Bowles explained that the drilling attempts were unsuccessful due to solid rock, cinder block, and other debris being encountered at a depth of about five feet. Mr. Bowles informed me that a long-time employee of Apex Fuel Company claims that Union Electric Company once used a building at this particular site to store transformers. The

basement of this building was said to be full of waste oil when the building was demolished several years ago. Mr. Bowles indicated that the foundation or basement of this demolished building might explain the IR/T anomaly.

I asked Mr. Gehm about the capabilities of the IR/T and if it could image at depths of several feet. He said that he thought that the IR/T could image areas of dissimilar makeup to a depth of about 20 feet. Mr. Bowles added that buried objects as small as five-gallon buckets have been identified with the instrument. Mr. Gehm said that the IR/T images are taken using a lift bucket and are taken at a height of about 30 feet above the ground.

At 10:15 a.m., Mr. Gehm and Mr. Bowles said that they had to leave to finish with the removal of the waste oil. I thanked them for their assistance and told them that I would stay in touch with them. After taking more photographs of the area, I then left the site at approximately 11:00 a.m.

DF:so

LATITUDE AND LONGITUDE CALCULATION WORKSHEET #2
LI USING ENGINEER'S SCALE (1/60)

SITE NAME: Mound Street PCB's CERCLIS #: MO 000 009367
 AKA: _____ SSID: _____
 ADDRESS: 100 Mound Street
 CITY: St. Louis STATE: MO ZIP CODE: 63102
 SITE REFERENCE POINT: Center of former Union Electric Property.
 USGS QUAD MAP NAME: Granite City, IL TOWNSHIP: 45N/S RANGE: 7E/W
 SCALE: 1:24,000 MAP DATE: 1954 SECTION: 11/4 1/4 1/4
 MAP DATUM: (1927) 1983 (CIRCLE ONE) MERIDIAN: 5th Principal
 COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 7.5' MAP (attach photocopy):
 LONGITUDE: 90 ° 07 ' 30 " LATITUDE: 38 ° 37 ' 30 "
 COORDINATES FROM LOWER RIGHT (SOUTHEAST) CORNER OF 2.5' GRID CELL:
 LONGITUDE: 90 ° 10 ' 00 " LATITUDE: 38 ° 37 ' 30 "

CALCULATIONS: LATITUDE (7.5' QUADRANGLE MAP)

- A) NUMBER OF RULER GRADUATIONS FROM LATITUDE GRID LINE TO SITE REF POINT: 195
 B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{64.42} "$$

- C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 1 ' 4 . 42 "

- D) ADD TO STARTING LATITUDE: 38 37 ' 30 . 00 " + 1 ' 4 . 42 " =

SITE LATITUDE: 38 ° 38 ' 34 . 00 "

CALCULATIONS: LONGITUDE (7.5' QUADRANGLE MAP)

- A) NUMBER OF RULER GRADUATIONS FROM RIGHT LONGITUDE LINE TO SITE REF POINT: 173
 B) MULTIPLY (A) BY 0.3304 TO CONVERT TO SECONDS:

$$A \times 0.3304 = \underline{57.15} "$$

- C) EXPRESS IN MINUTES AND SECONDS (1' = 60"): 0 ' 57 . 15 "

- D) ADD TO STARTING LONGITUDE: 90 ° 10 ' 00 . 00 " + 0 ' 57 . 15 " =

SITE LONGITUDE: 90 ° 10 ' 57 . 15 "

INVESTIGATOR: Don Falls DATE: 12/13/93

**ACTIVITIES REPORT
TRRA of St. Louis
First & Mound Streets Site
MDNR Spill Report
07143 - KB - 1331**

RECEIVED
SEP 16 1993
HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RESOURCES

**The GEHM Corporation
1417 Bingham Rd.
P.O. Box 65
Boonville, MO 65233**



TABLE OF CONTENTS

SECTION	PAGE
1.0 PROJECT SYNOPSIS	1
2.0 DESCRIPTION OF SURROUNDING PROPERTIES	1
3.0 SITE DESCRIPTION	2
4.0 SITE ACTIVITIES	3
4.1 Tank Contents Removal	3
4.2 Infrared Thermographic Survey	4
4.3 Drilling/Sampling	6
5.0 SUMMARY DISCUSSION	7
LIST OF ATTACHMENTS:	
Copy of TRRA Area Drawing	
Laboratory Reports	
Boring Logs	

ACTIVITIES REPORT
TRRA of St. Louis
First & Mound Streets Site
MDNR SPILL REPORT # 07143 - KB -1331



1.0 PROJECT SYNOPSIS

This is a report of activities and findings resulting from the discovery of oils seeping into a pump station operated by Metropolitan Sewer District (MSD) in St. Louis, Missouri. On July 14, 1993, MSD reported this situation to the MDNR. MSD analytical information revealed PCB levels of less than 50 ppm in the oils seeping into the pump station. Additionally, a sample was obtained from waste oil contained in an underground storage tank present in the area, and owned by Terminal Railroad Association of St. Louis (TRRA). The St. Louis Fire Department (SLFD) notified TRRA on July 28, 1993 and requested the contents of the tank be removed. TRRA was unaware of the existence of the tank prior to notification by the SLFD.

In response to the situation, TRRA initiated and completed the following tasks:

- **Contents of the tank were removed on August 4, 1993.** The tank was completely cleaned and freed of all liquids. The material was containerized on-site in 55 gallon drums for characterization and disposal.
- **An Infrared Thermographic Survey was conducted** of the area in an attempt to characterize leak plumes or trails.
- **Three borings were advanced** in the immediate area to determine subsurface soil conditions. Two soil samples were obtained from the site and submitted to a qualified laboratory for chemical analysis.

This report documents the response efforts and findings of the investigatory activities.

2.0 DESCRIPTION OF SURROUNDING PROPERTIES

The property is bordered by gravel roads on the north, east, and south sides. To the west is a gravel covered area containing truck scales and operated by Apex Oil Co. Across the road (Mound Street), and to the south is an empty lot formerly occupied by Union Electric Company of Missouri. To the east are several sets of railroad tracks immediately adjacent to the flood wall. To the north (across Brooklyn Street), is a facility operated by Continental Cement Company (apparently used for cement loading/unloading). The MSD Pump Station is situated adjacent to the flood wall and approximately 400-500 ft. north-east of the tank location. Southwest of the property (across Mound street) is a bulk petroleum storage/distribution facility. This facility is characterized by several large

(> 500,000 gallon capacity) above ground storage tank systems.




FIGURE 1: AREA SKETCH SHOWING PROPERTY AND SURROUNDING PROPERTIES.
(APPROX. SCALE: 1"=180')

Numerous combined sewer, water and other utilities exist (some abandoned) throughout the area which were not completely defined for this report. Utilities which were obvious from site observations and from conversations with MSD personnel included a sewer line adjacent to the TRRA property along Mound Street, and a main line extending west from the pump station. Several underground utility lines run parallel to the railroad tracks and flood wall in a north - south direction. A TRRA property drawing identified a vitrified pipe drain traversing the site from approximately the tank location to the southeast corner of the property (copy provided in attachments). No attempts were made intrusively to locate and verify the existence of this pipe, however, IR/T did not provide a signature typical of an underground conduit acting as a migratory pathway.

A slight gradient (approx. 1:20) typifies the immediate area from west to east.

Groundwater was encountered on the site at a depth of 8 to 8.5 feet from surface. However, site activities were conducted one day following the crest of the Mississippi River on August 1, 1993. Evidence of extreme hydrostatic pressure in the area was observed by water shooting approximately 10 feet high from a Corps of Engineers piezometer located adjacent to the flood wall (approximately 400 feet from the UST), and by a groundwater/surface interface along the area between the eastern most road and the railroad tracks (see Figure 1). Observations of this interface revealed an apparent petroleum sheen present in many areas where the groundwater was seeping from the




FIGURE 2: SITE SKETCH DEPICTING PROMINENT FEATURES. (APPROX. SCALE: 1"=200')

interface. A sheen was observed in an area extending from a line approximately even with the south side of the TRRA property, south to a line approximately even with the south side of the former Union Electric property.



3.0 SITE DESCRIPTION

The parcel of property identified as TRRA property and where the UST exists, measures approximately 150 ft. by 340 ft. The property is generally situated in a north-south direction between the ends of Mound and Brooklyn Streets, St. Louis County, St. Louis, Missouri. Two structures are on the property which appear to be abandoned grain elevator and storage/handling structures constructed of reinforced concrete. The larger of the two structures measures approximately 40 ft. by 160 ft. and is situated along the east side of the property. The smaller structure measures approximately 20 ft. by 170 ft., is situated along the west side of the property with the UST located at the south end. A railroad siding runs adjacent to this smaller structure as well.

4.0 SITE ACTIVITIES

The purpose of the site activities was twofold. First was in response to the requests of the SLFD assuming the tank as the most likely source of the contaminants entering the MSD pump station, and secondly, to assess the most likely migratory pathway of the contaminants for the purpose of determining the most effective abatement measures.

4.1 Tank Contents Removal

On August 4, 1993, field personnel were mobilized to the site to conduct removal of the tank contents and cleaning of the tank. This procedure was accomplished by Environmental Operations, St. Louis, Missouri. A vacuum truck was used to pump material from the tank then placed in 55 gallon drums, staged on site. The tank was entered, following Confined Space Entry Procedures to remove and clean the remaining product and debris. Samples of the waste were obtained and submitted to American Interplex Corporation for analyses and summarized in the following table.



TANK WASTE ANALYSIS SUMMARY			
PARAMETER	UNIT	RESULT	METHOD
IGNITABILITY	°F	Non-ignitable below 212	EPA 1010
TOTAL HALIDES	mg/Kg	880	EPA 9020
PCB	mg/Kg	<10	EPA 600/4-81/045
HEAT CONTENT	BTU/lb	9480	ASTM D240
TCLP:			EPA 1311 (FEDERAL REGISTER/VOL. 57, NO. 227/NOVEMBER 24, 1992), 3010A, 6010A, 7470.
SILVER	mg/l	<.007	
ARSENIC	mg/l	<.02	
BARIUM	mg/l	2.1	
CADMIUM	mg/l	.019	
CHROMIUM	mg/l	.0096	
MERCURY	mg/l	<.01	
LEAD	mg/l	<.1	
SELENIUM	mg/l	<.02	

Note: Analysis parameters were selected for the purpose of determining disposal options.

Sixteen drums (approximately 880 gallons) of sludge/liquid, and one drum containing solid debris were generated. The waste was dual phased consisting of 60% ethylene glycol and 40% waste oils (based on appearance).

The tank system was constructed of steel and riveted with the top of the tank at ground surface. An eighteen inch diameter manway centered the tank with a two inch line extending from the tank, above grade, through the wall of the nearby structure. Tank dimensions were 10.5' dia., and 18.5' in length providing a capacity of 12,000 gallons. Tank depth was at 10.5 feet from surface.

4.2 Infrared Thermographic Survey (IR/T).

An Infrared Thermographic Survey was conducted in the immediate area on August 17, 1993 by EnTech Engineering, Inc. Infrared Thermography (IR/T) was selected to be performed at this site due to its ability to provide on-site, real time data. IR/T measures the heat energy emitted from the earth's surface stored during daylight hours. Areas of dissimilar chemical or physical make-up (such as petroleum contaminated soils versus non-petroleum contaminated soils) emits stored heat energy at different rates. IR/T is used to identify potential contaminated areas in relation to a known source such as an Underground Storage Tank, Pipeline, etc.

The results of the IR/T investigation for this site did not portray evidence of a leak

plume, trail or other leak signature which would suggest a release capable of migrating from the UST to any point off-site.

The investigation did, however, indicate an anomaly on the former Union Electric Company property south of the TRRA property (see Figure 2). An area measuring approximately 10' x 10' was identified. IR/T cannot identify the cause of an anomaly without either an intrusive investigation or knowledge of a potential source of an anomaly. At the request and permission of Inspector Charles Gay (SLFD), this area was investigated and described in section 4.3.





FIGURE 3: SITE SKETCH SHOWING AREAS DEPICTED ON IR/T THERMOGRAMS.

From the IR/T data generated, three views were selected for presentation in this report. These views are depicted on the following site sketch and the thermograms are presented on the following pages. The data was gathered between 11:00 p.m and midnight from a lift truck at approximately 30'. The corresponding photographs are provided for the purpose of reference.



VISUAL IMAGE NUMBER: 1V


THERMOGRAM IMAGE NUMBER: 1T

LOCATION: Terminal R.R.
1st and Mound Street
St. Louis, Missouri

ITEM: Example data image

LOCATION: Refer to drawing item #1

INVESTIGATION DATE: 8/17/93



VISUAL IMAGE NUMBER: 2V


THERMOGRAM IMAGE NUMBER: 2T

LOCATION: Terminal R.R.
1st and Mound Street
St. Louis, Missouri

ITEM: Example data image

LOCATION: Refer to drawing item #2

INVESTIGATION DATE: 8/17/93



VISUAL IMAGE NUMBER: 3V

THERMOGRAM IMAGE NUMBER: 3T

LOCATION: Terminal R.R.
1st and Mound Street
St. Louis, Missouri

ITEM: Example data image

LOCATION: Refer to drawing item #3

INVESTIGATION DATE: 8/17/93



4.3 Drilling/Sampling.

On August 4, 1993, a drilling crew was mobilized to the site and a total of five boring attempts were made. Three attempts were unsuccessful with auger refusal at five feet. One unsuccessful attempt was made on site approximately 30 feet south of the west end of the tank. Solid debris was encountered to a depth of 5 feet and the attempt was abandoned. At the request and permission of Inspector Charles Gay (SLFD), two other attempts were made in the area of the IR/T anomaly discovered within the former Union Electric Property. Both attempts were abandoned at a depth of 5 feet encountering solid rock debris.

The two successful attempts were located at the east (down gradient) end of the tank location, and approximately 37.5 feet south of the tank location. One sample was obtained from each of these borings and submitted to a qualified laboratory per analysis presented in the following table

SAMPLE RESULTS SUMMARY TABLE (in ppm)							
I.D.	LOCATION	TPH	PCB	BENZENE	TOLUENE	E. BENZENE	XYLENES
01	10 FT. DEPTH	67	<0.05	<0.002	<0.002	<0.002	<0.002
02	8 FT. DEPTH	23	<0.05	<0.002	<0.002	<0.002	<0.002

5.0 SUMMARY/DISCUSSION

Analysis of the tank contents reveal a mixture of Ethylene Glycol (Antifreeze) and Waste Oil and should be disposed of in accordance with State and Federal Regulations.

The tank is scheduled for removal the first of October, 1993. Removal will be in accordance with MDNR UST Closure Guidance.

Results of site activities suggest the tank as the source of the oil seepage into the pump station unlikely for the following reasons:

- The pump station is located topographically upgradient from the UST.
- Soil sample results are not indicative of a release sufficient to supply free product from the UST to the pump station.



- IR/T failed to reveal anomalies on or around the site indicative of a leak plume, trail or signature.
- Water was not present in the tank. (Given the depth to groundwater 8.5', and depth to the tank bottom, 10.5', and the extreme amount of hydrostatic pressure in the area.)

Additionally, the presence of the sheen at the groundwater/surface interface suggests a problem much more widespread than that of a single source. It is likely, the rising groundwater from the effects of the flooding in the immediate area had a direct affect on the sudden presence of the oil in the pump station.

Report Distribution List:

1. Ms. Kris Davidson, Environmental Specialist
Missouri Department of Natural Resources
Hazardous Waste Program - Superfund Section
P.O. Box 176
Jefferson City, Missouri 65102
2. Mr. Charles Gay, Fire Inspector
St. Louis Fire Department
Fire Prevention Bureau
1421 N. Jefferson
St. Louis, Missouri 63106
3. Mr Bob Ripper
Terminal Railroad Association of St. Louis
700 North Second Street
St. Louis, Missouri 63102

Dec. 22, 1905 Engr #674

ST.

803-214

FIRST

STREET

BROOKLYN

STREET

AREAWAY (Granitoid)

T. R. R. A. of ST. L.
Leased to UNIVERSAL ATLAS
100 25 105' 50 3107 243.

235

1 STORY BRICK

POWER PLANT
CO. of MISSOURI
2 STORY BRICK

WER HOUSE
ON ELECTRIC
STORY BRICK

UST
LOCATION

COMMERCIAL 40' W. ST.
(Vacated Ord. No 50139)

REIN. CONC. EL

339'-6" x 4'
ELEVATOR
(14'-5')

Brick Paving

Reinforced Concrete
Grain Elevator

LOCKER
ROOM

BOUND

ST LOUIS TRANSFER RY.

LEASED FROM CITY OF ST. LOUIS UNDER ORDIN

GHEM CORPORATION
RAIL ROAD - ST. LOUIS

DEPTH IN FEET	DESCRIPTION OF MATERIAL	SAMPLES	STANDARD PENETRATION RESISTANCE (ASTM D 1586)				
			△ - BLOWS PER FOOT				
			10	20	30	40	50
	Black Silty Soils w/Const. Debris and Red Brick Debris to 10'						
- 5 -							
	Groundwater 8.5'						
- 10 -	Terminate Boring 10'	SS 10'					
- 15 -							
- 20 -							
- 25 -							
- 30 -							
- 35 -							

GROUNDWATER DATA		Environmental Operations, Inc.		Boring No. .01
ENCOUNTERED AT 8.5' FEET	FREE WATER NOT ENCOUNTERED DURING DRILLING	DATE: 3/5/93	PROJECT NO: 5780	
FEET AFTER _____ HOURS		DRILLER: GB	LOGGER: GB	
FEET AFTER _____ HOURS		AUGER: SF		
		SURFACE ELEVATION: _____		
		HOLLOW STEM: _____		

DEPTH IN FEET	DESCRIPTION OF MATERIAL	SAMPLES	STANDARD PENETRATION RESISTANCE (ASTM D 1586)				
			△ - BLOWS PER FOOT				
			10	20	30	40	50
	Black Silty Soil w/Const. Debris to 3'						
	Refusal 3'						
- 5 -							
- 10 -							
- 15 -							
- 20 -							
- 25 -							
- 30 -							
- 35 -							

GROUNDWATER DATA

ENCOUNTERED AT FEET
 AT FEET AFTER HOURS
 AT FEET AFTER HOURS

----- FREE WATER NOT ENCOUNTERED
 DURING DRILLING

Environmental Operations, Inc.

2649 Portageville St. Louis, MO 63118

DATE: 8/5/93 PROJECT NO.: 5780

DRILLER: GB LOGGER: GB AUGER: SF

SURFACE ELEVATION: HOLLOW STEM:

Boring No.

.02

DEPTH IN FEET	DESCRIPTION OF MATERIAL	SAMPLES	STANDARD PENETRATION RESISTANCE (ASTM D 1586)				
			△ - BLOWS PER FOOT				
	Black Silty Clay to 8'		10	20	30	40	50
- 5 -							
		SS x 200					
- 10 -	Terminate Boring 8'						
- 15 -							
- 20 -							
- 25 -							
- 30 -							
- 35 -							

GROUNDWATER DATA

ENCOUNTERED AT 8.5' FEET
 AT FEET AFTER HOURS
 AT FEET AFTER HOURS

FREE WATER NOT ENCOUNTERED
 DURING DRILLING

Environmental Operations, Inc.

2649 Postalsville St. Louis, MO 63118

DATE: 8/5/93 PROJECT NO.: 5780


DRILLER: GB LOGGER: GB AUGER: SF

SURFACE ELEVATION:


HOLLOW STEM:

Boring No.

.03

DEPTH IN FEET	DESCRIPTION OF MATERIAL	SAMPLES	STANDARD PENETRATION RESISTANCE (ASTM D 1586)				
			 - BLOWS PER FOOT				
			10	20	30	40	50
	Black Silty Clay w/Const. Debris to 8'						
- 5 -							
		SS 8'					
- 10 -	Terminate Boring 8'						
- 15 -							
- 20 -							
- 25 -							
- 30 -							
- 35 -							

ENCOUNTERED AT _____ FEET AT _____ FEET AFTER _____ HOURS AT _____ FEET AFTER _____ HOURS		FREE WATER NOT ENCOUNTERED DURING DRILLING		Environmental Operations, Inc. 2649 Pastorel St. Louis MO 63116 DATE: 8/5/93 PROJECT NO: 5780 DRILLER: GB LOGGER: GB AUGER: _____ SURFACE ELEVATION: _____ HOLLOW STEM: H.S.		Boring No. .04
---	--	---	--	--	--	------------------------------

DEPTH IN FEET	DESCRIPTION OF MATERIAL	SAMPLES	STANDARD PENETRATION RESISTANCE (ASTM D 1586)			
			 - BLOWE PER FOOT			
			10	20	30	40
	Brown Clay w/Rock Debris To 3'					
	Refusal 3'					
5						
10						
15						
20						
25						
30						
35						

GROUNDWATER DATA

COUNTERED AT _____ FEET
 _____ FEET AFTER _____ HOURS
 _____ FEET AFTER _____ HOURS

FREE WATER NOT ENCOUNTERED
 DURING DRILLING

Environmental Operations, Inc.

2649 Passanogel St. Louis MO 63118

DATE: 8/5/93 PROJECT NO.: 5780


DRILLER: GB LOGGER: GB AUGER: SF

SURFACE ELEVATION:

HOLLOW STEM:

Boring No.

.05

DEPTH IN FEET	DESCRIPTION OF MATERIAL	SAMPLES	STANDARD PENETRATION RESISTANCE (ASTM D 1586)				
			 - BLOWS PER FOOT				
			10	20	30	40	50
	Brown Clay w/Const. Debris to 5'						
5	Refusal 5'						
10							
15							
20							
25							
30							
35							
40							
45							
50							
55							
60							
65							
70							
75							
80							
85							
90							
95							
100							

ENTERED AT FEET FEET AFTER HOURS FEET AFTER HOURS		FREE WATER NOT ENCOUNTERED DURING DRILLING		Environmental Operations, Inc. 2649 Parkview St. Louis MO 63118 DATE 8/5/93 PROJECT NO. 5780 DRIVER: GB LOGGER: GB AUGER: SF SURFACE ELEVATION: HOLLOW STEM:		Spring No. .06
---	--	---	--	--	--	-------------------



8600 Kanis Road
Little Rock, AR 72204-2322
(501) 224-5060

The Gehm Corporation (C-1270)
Post Office Box 65
Boonville, MO 65233

August 16, 1993

ATTN: Mr. Daryl Bowles

Control No. 3520

Sample Description: Two (2) soil received on 8/9/93
Re: Terminal Rr Assoc. of St. Louis Mound & First Streets
(Site) St. Louis, MO Project No. 0116
P.O. No. 080-693 116

Result:

Parameter	Unit	01 8-4-93 0930	02 8-4-93 0945
Total Petroleum Hydrocarbons	mg/Kg	67	23
PCB	mg/Kg	<0.05	<0.05
Benzene	mg/Kg	<0.002	<0.002
Toluene	mg/Kg	<0.002	<0.002
Ethylbenzene	mg/Kg	<0.002	<0.002
m- & p-Xylenes	mg/Kg	<0.002	<0.002
o-Xylenes	mg/Kg	<0.002	<0.002

Method: Modified EPA 418.1, EPA 3550, 8080, 5030, 8020

Remark: Results are presented on an as-received basis.

Enclosure: Chain of custody

AMERICAN INTERPLEX CORPORATION

MWM/tj

By Michael W. McNerlin
Michael W. McNerlin
Laboratory Director



Submitted by: (Name/Telephone/Date) THE GENM CORPORATION 1417 BINGHAM RD., P.O. Box 65 BOONVILLE, MO 65233-0065 DARYL BOWLES 816-882-3485			Lab: (Name/Address/Telephone) AMERICAN INTERPLEX CORP. 8600 KANIS RD. LITTLE ROCK, AR. 72204-2322			Client Name/Project Location: (Contact/Phone #) TERMINAL RR ASSOC. OF ST. LOUIS MOUND { FIRST STREETS (SITE) ST. LOUIS, MO. BOB RIPPER 314-539-4712									
Project No.: 0116		Applicable Regulatory No.: 07143-KB-1331		P.O. # (For Lab) 080-693 116		Sample Signature <i>Daryl L. Bowles</i>									
					ANALYSIS REQUEST										
Sample ID	Matrix	Preservative	Date	Time	BTX (8020)	TPH (418.1)	TPH MO MOD (418.1)	QA-1 (QOWA)	QA-2 (QOWA)	TOG (412.1)	PCB CONT. (8080)	OTHER	OTHER	OTHER	
01	Soil	ICE	8-4-93	0930	X		X				X				
02	Soil	ICE	8-4-93	0945	X		X				X				
COMMENTS/SPECIAL INSTRUCTIONS: - NORMAL TURN AROUND - PLEASE FAX RESULTS TO: DARYL BOWLES 816-882-5766															
Requested by: <i>Daryl L. Bowles</i>					Date: 8-6-93		Time: 1100		Received by: <i>Matha Lurie</i>			Date: 08-07-93		Time: 0915	
Requested by:					Date:		Time:		Received by:			Date:		Time:	



8600 Kanis Road
Little Rock, AR 72204-2322
(501) 224-5060

The Gehm Corporation (C-1270)
Post Office Box 65
Boonville, MO 65233

August 20, 1993

ATTN: Mr. Daryl Bowles

Control No. 3586

Sample Description: One (1) glycol/oil collected by Environmental Operations
received on 8/12/93
Re: Gehm Corp 0111

Result:

<u>Parameter</u>	<u>Unit</u>	<u>5780</u>	<u>Regulatory Level</u>
Ignitability	OF	Non-Ignitable below 212	-
Toxicity Characteristic Leaching Procedure			
Solids	%	100	-
Silver	mg/l	<0.007	5.0
Arsenic	mg/l	<0.2	5.0
Barium	mg/l	2.1	100.0
Cadmium	mg/l	0.019	1.0
Chromium	mg/l	0.0096	5.0
Mercury	mg/l	<0.01	0.2
Lead	mg/l	<0.1	5.0
Selenium	mg/l	<0.2	1.0

Method: EPA 1010, EPA 1311 (Federal Register/Vol. 57, No. 227/November 24, 1992), 3010A, 6010A, 7470

Enclosure: Chain of custody

AMERICAN INTERPLEX CORPORATION

SL/tm

By Steven Lovell
Steven Lovell
Technical Director



8600 Kanis Road
Little Rock, AR 72204-2322
(501) 224-5060

The Gehm Corporation (C-1270)
Post Office Box 65
Boonville, MO 65233

August 20, 1993

ATTN: Mr. Daryl Bowles

Control No. 3521

Sample Description: One (1) oil/glycol received on 8/9/93
P.O. No. 050593 DB

Result:

<u>Parameter</u>	<u>Unit</u>	<u>TANK WASTE</u> <u>8-04-93 1000</u>
Total Halides	mg/Kg	880
PCB	mg/kg	<10
Heat Content	BTU/lb	9480

Method: EPA 9020, 600/4-81/045, ASTM D240

Remark: As requested analysis for Toxicity Characteristic Leaching Procedure and Flash Point was performed on additional sample referenced American Interplex Corporation Control No. 3586. Analysis performed on oil layer only.

Enclosure: Chain of Custody

AMERICAN INTERPLEX CORPORATION

SL/tm

By Steven Lovell
Steven Lovell
Technical Director

[illegible]

CUSTODY TRANSFER RECORD/LABORATORY WORK REQUEST

COMPANY Environmental operations CONTACT Michael Lechae PROJECT NO. 5780
 ADDRESS 2649 Pestalozzi DATE 8-11-93 P.O. NO. _____
 CITY/STATE/ZIP ST LOUIS MO 63118 DUE DATE _____
 PHONE (314) 771-8442 FAX () _____

Page 1 of 1

AICCN 3580

SPECIAL INSTRUCTIONS: ATTN: KRISTA

Reference: Gehm Corp. Case # 0111

SAMPLE IDENTIFICATION

ITEM	LAB NO.	SITE CODE/ SAMPLE DESCRIPTION	DATE COLLECTED	PRESERV.	CONTAINER
1	(1)	70% Glycol / 30% waste oil	8-11-93		Glass 32oz
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					

ANALYSES REQUESTED

<div style="display: flex; justify-content: space-between;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">KLP METALS</div> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Flash Point</div> </div>										COMMENTS
X	X									

ITEMS TRANSFERRED	RELINQUISHED BY	Date	Time	RECEIVED BY	Date	Time	REASON for TRANSFER
				<i>S. H. Smith</i>	8/11/93	6:15 PM	



1417 Bingham Road
Post Office Box 65
Boonville, MO 65233

816-882-3485
816-882-5766 (Fax)

RECEIVED
OCT 28 1993

HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RESOURCES

October 26, 1993

Ms. Kris Davidson, Environmental Specialist
Missouri Department of Natural Resources
Hazardous Waste Program - Superfund Section
P.O. Box 176
Jefferson City, Missouri 65102

RE: UST Removal Closure Report

Dear Ms. Davidson,

We are submitting the enclosed report on behalf of Terminal Railroad Association (TRRA) of St. Louis. The report contains soil sample analysis results as requested by TRRA. I hope you find this information useful in your investigation of the area.

Should you have any questions regarding this report or require additional information, please call me at (816) 882-3485.

Sincerely,

Daryl R. Bowles, CHMM
Director,
Environmental Field Services

cc: Mr Bob Ripper
Terminal Railroad Association of St. Louis
700 North Second Street
St. Louis, Missouri 63102


UST CLOSURE REPORT

for
Terminal Railroad Association



OWNER/FACILITY INFORMATION:

Facility Name:	NONE	UT#	N/A
Address	First & Mound Streets		
County	St. Louis	City	St. Louis, MO
		Zip Code	63102
Telephone/Contact	(314) 539-4712	Mr. Bob Ripper	
Date of Tank Removal	October 11, 1993		



SITE SKETCH SHOWING EXCAVATION OF TANK REMOVAL.

UST CLOSURE REPORT

TRRA, First & Mound Streets, St. Louis, MO

October 26, 1993



PROJECT SYNOPSIS

This underground storage tank removal project is a result of the discovery of oils seeping into a pump station operated by Metropolitan Sewer District (MSD) in St. Louis, Missouri. On July 14, 1993, MSD reported this situation to the MDNR. MSD analytical information revealed PCB levels of less than 50 ppm in the oils seeping into the pump station. Additionally, a sample was obtained from waste oil contained in an underground storage tank present in the area, and owned by Terminal Railroad Association of St. Louis (TRRA). The St. Louis Fire Department (SLFD) notified TRRA on July 28, 1993 and requested the contents of the tank be removed. TRRA was unaware of the existence of the tank prior to notification by the SLFD.

In response to the situation, TRRA initiated and completed the following tasks:

- **Contents of the tank were removed on August 4, 1993.** The tank was completely cleaned and freed of all liquids. The material was containerized on-site in 55 gallon drums for characterization and disposal.
- **An Infrared Thermographic Survey was conducted of the area in an attempt to characterize leak plumes or trails.**
- **Three borings were advanced in the immediate area to determine subsurface soil conditions.** Two soil samples were obtained from the site and submitted to a qualified laboratory for chemical analysis.

The results of these efforts are documented in an ACTIVITIES REPORT dated September 1, 1993 which documents the response efforts and findings of the investigatory activities.

This UST had no record of registration with the Missouri Department of Natural Resources. TRRA indicated no knowledge of the existence of the tank prior to notification by the SLFD. The UST removal project included removal of the soil overburden, removal of the tank, obtaining samples of the soils below the tank, on the down gradient wall and of the soil pile, disposal of the tank as scrap metal, and backfilling the excavation.

1.0 SAMPLE RESULTS

Soil sampling for this UST removal project included sampling below the tank and the down gradient wall. Additionally, one composite sample of excavated soil was obtained.



SAMPLE RESULTS SUMMARY TABLE (in ppm)							
I.D	LOCATION	TPH	BENZENE	TOLUENE	E. BENZENE	XYLENES	PCB's
PIT	FROM BELOW TANK, 2 COMPOSITE POINTS AT EACH END, OF NATIVE SOIL, 12FT. DEPTH	<5	<0.002	<0.002	<0.002	<0.004	<.05
DGW	FROM DOWN GRADIENT WALL (EAST WALL), 10.5 FT. DEPTH	< 5	<0.002	<0.002	<0.002	<0.004	<.05
SP	FROM FOUR COMPOSITE POINTS OF THE EXCAVATED SOILS	66	<0.002	0.002	0.002	0.004	<.05

2.0 LOCATION OF LINES AND UTILITIES

Underground lines or utilities were not discovered in the immediate area during excavation activities. However, an area drawing supplied by TRRA denotes a vitrified pipe extending across the site. (See Sketch Section 5.0)

3.0 FORMER LOCATIONS OF TANK(S)

One 10,000 gallon tank was located at the south end of the eastern most building on the property. The tank overburden consisted of grass and soil. The product line extended north from the tank approximately 10 feet and entered the building through a concrete wall at ground elevation.

4.0 DEPTH & SIZE OF TANK

Tank capacity was 10,000 gallons. Dimensions were 10.5 ft. diameter by 18.5 ft long. The top of the tank was exposed at grade elevation.



5.0 EXCAVATION BOUNDARIES

The excavation was limited to that necessary for tank removal. This excavation extended approximately 4 feet beyond the outer limits of the tank to a depth of 12 feet. Final dimensions of the tank pit excavation was 16 ft wide, 25 feet long and 12 feet deep.

6.0 ABOVE GROUND TANKS & PIPING

There were no above ground tank systems at this site.

7.0 DISTANCE TO WELLS, STREAMS, AND LAKES.

There were no private drinking water wells, or lakes within .5 miles of the tank location. The site is adjacent to the Mississippi River approximately 1,000 feet to the east.

8.0 SOILS DESCRIPTION

Soils encountered was black junk fill with cinders to a depth of 12 feet. Below, native soils consisted of typical river sands/silts.

9.0 PHOTOGRAPHS



PHOTO #1: NORTH EAST VIEW SHOWING TANK AT BEGINNING OF EXCAVATION.




PHOTO #2: BOTTOM AND END OF TANK AFTER REMOVAL.

UST CLOSURE REPORT
TRRA, First & Mound Streets, St. Louis, MO
October 26, 1993



PHOTO #3: BOTTOM OF PIT AND EAST END OF EXCAVATION.




PHOTO #4: SITE CONDITION AT COMPLETION.



11.0 DESCRIPTION OF RESIDUAL CONTAMINATION

Based on odor and appearance, no contaminated media was observed during tank removal operations.

12.0 AMOUNT OF EXCAVATED SOILS

Approximately 30 cubic yards of soil was removed in efforts to remove the tank and affected soils.

13.0 SLUDGE IN TANKS

The tank had previously been emptied of all contents and cleaned. Fifteen drums of Waste Oil/ethylene glycol sludge/liquid was generated for disposal.

15.0 DISPOSAL OF TANK CONTENTS

Tank contents is currently awaiting acceptance for disposal by a licensed and permitted disposal company.

16.0 DISPOSAL OF TANK(S)

The tank was transported to, and disposed of through scrap metal recycling at Grossman Iron & Steel Company, St. Louis, MO.

17.0 FORMER CONTENTS OF TANK(S)

TRRA indicated the tank originally was used to store Fuel Oil.

18.0 DEPTH OF GROUNDWATER

After tank removal, a small amount of water was present in the tank pit area estimated at < 50 gallons. This water was absorbed into the loose soils in the pit during subsequent excavation activities. No other water accumulated or was encountered.



8600 Kanis Road
Little Rock, AR 72204-2322
(501) 224-5060

The Gehm Corporation (C-1270)
Post Office Box 65
Boonville, MO 65233

October 19, 1993

ATTN: Mr. Daryl Bowles

Control No. 4528

Sample Description: Three (3) soil received on 10/13/93
Re: Terminal Railroad Assn. 0119
P.O. No. 101-293 0119

Result:

Parameter	Unit	Pit 10-11-93	DGW 10-11-93	SP 10-11-93
		<u>1020</u>	<u>1022</u>	<u>1025</u>
Total Recoverable				
Petroleum Hydrocarbons	mg/Kg	<5	<5	66
PCB	mg/Kg	<0.05	<0.05	<0.05
Benzene	mg/Kg	<0.002	<0.002	<0.002
Toluene	mg/Kg	<0.002	<0.002	<0.002
Ethylbenzene	mg/Kg	<0.002	<0.002	<0.002
m- & p-Xylenes	mg/Kg	<0.002	<0.002	<0.002
o-Xylene	mg/Kg	<0.002	<0.002	<0.002

Method: Modified EPA 418.1, EPA 3550, 8080, 5030A, 8020

Remark: Results are presented on an as-received basis.

Enclosure: Chain of Custody

AMERICAN INTERPLEX CORPORATION

MWM/tj

By Steven Lovell
Steven Lovell
Technical Director

[illegible]

Petroleum Fuel & Terminal
Foot of Mullanphy Street
St. Louis, Missouri 63102
(314) 621-0522

Reference 11

Charles Gay
Fire Inspector
Fire Prevention Bureau
1421 North Jefferson
St. Louis, Missouri 63106

Dear Mr. Gay

Per our conversation on September 8, 1993. We discovered the leak during our yearly hydro testing of our pipe lines/noises. When we experienced a loss of 25# lb of pressure.

We then started to isolate the most likely place and this would be in the expansion joint at the sea wall. After excavating the site we then found a small pin hole in a 6 inch pipe line. After making the necessary repairs we decided to take this pipe line out of service.

We recovered 2 1/2 bbls of oil/soil to be disposed of. If you feel the need to contact me on this matter please feel free to do so at (314) 621-0522.

Thank you

Randel H. Lewis
Randel H. Lewis
Terminal Manager

HE
9/24/93

Post-It™ brand fax transmittal memo 7671

To	Howard Europe	From	Charles Gay
Co.		Co.	
Dept.		Phone #	
Fax #		Fax #	

MSD ENVIRONMENTAL COMPLIANCE LABORATORY INSTRUMENTATION ANALYSIS

Reference 12

Lab. No. 270 Sample Source: Wet Well Date Received 7-9-93
Sample Date 7-8-93 Time: _____ ☐ Grab ☐ Comp Collected by: _____

☒ IR ☐ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☐ TLC ☐ _____

<input type="checkbox"/> Priority Pollutant	mg/L	(except as noted)	BASE/NEUTRALS: (Cont'd)
<input type="checkbox"/> VOLATILES:		ACIDS: (Cont'd)	
acrolein		2,4-dinitrophenol	hexachlorocyclopentadiene
acrylonitrile		2-nitrophenol	hexachloroethane
benzene		4-nitrophenol	indeno (1,2,3-cd) pyrene
bromodichloromethane		pentachlorophenol	isophorone
bromofom		phenol	naphthalene
bromomethane		2,4,6-trichlorophenol	nitrobenzene
carbon tetrachloride			N-nitrosodimethylamine
chlorobenzene		<input type="checkbox"/> BASE/NEUTRALS	N-nitrosodi-n-propylamine
chloroethane		acenaphthene	N-nitrosodiphenylamine
2-chloroethyl vinyl ether		acenaphthylene	phenanthrene
chloroform		anthracene	pyrene
chloromethane		benzidine	2,3,7,8-tetrachlorodibenzo-p-dioxin
dibromochloromethane		benzo(a)anthracene	1,2,4-trichlorobenzene
1,2-dichlorobenzene		benzo(a)pyrene	
1,3-dichlorobenzene		benzo (b) fluoranthene	<input type="checkbox"/> PESTICIDES:
1,4-dichlorobenzene		benzo (g,h,i) perylene	aldrin
1,1-dichloroethane		benzo (k) fluoranthene	alpha-BHC
1,2-dichloroethane		bis (2-chloroethoxy) methane	beta-BHC
1,1-dichloroethene		bis (2-chloroethyl) ether	gamma-BHC
trans-1, 2-dichloroethene		bis (2-chloroisopropyl) ether	delta-BHC
1,2-dichloropropane		bis (2-ethylhexyl) phthalate	chlordan
1, 3-dichloropropene, cis		4-bromophenyl phenyl ether	4,4'-DDD
1, 3-dichloropropene, trans		butyl benzyl phthalate	4,4'-DDE
ethyl benzene		2-chloronaphthalene	4,4'-DDT
methylene chloride		4-chlorophenyl phenyl ether	dieldrin
1,1,2,2-tetrachloroethane		chrysene	alpha-endosulfan
tetrachloroethane		dibenzo (a,h) anthracene	beta-endosulfan
toluene		3,3-dichlorobenzidine	endosulfan sulfate
1,1,1-trichloroethane		diethyl phthalate	endrin
1,1,2-trichloroethane		dimethyl phthalate	endrin aldehyde
trichloroethene		di-n-butyl phthalate	heptachlor epoxide
vinyl chloride		di-n-octyl phthalate	heptachlor
<input type="checkbox"/> ACIDS:		2,4-dinitrotoluene	
4-chloro-3-methylphenol		2,6-dinitrotoluene	PCB-1016
2-chlorophenol		1,2-diphenylhydrazine	PCB-1221
2,4-dichlorophenol		fluoranthene	PCB-1232
2,4-dimethylphenol		fluorene	PCB-1242
4, 6-dinitro-2-methylphenol		hexachlorobenzene	PCB-1248
		hexachlorobutadiene	PCB-1254
			PCB-1260
			toxaphene

☐ Gas Chromatography results: _____

☐ Thin-Layer Chromatography results: _____

☒ Infrared Spectroscopy (a) methods utilized: Smear test
2920 cm⁻¹ - Triplet - Strong
(b) results: 1460 cm⁻¹ - Singlet - Moderate
1380 cm⁻¹ - Singlet - Moderate

☐ Ultraviolet/Visible Spectroscopy results: _____

☒ Appearance: Dark oil

☒ Odor: Gasoline

☐ API Gravity: _____

☐ Solubilities: _____

☐ Distillation Range: _____

☐ Flash Point: _____

☒ Special Tests: (specify) Dexsil "Clor-n-oil" PCB screening Kit 1/50 Dilution > 50ppm^{PC}
Conclusions Infrared spectra on samples #0434 and #270 are similar.

Date Transmitted: 7/19/93 by: Daniel F. Florida

MSD ENVIRONMENTAL COMPLIANCE LABORATORY
SPECIAL SAMPLE FORM

Reference 13

Lab. No. 886 ☐ Comp ☒ Grab Date Received 8/9/93
 Sample Date 8/9/93 Sample Time 0845 to _____
 Requested by: HEDMOND Collected by: SAME
 Sample Source: MH # MH12 F-6A1 Truck No. _____
 Sampling Location: NEXT TO FLOOD WALL + MULLANPHY
 Reason for sample: TO DETERMINE IF PCB'S PRESENT
☐ Trunk ☐ Sanitary ☐ Stream ☐ Storm ☐ Seepage ☐ STP ☐ Hauler
☐ Industry ☐ Other (explain) _____

Analysis: ☐ except as noted ☐ mg/L ☐ ug/L ☐ mg/kg ☐ % comp ☐ other _____

<input type="checkbox"/> pH _____ (units)	<input type="checkbox"/> F _____	<input type="checkbox"/> Hg _____
<input type="checkbox"/> SPC _____ (umhos/cm)	<input type="checkbox"/> Cl _____	<input type="checkbox"/> As _____
<input type="checkbox"/> ALK _____	<input type="checkbox"/> CN _____	<input type="checkbox"/> Ba _____
<input type="checkbox"/> ACI _____	<input type="checkbox"/> CNA _____	<input type="checkbox"/> Be _____
<input type="checkbox"/> TS _____	<input type="checkbox"/> KJN _____	<input type="checkbox"/> Cd _____
<input type="checkbox"/> SS _____	<input type="checkbox"/> NH ₃ _____	<input type="checkbox"/> Cr _____
<input type="checkbox"/> VSS _____	<input type="checkbox"/> NO ₃ _____	<input type="checkbox"/> Cu _____
<input type="checkbox"/> %V _____	<input type="checkbox"/> NO ₂ _____	<input type="checkbox"/> Fe _____
<input type="checkbox"/> SET _____ (ml/L)	<input type="checkbox"/> PHT _____	<input type="checkbox"/> Pb _____
<input type="checkbox"/> GRE _____	<input type="checkbox"/> PHO _____	<input type="checkbox"/> Ni _____
<input type="checkbox"/> BOD _____	<input type="checkbox"/> SO ₄ _____	<input type="checkbox"/> Se _____
<input type="checkbox"/> COD _____	<input type="checkbox"/> SO ₃ _____	<input type="checkbox"/> Ag _____
<input type="checkbox"/> TOC _____	<input type="checkbox"/> S _____	<input type="checkbox"/> Zn _____
<input type="checkbox"/> PHE _____	<input type="checkbox"/> SUR _____	<input type="checkbox"/> TI _____
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> Sb _____
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> _____
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> _____
<input type="checkbox"/> Color: _____	<input type="checkbox"/> Cr ⁺⁶ _____	<input type="checkbox"/> _____
<input type="checkbox"/> Odor: _____	<input type="checkbox"/> Tot. Hardness _____	
<input type="checkbox"/> Appearance: _____	<input type="checkbox"/> Tot. Chlorine _____	

☐ Organics ☐ IR ☐ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☒ ID
☐ Biological: ☐ Bioassay: ☐ Total Coli: _____ No./100ml
☐ _____ ☐ Microscopic: ☐ Fecal Coli: _____ No./100ml
☐ _____ ☐ Fecal Strep: _____ No./100ml

Remarks: CHECK FOR PCB'S

Date Transmitted: 8/17/93 by: MARIO J. DRPBM

MSD ENVIRONMENTAL COMPLIANCE LABORATORY INSTRUMENTATION ANALYSIS

Lab. No. 886 Sample Source: Manhole F-6A1 (#12) Date Received: 8/9/93
Sample Date: 8/9/93 Time: 0845 ☒ Grab ☐ Comp Collected by: _____

☒ IR ☒ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☐ TLC ☐

☐ Priority Pollutant mg/L (except as noted)

☐ VOLATILES:

acrolein	
acrylonitrile	
benzene	21.0
bromodichloromethane	
bromoform	
bromomethane	
carbon tetrachloride	
chlorobenzene	
chloroethane	
2-chloroethyl vinyl ether	
chloroform	
chloromethane	
dibromochloromethane	
1,2-dichlorobenzene	
1,3-dichlorobenzene	
1,4-dichlorobenzene	
1,1-dichloroethane	
1,2-dichloroethane	
1,1-dichloroethane	
trans-1, 2-dichloroethane	
1,2-dichloropropane	
1, 3-dichloropropane, cis	
1, 3-dichloropropane, trans	
ethyl benzene	32.0
methylene chloride	
1,1,2,2-tetrachloroethane	
tetrachloroethene	
toluene	21.0
1,1,1-trichloroethane	
1,1,2-trichloroethane	
trichloroethene	
vinyl chloride	

☐ ACIDS:

4-chloro-3-methylphenol	
2-chlorophenol	
2,4-dichlorophenol	
2,4-dimethylphenol	
4, 8-dinitro-2-methylphenol	

ACIDS: (Cont'd)

2,4-dinitrophenol	
2-nitrophenol	
4-nitrophenol	
pentachlorophenol	
phenol	
2,4,6-trichlorophenol	

☐ BASE/NEUTRALS

acenaphthene	
acenaphthylene	
anthracene	
benzidine	
benzo(a)anthracene	
benzo(a)pyrene	
benzo (b) fluoranthene	
benzo (q,h,i) perylene	
benzo (k) fluoranthene	
bis (2-chloroethoxy) methane	
bis (2-chloroethyl) ether	
bis (2-chloroisopropyl) ether	
bis (2-ethylhexyl) phthalate	
4-bromophenyl phenyl ether	
butyl benzyl phthalate	
2-chloronaphthalene	
4-chlorophenyl phenyl ether	
chrysene	
dibenzo (a,h) anthracene	
3,3-dichlorobenzidine	
diethyl phthalate	
dimethyl phthalate	
di-n-butyl phthalate	
di-n-octyl phthalate	
2,4-dinitrotoluene	
2,6-dinitrotoluene	
1,2-diphenylhydrazine	
fluoranthene	
fluorene	
hexachlorobenzene	
hexachlorobutadiene	

BASE/NEUTRALS: (Cont'd)

hexachlorocyclopentadiene	
hexachloroethane	
indeno (1,2,3-cd) pyrene	
isophorone	
naphthalene	
nitrobenzene	
N-nitrosodimethylamine	
N-nitrosodi-n-propylamine	
N-nitrosodiphenylamine	
phenanthrene	
pyrene	
2,3,7,8-tetrachlorodibenzo-p-dioxin	
1,2,4-trichlorobenzene	

☐ PESTICIDES:

aldrin	
alpha-BHC	
beta-BHC	
gamma-BHC	
delta-BHC	
chlordan	
4,4'-DDD	
4,4'-DDE	
4,4'-DDT	
dieldrin	
alpha-endosulfan	
beta-endosulfan	
endosulfan sulfate	
endrin	
endrin aldehyde	
heptachlor epoxide	
heptachlor	
PCB-1016	21.0
PCB-1221	
PCB-1232	
PCB-1242	
PCB-1248	21.0
PCB-1254	25.4
PCB-1260	21.0
toxaphene	

☐ Gas Chromatography results: Run Method 203 on Volatiles

GC/FID resembles Diesel Fuel

☐ Thin-Layer Chromatography results: _____

☒ Infrared Spectroscopy (a) methods utilized: Smear test

(b) results: 2920 cm⁻¹ - Triplet - Strong
1460 cm⁻¹ - Singlet - Moderate
1390 cm⁻¹ - Singlet - Moderate
1590 cm⁻¹ - Singlet - Moderate

☐ Ultraviolet/Visible Spectroscopy results: _____

☐ Special Tests: (specify)

Conclusions Both Infrared spectra and GC/FID resemble Diesel Fuel.

MSD ENVIRONMENTAL COMPLIANCE LABORATORY SPECIAL SAMPLE FORM

Lab. No. 887 ☐ Comp ☒ Grab Date Received 8/9/93

Sample Date 8/9/93 Sample Time: 0835 to _____

Requested by: HEIDMANN Collected by: 1-SAME

Sample Source: MH H MH013 F-641 Truck No. _____

Sampling Location: NEXT TO FLOOD WALL AT MULLANPHY

Reason for sample: TO DETERMINE IF PCB'S PRESENT

☐ Trunk ☐ Sanitary ☐ Stream ☐ Storm ☐ Seepage ☐ STP ☐ Hauler
☐ Industry ☐ Other (explain) _____

Analysis: except as noted ☐ mg/L ☐ ug/L ☐ mg/kg ☐ % comp ☐ other _____

<input type="checkbox"/> pH _____ (units)	<input type="checkbox"/> F _____	<input type="checkbox"/> Hg _____
<input type="checkbox"/> SPC _____ (umhos/cm)	<input type="checkbox"/> Cl _____	<input type="checkbox"/> As _____
<input type="checkbox"/> ALK _____	<input type="checkbox"/> CN _____	<input type="checkbox"/> Ba _____
<input type="checkbox"/> ACI _____	<input type="checkbox"/> CNA _____	<input type="checkbox"/> Be _____
<input type="checkbox"/> TS _____	<input type="checkbox"/> KJN _____	<input type="checkbox"/> Cd _____
<input type="checkbox"/> SS _____	<input type="checkbox"/> NH ₃ _____	<input type="checkbox"/> Cr _____
<input type="checkbox"/> VSS _____	<input type="checkbox"/> NO ₃ _____	<input type="checkbox"/> Cu _____
<input type="checkbox"/> %V _____	<input type="checkbox"/> NO ₂ _____	<input type="checkbox"/> Fe _____
<input type="checkbox"/> SET _____ (ml/L)	<input type="checkbox"/> PHT _____	<input type="checkbox"/> Pb _____
<input type="checkbox"/> GRE _____	<input type="checkbox"/> PHO _____	<input type="checkbox"/> Ni _____
<input type="checkbox"/> BOD _____	<input type="checkbox"/> SO ₄ _____	<input type="checkbox"/> Se _____
<input type="checkbox"/> COD _____	<input type="checkbox"/> SO ₃ _____	<input type="checkbox"/> Ag _____
<input type="checkbox"/> TOC _____	<input type="checkbox"/> S _____	<input type="checkbox"/> Zn _____
<input type="checkbox"/> PHE _____	<input type="checkbox"/> SUR _____	<input type="checkbox"/> Ti _____
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> Sb _____
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> _____
<input type="checkbox"/> _____	<input type="checkbox"/> _____	<input type="checkbox"/> _____
<input type="checkbox"/> Color: _____	<input type="checkbox"/> Cr ⁺⁶ _____	<input type="checkbox"/> _____

☐ Odor: _____ ☐ Tot. Hardness _____

☐ Appearance: _____ ☐ Tot. Chlorine _____

☐ Organics ☐ IR ☐ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☒ ID

☐ Biological: ☐ Bioassay: ☐ Total Coli: _____ No./100ml

☐ _____ ☐ Microscopic: ☐ Fecal Coli: _____ No./100ml

☐ _____ ☐ Fecal Strep: _____ No./100ml

Remarks: CHECK FOR PCB'S

Date Transmitted: 8/17/93 by: MARIO J. D. P. R. L.

MSD ENVIRONMENTAL COMPLIANCE LABORATORY INSTRUMENTATION ANALYSIS

Lab No. 887 Sample Source: Manhole F-6A1 (#13) Date Received 8/9/93
Sample Date 8/9/93 Time: 0835 ☒ Grab ☐ Comp Collected by: _____

☒ IR ☒ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☐ TLC ☐ _____

☐ Priority Pollutant mg/L

(except as noted)

☐ VOLATILES:

acrolein	
acrylonitrile	
<input checked="" type="checkbox"/> benzene	<u><1.0</u>
bromodichloromethane	
bromoform	
bromomethane	
carbon tetrachloride	
chlorobenzene	
chloroethane	
2-chloroethyl vinyl ether	
chloroform	
chloromethane	
dibromochloromethane	
1,2-dichlorobenzene	
1,3-dichlorobenzene	
1,4-dichlorobenzene	
1,1-dichloroethane	
1,2-dichloroethane	
1,1-dichloroethane	
trans-1, 2-dichloroethane	
1,2-dichloropropane	
1, 3-dichloropropane, cis	
1, 3-dichloropropane, trans	
<input checked="" type="checkbox"/> ethyl benzene	<u>21.0</u>
methylene chloride	
1,1,2,2-tetrachloroethane	
tetrachloroethene	
<input checked="" type="checkbox"/> toluene	<u><1.0</u>
1,1,1-trichloroethane	
1,1,2-trichloroethane	
trichloroethene	
vinyl chloride	

☐ ACIDS:

4-chloro-3-methylphenol	
2-chlorophenol	
2,4-dichlorophenol	
2,4-dimethylphenol	
4, 6-dinitro-2-methylphenol	

ACIDS: (Cont'd)

2,4-dinitrophenol	
2-nitrophenol	
4-nitrophenol	
pentachlorophenol	
phenol	
2,4,6-trichlorophenol	

☐ BASE/NEUTRALS

acenaphthene	
acenaphthylene	
anthracene	
benzidine	
benzo(a)anthracene	
benzo(a)pyrene	
benzo (b) fluoranthene	
benzo (q,h,i) perylene	
benzo (k) fluoranthene	
bis (2-chloroethoxy) methane	
bis (2-chloroethyl) ether	
bis (2-chloroisopropyl) ether	
bis (2-ethylhexyl) phthalate	
4-bromophenyl phenyl ether	
butyl benzyl phthalate	
2-chloronaphthalene	
4-chlorophenyl phenyl ether	
chrysene	
dibenzo (a,h) anthracene	
3,3-dichlorobenzidine	
diethyl phthalate	
dimethyl phthalate	
di-n-butyl phthalate	
di-n-octyl phthalate	
2,4-dinitrotoluene	
2,6-dinitrotoluene	
1,2-diphenylhydrazine	
fluoranthene	
fluorene	
hexachlorobenzene	
hexachlorobutadiene	

BASE/NEUTRALS: (Cont'd)

hexachlorocyclopentadiene	
hexachloroethane	
indeno (1,2,3-cd) pyrene	
isophorone	
naphthalene	
nitrobenzene	
N-nitrosodimethylamine	
N-nitrosodi-n-propylamine	
N-nitrosodiphenylamine	
phenanthrene	
pyrene	
2,3,7,8-tetrachlorodibenzo-p-dioxin	
1,2,4-trichlorobenzene	

☐ PESTICIDES:

aldrin	
alpha-BHC	
beta-BHC	
gamma-BHC	
delta-BHC	
chlordan	
4,4'-DDD	
4,4'-DDE	
4,4'-DDT	
dieldrin	
alpha-endosulfan	
beta-endosulfan	
endosulfan sulfate	
endrin	
endrin aldehyde	
heptachlor epoxide	
heptachlor	
<input checked="" type="checkbox"/> PCB-1016	<u><1.0</u>
<input checked="" type="checkbox"/> PCB-1221	
<input checked="" type="checkbox"/> PCB-1232	
<input checked="" type="checkbox"/> PCB-1242	
<input checked="" type="checkbox"/> PCB-1248	<u><1.0</u>
<input checked="" type="checkbox"/> PCB-1254	<u>11.7</u>
<input checked="" type="checkbox"/> PCB-1280	<u><1.0</u>
toxaphene	

☐ Gas Chromatography results: Run Method 203 on Volatiles

GC/FID resembles Diesel Fuel

☐ Thin-Layer Chromatography results: _____

☐ Appearance: _____

☒ Infrared Spectroscopy (a) methods utilized: Smear test

(b) results: 2920 cm⁻¹ - Strong - Triplet
1460 cm⁻¹ - Moderate - Singlet
1380 cm⁻¹ - Moderate - Singlet
1590 cm⁻¹ - Moderate - Singlet

☐ Odor: _____

☐ API Gravity: _____

☐ Solubilities: _____

☐ Distillation Range: _____

☐ Flash Point: _____

☐ _____

☐ Special Tests: (specify)

Conclusions Infrared spectra and GC/FID resembles Diesel Fuel

Date Transmitted: 8/13/93

by: Daniel Florido

SPECIAL SAMPLE FORM

Sample Date: 8/9/93 Sample Time: 0623 to 0625

Requested by: HEDMONID Collected by: BAME

Sample Source: MH F MH 14 F-691 Truck No.

Sampling Location: NEXT TO FLUID WALL AT MULLANPHY

Reason for sample: TO DETERMINE IF PCB'S PRESENT

☐ Trunk ☐ Sanitary ☐ Stream ☐ Storm ☐ Seepage ☐ STP ☐ Hauler

☐ Industry ☐ Other (explain) _____

Analysis: ☒ except as noted ☐ mg/L ☐ ug/L ☐ mg/kg ☐ % comp ☐ other _____

☐ pH _____ (units) ☐ F _____ ☐ Hg _____

☐ SPC _____ (umhos/cm) ☐ Cl _____ ☐ As _____

☐ ALK _____ ☐ CN _____ ☐ Ba _____

☐ ACI _____ ☐ CNA _____ ☐ Be _____

☐ TS ☐ KJN ☐ Cd

☐ SS _____ ☐ NH₃ _____ ☐ Cr _____

☐ VSS _____ ☐ NO₂ _____ ☐ Cu _____

☐ %V _____ ☐ NO _____ ☐ Fe _____

☐ SET : _____ (ml/L) ☐ PHT : _____ ☐ Pb : _____

☐ GRE ☐ PHO ☐ NI☐ BOD _____ ☐ SO _____ ☐ Se _____

☐ COD ☐ SO ☐ Ag

☐ TOC ☐ S ☐ Zn

☐ PHE _____ ☐ SUR _____ ☐ TI _____

☐ _____ ☐ _____ ☒ Sb _____

☐ Color: _____ ☐ Cr⁺⁶ _____ ☐ _____

☐ Odor: _____ ☐ Tot. Hardness _____

☐ Appearance: _____ ☐ Tot. Chlorine _____

☐ Organics ☐ IR ☐ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☒ ID

☐ Biological: ☐ Bioassay: ☐ Total Coll: No. /100ml

Fecal Coli: _____ No./100ml

Remarks: CHECK FOR PCB'S

Date Transmitted: 8/17/93 by: MARIO J. DEPRIMO

by: MARIO J. DEPRIM

MSD ENVIRONMENTAL COMPLIANCE LABORATORY INSTRUMENTATION ANALYSIS

Lab. No. 888 Sample Source: Mech. F-6A1 (#14) Date Received 8/9/93
Sample Date 8/9/93 Time 0825 ☒ Grab ☐ Comp. Collected by: _____

☒ IR ☒ GC ☐ LEL ☐ RAD ☐ UV ☐ FLUOR ☐ TLC ☐

☐ Priority Pollutant mg/L (except as noted)

☐ VOLATILES:

acrolein	
acrylonitrile	
<input checked="" type="checkbox"/> benzene	21.0
bromodichloromethane	
bromofom	
bromomethane	
carbon tetrachloride	
chlorobenzene	
chloroethane	
2-chloroethyl vinyl ether	
chloroform	
chloromethane	
dibromochloromethane	
1,2-dichlorobenzene	
1,3-dichlorobenzene	
1,4-dichlorobenzene	
1,1-dichloroethane	
1,2-dichloroethane	
1,1-dichloroethane	
trans-1, 2-dichloroethane	
1,2-dichloropropane	
1, 3-dichloropropane, cis	
1, 3-dichloropropane, trans	
<input checked="" type="checkbox"/> ethyl benzene	21.0
methylene chloride	
1,1,2,2-tetrachloroethane	
tetrachloroethane	
<input checked="" type="checkbox"/> toluene	21.0
1,1,1-trichloroethane	
1,1,2-trichloroethane	
trichloroethane	
vinyl chloride	

☐ ACIDS:

4-chloro-3-methylphenol	
2-chlorophenol	
2,4-dichlorophenol	
2,4-dimethylphenol	
4, 6-dinitro-2-methylphenol	

ACIDS: (Cont'd)

2,4-dinitrophenol	
2-nitrophenol	
4-nitrophenol	
pentachlorophenol	
phenol	
2,4,6-trichlorophenol	

☐ BASE/NEUTRALS

acenaphthene	
acenaphthylene	
anthracene	
benzidine	
benzo(a)anthracene	
benzo(a)pyrene	
benzo (b) fluoranthene	
benzo (g,h,i) perylene	
benzo (k) fluoranthene	
bis (2-chloroethoxy) methane	
bis (2-chloroethyl) ether	
bis (2-chloroisopropyl) ether	
bis (2-ethylhexyl) phthalate	
4-bromophenyl phenyl ether	
butyl benzyl phthalate	
2-chloronaphthalene	
4-chlorophenyl phenyl ether	
chrysene	
dibenzo (a,h) anthracene	
3,3-dichlorobenzidine	
diethyl phthalate	
dimethyl phthalate	
di-n-butyl phthalate	
di-n-octyl phthalate	
2,4-dinitrotoluene	
2,6-dinitrotoluene	
1,2-diphenylhydrazine	
fluoranthene	
fluorene	
hexachlorobenzene	
hexachlorobutadiene	

BASE/NEUTRALS: (Cont'd)

hexachlorocyclopentadiene	
hexachloroethane	
indeno (1,2,3-cd) pyrene	
isophorone	
naphthalene	
nitrobenzene	
N-nitrosodimethylamine	
N-nitrosodi-n-propylamine	
N-nitrosodiphenylamine	
phenanthrene	
pyrene	
2,3,7,8-tetrachlorodibenzo-p-dioxin	
1,2,4-trichlorobenzene	

☐ PESTICIDES:

aldrin	
alpha-BHC	
beta-BHC	
gamma-BHC	
delta-BHC	
chlordane	
4,4'-DDD	
4,4'-DDE	
4,4'-DDT	
dieldrin	
alpha-endosulfan	
beta-endosulfan	
endosulfan sulfate	
endrin	
endrin aldehyde	
heptachlor epoxide	
heptachlor	
<input checked="" type="checkbox"/> PCB-1016	21.0
<input checked="" type="checkbox"/> PCB-1221	
<input checked="" type="checkbox"/> PCB-1232	
<input checked="" type="checkbox"/> PCB-1242	
<input checked="" type="checkbox"/> PCB-1248	21.0
<input checked="" type="checkbox"/> PCB-1254	36.6
<input checked="" type="checkbox"/> PCB-1260	21.0
toxaphene	

☐ Gas Chromatography results: Run Method 203 on Volatiles

GC/FID resembles Diesel Fuel

☐ Thin-Layer Chromatography results: _____

☐ Appearance: _____

☒ Infrared Spectroscopy (a) methods utilized: Smear test

☐ Odor: _____

(b) results: 2920 cm⁻¹ - Strong - Triplet
1460 cm⁻¹ - Moderate - Singlet
1380 cm⁻¹ - Moderate - Singlet
1060 cm⁻¹ - Moderate - Singlet

☐ API Gravity: _____

☐ Solubilities: _____

☐ Ultraviolet/Visible Spectroscopy results: _____

☐ Distillation Range: _____

☐ Flash Point: _____


☐ Special Tests: (specify)

Conclusions Infrared spectra and GC/FID resemble Diesel Fuel.

PRELIMINARY ASSESSMENT
MOUND STREET PCB'S
CITY OF ST. LOUIS, MISSOURI

March 21, 1994

Missouri Department of Natural Resources
Hazardous Waste Program



Prepared By

Don Falls

Don Falls
Environmental
Specialist

Reviewed By

James L. Kavanaugh

James L. Kavanaugh
Chief, Site
Evaluation Unit

Approved By

Edwin Knight

Edwin Knight
Chief
Superfund Section

Rules of

Department of Natural Resources

Division 20—Clean Water Commission

Chapter 7—Water Quality

Title	Page
10 CSR 20-7.010 Prevention of Pollution from Wells to Subsurface Waters of the State (Rescinded July 10, 1980)	3
10 CSR 20-7.015 Effluent Regulations	3
10 CSR 20-7.020 Effluent Regulations (Rescinded July 11, 1980)	10
10 CSR 20-7.030 Water Quality Standards (Rescinded December 11, 1977)	10
10 CSR 20-7.031 Water Quality Standards	10

This copy of the regulations has been printed for use by this agency. It is copied from the Code of State Regulations by permission from the Secretary of State. Subscriptions to the Missouri Register and copies of the Code of State Regulations are available through the Office of the Secretary of State, Administrative Rules Division, P.O. Box 778, Jefferson City, MO 65102. This copy of the Clean Water Commission regulations may not be used as evidence in a court of law. Copies for this purpose must be obtained from the official state records which are available through the Office of the Secretary of State. Recopy of this publication is not permitted without permission from the Secretary of State.

DEPARTMENT OF NATURAL RESOURCES
Division of Environmental Quality
Hazardous Waste Program

TELEPHONE OR CONFERENCE RECORD

File: Mound Street PCB Site

Date: December 29, 1993

TELEPHONE

CONFERENCE

Incoming (X)
Outgoing ()

Field ()
Office (X)

SUBJECT: Mound Street PCB Site, Drinking Water Intakes

PERSONS INVOLVED

Name

Representing

Eddie Starbuck
Don Falls
Sally McConkey
Richard Reed

MDNR, Geology and Land Survey
MDNR, Hazardous Waste Program
Illinois Water Survey
Illinois American Water Company

SUMMARY OF CONVERSATION:

Eddie Starbuck phoned to let me know that she had reviewed her notes from her previous work on the St. Louis Ship site and discovered a note that indicates that there is a drinking water intake located downstream of the Mound Street PCB site (approximately one mile) on the Illinois side of the Mississippi River. Her notes give the location of this intake as the SE 1/4 of the SW 1/4 of Section 11, T2N, R10W.

Eddie said she obtained this information from the Illinois Water Survey approximately two years ago and that their phone numbers are (217) 333-7223 and 333-5482.

ACTION TAKEN

I phoned the Illinois Water Survey and spoke with Ms. Sally McConkey. Ms. McConkey referred me to the Illinois American Water Company at (618) 874-1873. I then phoned Illinois American Water Company and spoke with a Mr. Richard Reed, Assistant Production Supervisor. Mr. Reed informed me that the Illinois American Water Company utilizes two water intake locations, one at Chouteau Island, which is about 10 miles upstream from the Mound Street site, and the intake in Section 11 in East St. Louis, Illinois. Mr. Reed said that their water company serves 19 medium to small communities with a combined service population of approximately 300,000. He also said that the East St. Louis intake has a

Telephone or Conference Record
December 29, 1993
Page 2

production capacity of 30 million gallons a day and is blended with water from the Chouteau Island intake. The East St. Louis intake provides approximately 60% of the total according to Mr. Reed.

FINAL RESULTS:

This information will be incorporated into the Mound Street PCB Preliminary Assessment.

Don Falls
Don Falls
Environmental Specialist

DF:so

DEPARTMENT OF NATURAL RESOURCES
Division of Environmental Quality
Hazardous Waste Program

Reference 18

TELEPHONE OR CONFERENCE RECORD

File: Mound Street PCBs

Date: March 15, 1994

TELEPHONE (314) 882-9880

CONFERENCE

Incoming ()
Outgoing (X)

Field ()
Office (X)

SUBJECT: Fish Consumption From the Mississippi River at St. Louis

PERSONS INVOLVED

Name

Representing

Jack Robinson
Don Falls

Missouri Department of Conservation
MDNR, Hazardous Waste Program

SUMMARY OF CONVERSATION:

I contacted the Missouri Department of Conservation (MDOC) office in Columbia to see if their department has any records concerning annual fish consumption from the Mississippi River at St. Louis. I was referred to Mr. Jack Robinson, a fisheries biologist with the MDOC who is responsible for records of commercial fish harvest on the Missouri, Meramec, and Mississippi Rivers.

Mr. Robinson explained that MDOC did not have information on actual consumption of fish, but only on the numbers caught by commercial fishermen. This information also does not include the numbers of fish taken and eaten by sports fishers.

Mr. Robinson said that he would send me the information on annual harvest from the Mississippi River later in the week. Mr. Robinson suggested that the Missouri Department of Health might have figures on the actual amount of fish consumed because of their previous studies on Chlordane and fish.

FINAL RESULTS:

This information will be included in the Mound Street PCBs Preliminary Assessment.



Don Falls
Environmental Specialist
Hazardous Waste Program

CHECK OF DATA

SPECIE	RIVER= TOTAL		COUNTY=TOTAL									
	SEINE		TRAMMEL NET		GILL NET		HOOP NET		TROT LINE		TOTAL	
	POUNDS	DOLLARS	POUNDS	DOLLARS	POUNDS	DOLLARS	POUNDS	DOLLARS	POUNDS	DOLLARS	POUNDS	DOLLARS
SIATIC CARP	.	.	6063	720	69	8	1810	181	.	.	7642	917
WASSCARP	.	.	10762	2240	947	199	5770	1212	20	4	17499	3675
ADDLEFISH	.	.	2612	784	1361	408	1144	343	50	15	5167	1550
EL	104	19	227	41	331	60
AR	.	.	4083	400	60	6	3171	317	913	91	8227	823
IS CARP	.	.	26708	5075	145	28	60163	11431	.	.	87016	16533
WCKER	.	.	4059	348	550	49	11577	2042	.	.	16186	1457
TURGEON	.	.	4468	1117	1353	338	11150	2788	30	8	17001	4250
KOMFIN	.	.	820	57	.	.	10	1	.	.	830	58
BLUE CAT	.	.	10590	5829	6415	3528	12617	6939	10048	5964	40478	22263
CHANNEL CAT	.	.	7188	3953	570	208	90990	50044	20036	11020	118592	65226
MULLHEAD	.	.	31	7	52	12	502	120	400	96	908	236
PLATHEAD	.	.	4466	2412	1522	822	69536	37849	2905	1549	78429	42352
XRUM	.	.	8919	1338	1412	212	37823	5473	2188	328	50342	7551
CARP	.	.	66367	7964	2727	327	75196	9018	512	61	144752	17370
BUFFALO	.	.	87332	20960	12841	3082	95306	22873	3069	737	198548	47652
TOTAL	.	.	244476	53257	29832	9228	476519	149551	41198	19936	792025	231972
DAYS			2938		450		105907		5930			

Total reported harvest from the Missouri, Mississippi, & St Francis Rivers
in 1992

1992

CHECK OF DATA

Total harvest reported from the Mississippi River

RIVER= MISSISSIPPI COUNTY=TOTAL

SPECIE	SEINE POUNDS DOLLARS	TRAWL NET POUNDS DOLLARS	GILL NET POUNDS DOLLARS	HOOP NET POUNDS DOLLARS	TROT LINE POUNDS DOLLARS	TOTAL POUNDS DOLLARS
ASIATIC CARP	.	2372 285	69 8	930 112	.	3371 405
BRASSCARP	.	6413 1347	437 92	2813 591	.	9663 2029
PADDLEFISH	.	2512 754	1361 408	902 271	50 15	4825 1447
EEL	.	.	.	98 18	227 41	325 58
GAR	.	2590 259	10 1	1440 144	904 90	4944 494
R S CARP	.	14788 2810	145 28	49224 9353	.	64169 12190
SUCKER	.	2109 190	510 46	10471 960	.	13290 1196
STURGEON	.	3024 756	1393 338	7443 1911	30 8	12050 3013
BONFIN	.	820 57	.	10 1	.	830 58
BLUE CAT	.	4465 2454	6040 3322	6832 3758	6875 4881	26212 14417
CHANNEL CAT	.	5078 2793	378 208	72575 39916	10406 10123	94437 53040
BULLHEAD	.	30 7	52 12	270 65	400 96	752 180
FLATHEAD	.	2616 1413	1622 822	47919 25876	2325 1255	54382 29366
DRUM	.	5191 779	1330 199	29340 4401	2110 314	37971 5696
CARP	.	30209 3626	832 100	36154 4338	450 54	67645 8117
BUFFALO	.	37791 9070	11256 2701	66274 15906	3007 722	118328 28599
TOTAL	.	120008 26599	25295 8286	333097 107619	36784 17602	515184 160107
DAYS	.	1371	407	58430	4961	

RIVER= MISSISSIPPI COUNTY=BOONE 11

SPECIE	SEINE POUNDS DOLLARS	TRAWL NET POUNDS DOLLARS	GILL NET POUNDS DOLLARS	HOOP NET POUNDS DOLLARS	TROT LINE POUNDS DOLLARS	TOTAL POUNDS DOLLARS
BLUE CAT	.	.	.	201 111	414 228	414 228
CHANNEL CAT	.	.	.	109 26	492 271	693 381
BULLHEAD	.	.	.	97 52	51 17	109 26
FLATHEAD	.	.	.	217 85	10 1	128 69
DRUM	.	.	.	100 12	.	227 34
CARP	.	.	.	561 135	.	100 12
BUFFALO	.	.	.	1285 368	947 517	561 135
TOTAL	.	.	.	526	108	2232 685
DAYS	.	.	.			

RIVER= MISSISSIPPI COUNTY=BOONE 11

SPECIE	SEINE POUNDS DOLLARS	TRAWL NET POUNDS DOLLARS	GILL NET POUNDS DOLLARS	HOOP NET POUNDS DOLLARS	TROT LINE POUNDS DOLLARS	TOTAL POUNDS DOLLARS
GRASSCARP	.	70 15	.	350 73	.	420 88
PADDLEFISH	.	300 90	300 90	15 4	.	615 184
R S CARP	.	150 28	20 4	.	.	170 52
STURGEON	.	100 25	.	.	.	100 25
BONFIN	.	20 1	.	.	.	20 1
BLUE CAT	.	40 22	.	225 124	.	265 146
CHANNEL CAT	.	160 88	.	560 308	.	720 396
FLATHEAD	.	300 162	.	256 138	.	556 300
DRUM	.	.	.	568 85	.	568 85

MAR 21 '94 15:28

COMMERCIAL FISHING 1992

11:30 THURSDAY, MARCH 17, 1994 21

CHECK OF DATA

CHANNEL CAT	375	206	587	323	2221	1222	3183	1751
FLATHEAD	106	57	764	413	70	38	940	508
DRUM	84	13	185	28	243	30	512	77
CARP	705	85	99	12	20	2	824	99
BUFFALO	1259	302	2036	489	.	.	3895	791
TOTAL	3169	898	5711	1274	2634	1335	9514	3509
DAYS	24		4174		707			

RIVER= MISSISSIPPI COUNTY=ST GENEVIEVE 96

SPECIE	SEINE POUNDS DOLLARS	TRAMMEL NET POUNDS DOLLARS	GILL NET POUNDS DOLLARS	HOOP NET POUNDS DOLLARS	TROT LINE POUNDS DOLLARS	TOTAL POUNDS DOLLARS
GAR	100 10	100 10
Q S CARP	.	12 2	.	70 13	.	82 16
CHANNEL CAT	25 14	25 14
BULLHEAD	125 30	125 30
FLATHEAD	50 27	50 27
DRUM	.	.	.	25 4	.	25 4
CARP	50 6	50 6
BUFFALO	.	30 7	.	15 4	280 67	325 78
TOTAL	.	42 9	.	110 21	630 154	782 184
DAYS	.	3	.	5	115	

RIVER= MISSISSIPPI COUNTY=ST LOUIS 97

SPECIE	SEINE POUNDS DOLLARS	TRAMMEL NET POUNDS DOLLARS	GILL NET POUNDS DOLLARS	HOOP NET POUNDS DOLLARS	TROT LINE POUNDS DOLLARS	TOTAL POUNDS DOLLARS
PADOLEFISH	.	175 52	.	.	.	175 52
GAR	.	33 3	.	.	1 0	34 3
Q S CARP	.	255 48	.	.	.	255 48
STURGEON	.	60 15	.	.	.	60 15
BLUE CAT	.	541 298	.	25 14	235 129	801 441
CHANNEL CAT	.	154 85	.	493 271	2056 1131	2703 1487
FLATHEAD	.	10 5	.	145 78	539 291	694 375
DRUM	.	67 10	.	15 2	68 13	170 25
CARP	.	705 85	.	.	.	705 85
BUFFALO	.	1150 276	.	121 29	900 216	2171 521
TOTAL	.	3150 878	.	799 394	3819 1780	7768 3052
DAYS	.	17	.	293	274	

RIVER= MISSISSIPPI COUNTY=SCOTT 101

SPECIE	SEINE POUNDS DOLLARS	TRAMMEL NET POUNDS DOLLARS	GILL NET POUNDS DOLLARS	HOOP NET POUNDS DOLLARS	TROT LINE POUNDS DOLLARS	TOTAL POUNDS DOLLARS
GRASSCARP	.	35 7	.	.	.	35 7
EEL	10 2	10 2
GAR	50 5	50 5
BLUE CAT	.	50 27	.	.	2379 1308	2429 1336
CHANNEL CAT	.	.	.	122 12	2079 1143	2201 1155
BULLHEAD	20 5	20 5
FLATHEAD	.	.	.	36 19	50 27	86 46

1992
Reported commercial harvest of
licensed fishermen from the Mississippi
River - St. Louis county
dollar value is live-weight
whole sale value.

Memo No. _____

Job No. 010865-370303Date June 3 19 96Time 10:30 a.m.Between (SVC) Michael McCurdy Placed ☒ Rec'd _____And John Schiermann Tel (618) 874-1873 / 874-0523Of IL-American Water CompanySubject Raw water sampling & analysis for East St Louis Intake

Asked if they monitor intake for PCBs, PAH & BETX.

- He stated that they used to monitor the raw water for priority pollutants. Since the EPA switched to SOC analysis of drinking water, they don't analyze the raw water. The exception is they will sample the raw water after a spill in the Mississippi River to determine their PAC dosage during treatment. He stated they have collected raw water samples at the Chouteau Island intake after a spill, but have not at the East St Louis intake.

Asked if they have any raw water data within the last four years.

- He stated the last raw water sampling was probably conducted in 1992 or 1993 and he would fax a copy of analysis reports he finds.

Asked what his title is.

- Water Quality Supervisor

He called back about 11:30am and stated he found some analysis reports for 1992 for PCB and BUA. The reports are attached.

SPECIAL PROBLEM INVESTIGATION
DEPARTMENT OF ENVIRONMENTAL COMPLIANCE

Reference 20

CONTROL NUMBER: 93 07 08
YR MO DAY

CROSS REFERENCE: _____

NEW FILE: BROOKLYN STREET PUMP STATION

TO: HOWARD EDMOND FROM: SI SMITH
DATE ASSIGNED: 07-08-93 TIME: 0800
SUBJECT: OIL IN BROOKLYN STREET PUMP STATION
SPECIAL INSTRUCTIONS: LOCATE SOURCE OF OIL ENTERING BROOKLYN STREET PUMP
STATION AND TAKE CORRECTIVE ACTION

STREET ADDRESS: FOOT OF BROOKLYN STREET ZIP CODE: 63102
NEAREST INTERSECTION: MULLANPHY MAP COORDINATES: 28-D-19

TYPE OF PROBLEM: OIL ENTERING PUMP STATION
TRUNK SEWER: BCH TRTMT PLANT: BISSELL WATER COURSE: N/A

VOLUME: UNKNOWN QUANTITY: UNKNOWN
CAUSE: _____ SOURCE: POSSIBLE LEAKING TANK

PERSON REPORTING: _____ TELEPHONE: _____
CONTACT PERSON: JAMES GARAVAGLIA TELEPHONE: 622-3588

DATE OF INCIDENT: ON GOING RESPONSIBLE PARTY: CITY OF ST. LOUIS
REGULATORY AGENCY CONTACTED: MSD, MODNR, FIRE DEPT, & CITY OF ST. LOUIS
CLEAN UP BY: REACT ENVIRONMENTAL ENGINEERS

COMPLETION DATE: 08-19-93 DAMAGES BILLED (\$): _____

INVESTIGATIVE ACTION SUMMARY: 07-08-93 Call from MSD pump station stating oil was entering Brooklyn pump station. I obtained a sample for analysis. Started looking for possible source. Located an under ground storage tank, which has large hole in the top, on the south side of a vacant building located just west of the pump station and south of Brooklyn Street. A sample of the oil still in this tank was collected. The analysis of the oil from the pump station contained 47 mg/l of 1254 pcb's and the oil from the tank contained 39 mg/l of 1254 pcb's. I contacted Charlie Gay of the Fire Marshall's office and met him at the site on 07-16-93 to show him the problem and to obtain help in finding owner of property. Charlie contacted Chief Horn, informed him of the situation. Chief Horn contacted James Garavaglia of the comptroller's office. We met at site. It was determined at this time that the City of St. Louis is the owner of the east half of the property between 1st St. and the flood wall and Wheeler Ferry Company owns the west half. Cont. Page two

CONCLUSION: It appears at this time an underground storage tank is the cause of this problem. Also the possibility exist of ground saturation of oil from an old Union Electric building.

Copy sent to: _____ Date: _____

SPECIAL PROBLEM INVESTIGATION continued:

Page 2 of 3

<u>93</u>	<u>07</u>	<u>08</u>
Yr	Mo	Day
<u>BROOKLYN PUMP STATION</u>		

DETAILS OF INVESTIGATION: The City is to locate owners of the property and take action on getting area cleaned up. They contacted React Environmental Engineers.

07-16-93 Met with city engineers and React to determine what is to be done. At the present time React is placing booms in the wet well of the pump station to soak up the oil entering. It was not determined at this time what to do with the underground tank. React wanted to trench along the sewer entering the pump station but due to the high water table and the possibility of causing a major problem with the flood waters no trench at this time.

07-26-93 Returned to the pump station to follow up on the clean up. React did not place booms in station they only put absorbent pads. The pump station maintenance crew removed the pads to prevent them from being pulled into the pumps since they were not tied down. I contacted the city comptroller and informed him of this problem. React contacted me and I told them that they had to use booms inside the station and tied to prevent any possibility of being pulled into the pumps or move outside station into the first manhole up stream to collect the oil.

07-27-93 Met Chief Horn at the pump station. React has installed boom and they are tied. Checked the underground tank and nothing has been done to the tank. It still has oil standing in the bottom. It appears that there could be at least 6 to 8 inches of oil in the tank. There is still a small oil sheen on the water entering the station. Chief Horn is to find out what is to be done with the tank and let me know.

07-28-93 Met Chief Horn and Clifford Trice, chief engineer for Terminal Railroad Association at the site of the underground tank. It has been determined that the property belongs to Terminal Railroad. They are to take steps to remove the tank.

07-29-93 Received call from Daryl Bowles, Gehm Corp, rep for Terminal Railroad requesting copies of analysis on pump station and tank. They are to preform an infrared test on area to try and determine just where the oil is entering the sewer. Test is to be done first week of August. Copies of analysis sent.

08-03-93 Made follow up on progress of clean up. The area around the tank has been cleaned up and graded but the opening to the tank has been covered. No way at this time to tell if tank has been pumped. The booms at the pump station do not appear to have been serviced since they were last installed.

TE

SPECIAL PROBELM INVESTIGATION continued

PAGE 3 of 3
93 07 08
Yr Mo Day
BROOKLYN PUMP STATION

08-04-08 Met with Terminal Railroad, consulting company and fire department
underground tank is being pumped out today. Tank will be removed as soon as the
water level goes down. The infrared pictures that were taken do not indicate
the source of oil in pump station is from tank. They did indicated a possible
location of another underground tank on the city property just south of Mound
Street. Fire department was notified.

08-08-93 1015 Hrs Received call from Chief Horne requesting my presents at 1st
& Mullanphy. Three manholes were located along the flood wall which contained
a large amount of oil. Could not determine at this time where oil is coming
from. The manholes are holding water. I will return 08-09-93 to collect samples
to find out if pcb's are present. There is some question as to the manholes
belonging to MSD or the City.

08-09-93 Collected oil samples from all three manholes. Waiting on analysis.

08-10-93 Met Charlie Gay of fire department. He wanted to know where the
manholes were located that contain this last source of oil. Also wanted to
look at clean up that was preformed on the underground tank. The tank has been
pumped and washed out. The oil has been remove.

08-17-93 The analysis of the samples taken from the manholes indicated they
also contained a small amount of pcb 1254. These manhole belong to the city
and Fire Marshall Horne was notified of this fact and also the results of
the analysis on the manholes. The pads at the pump station have not been
changed as of 08-17-93. Chief Horne was also informed of this situation.

08-19-93 The pads at the pump station were changed yesterday 08-18-93. The
City of St. Louis is now taking care of having this problem cleaned up. *JK*

STATE OF MISSOURI
DEPARTMENT OF NATURAL RESOURCES
MEMORANDUM

DATE: December 29, 1993
TO: Don Falls, ^{MS} Environmental Specialist, HWP, DEQ
FROM: Edith Starbuck, Geologist, Environmental Geology Section, DGLS
SUBJECT: PA/SI Geology Report for the Mound Street Site, St. Louis City

Enclosed is my report on the geologic and hydrologic considerations for the Mound Street Site. The report addresses specific components of the HRS. Please let me know if you have any questions or comments or need additional information.

RECEIVED
'94 JAN 3 AM 11 27
HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RESOURCES

3.0.1 General Considerations

The Mound Street site is located on the riverfront in the City of St. Louis. It is east of Second Street between Mound and Brooklyn Streets.

3.0.1.1 Groundwater target distance limit

The site is located on a narrow strip of alluvium between an area of limestone bedrock and the Mississippi River. (Ref. 1) The groundwater within the alluvium will move generally in the direction of the river, that is, to the east or southeast, and it will eventually discharge to the river. During unusually high river stages, the groundwater may temporarily flow away from the river. Since no confining layer is known to exist between the alluvial aquifer and the bedrock of Mississippian limestone (Ref. 4, p. I-136), the groundwater target distance should extend for a four mile radius from the site.

3.0.1.2 Aquifer boundaries

The shallowest material at the site is fill material. Its thickness is unknown, but is estimated at 15 to 18 feet.

The alluvium consists of a mixture of stratified sediments deposited by the river. Based on findings at a nearby site, the alluvium is made up of clay, and silty clay in the top 10 to 30 feet, but becomes generally coarser with depth, becoming silty sand and sand. Lenses of gravel can be found. (Ref. 2, p. 3-19 to 3-33) The total thickness of the alluvium is estimated at approximately 80 feet. The alluvial aquifer can be expected to yield large quantities of fresh water. (Ref. 15, p. 21) The depth to water will be approximately 20 feet. The bedrock is Mississippian aged limestone.

The Mississippian System in this area is made up of a sequence of limestone, cherty limestone, and sandy or shaley limestones. This system includes, in descending order; the Ste. Genevieve Limestone, St. Louis Limestone, Salem Formation, Warsaw Formation, Burlington-Keokuk Limestone, and the Fern Glen Formation. (Ref. 13) The Salem and Warsaw formations are generally shaley limestones and do contain shale beds in the St. Louis area. (Ref. 14, p. 101-110) However, the thickness and position of shale horizons varies within this area (Ref. 14, figs 88, 89, 91, 92) The shallowest reliable aquitard in the area is the Maquoketa Shale at the top of the Ordovician System. The Mississippian aquifer might yield small quantities of fresh water in the target area, (Ref. 15, Ref. 16) but very little data is available. Any groundwater below the Maquoketa is expected to be mineralized. (Ref. 15, Ref. 16)

3.0.1.2.1 Aquifer interconnections

Drilling at a nearby site encountered no confining material between the alluvium and bedrock. (Ref. 4, p. I-136) The bedrock and alluvium can be considered one aquifer for HRS purposes.

3.0.1.2.2 Aquifer discontinuities

The alluvial aquifer is bounded by the limits of its deposition within the target area. Bedrock faulting in the area does not completely transect the Mississippian aquifer. No aquifer discontinuity exists within the target area.

3.1 Likelihood of release

3.1.2 Potential to release

3.1.2.2 Net precipitation

The assigned net precipitation factor value for the site is 3. (Ref. 3, figure 3-2)

3.1.2.3 Depth to aquifer

The depth to groundwater at the site is approximately 20 feet. The alluvial sediments at this depth may not be good aquifer material, however, the depth at which the alluvial material is saturated should be considered the aquifer. The depth to aquifer factor value is 5. (Ref. 3, table 3-5)

3.1.2.4 Travel time

The hydraulic conductivity for the shallow part of the alluvium consisting of silty clay and clay has been calculated at 9.9×10^{-6} . (Ref. 4, p. 6-26) Its thickness ranges from 10 to 30 feet. The travel time factor value is 15. (Ref. 3, table 3-7)

3.3.1 Nearest well

There is not believed to be any groundwater use within the target area. (Ref. 4, p. I-136; Ref. 5; Ref. 6). The nearest well factor value is 0. (Ref. 3, table 3-11)

3.3.4 Wellhead protection area

There is no wellhead protection area within the target area.

4.1.1.1 Definition of hazardous substance migration path for overland/flood migration component

The site is located on top of the flood wall constructed to protect the area from flooding. No channels or ditches were observed crossing the site. (Ref. 7) Much of the site is relatively flat. The eastern edge of the area slopes to the east, toward the river. The site is less than 300 feet from the river.

4.1.1.2 Target distance limit

- ✓ The target distance limit should include the Mississippi River from the area downgradient from the site to a point fifteen miles downstream. This should be at approximately Mississippi River mile marker 166.

4.1.2.1.2.1 Potential to release by overland flow

4.1.2.1.2.1.2 Runoff

- ✓ The drainage area for the site is less than 50 acres. (Ref. 8) the drainage area value is 1. (Ref. 3, table 4-3) The soil at the site appeared to be somewhat coarse textured. (Ref. 7) A moderate infiltration rate would be expected. The soil group designation is B. (Ref. 3, table 4-4) The two-year, 24-hour rainfall for the area is approximately 3.5 inches. (Ref. 9)

The rainfall/runoff value is 4. (Ref. 3, table 4-5) The runoff factor value is 1. (Ref. 3, table 4-6)

4.1.2.1.2.1.3 Distance to surface water

Since no ditches or channels were noted, the distance to surface water is estimated as a straight line between the site and the river. This distance is about 300 feet. (Ref. 8) The distance to surface water factor value is 20. (Ref. 3, table 4-7)

4.1.2.1.2.2 Potential to release by flood

4.1.2.1.2.2.2 Flood frequency

- ✓ The site is located on top of a flood wall constructed to withstand a 500-year flood. It is elevated above the floodplain and therefore, the flood frequency factor value is 0. (Ref. 3, table 4-9)

4.1.2.3.1 Nearest intake

On the Missouri side of the Mississippi River, the nearest intakes are approximately 10 miles upstream from the site and 126 miles downstream. (Ref. 11) Information from the Illinois Water Survey indicates that there is a public water supply intake within the target area on the Illinois side. This intake is in the SE 1/4 of the SW 1/4 of section 11, T.2 N., R.10 W. in St. Clair County, Illinois. (Ref. 10) This would be less than one mile downstream from the site.

The Mississippi River is a very large river with an average flow greater than 100,000 cfs. (Ref. 12, p. 180) The assigned dilution weight is 0.00001. (Ref. 3, table 4-13) Because of this small dilution weight, the intake factor value is 0. (Ref. 3, p. 51613)

REFERENCES

1. Geologic Map of St. Louis City and County, Missouri, K.G. Brill, DGLS, 1991.
2. Remedial Investigation Report for the St. Louis Site, prepared for U.S. Department of Energy under the Formerly Utilized Site Remedial Action Program by Bechtel National, June 1991.
3. Federal Register, vol. 55, No. 241.
4. Radiological, Chemical, and Hydrogeological Characterization Report for the St. Louis Downtown Site in St. Louis, Missouri, prepared for the U.S. Department of Energy under the Formerly Utilized Site Remedial Action Program by Bechtel National, September, 1990.
5. Census of Missouri Public Water Systems, 1991, DEQ.
6. Well records for the area on file at DGLS.
7. Field observations, 10/6/93.
8. Granite City 7.5 minute topographic quadrangle, U.S. Geological Survey, 1954, photorevised 1982.
9. Rainfall Frequency Atlas of the United States, Technical Paper No. 40, U.S. Department of Commerce.
10. Telephone messages from Dorothy Waller, Illinois Water Survey, June 11, and 12, 1992.
11. Census of Missouri Public Water systems, 1991, DEQ.
12. Water Resources Data, Missouri, Water Year 1989, U.S. Geological Survey Water-Data Report MO-89-1.
13. Geologic Map of St. Louis City and County, Missouri, K.G. Brill, DGLS, 1991.
14. Paleozoic Succession in Missouri-Part 4, Mississippian System, Report of Investigation No. 70, Part 4; Thomas L. Thompson; DGLS, 1986.
15. Water Resources, St. Louis Area, Missouri, Water Resources Report No. 30; Don E. Miller, et. al.; DGLS/USGS; 1974.
16. Groundwater Areas Map in Groundwater Maps of Missouri; Missouri Geological Survey and Water Resources; 1963.

DEC-02-53 THU 09.43 ID.WATER RESOURCES

TEL NO. 314-751-8473

4656 F02


shown on this map to determine when actuarial rates apply to structures in the zones where elevations or depths have been established

To determine if flood insurance is available in this community, contact your local insurance agent or call the National Flood Insurance Program, at (800) 638-6620, or (800) 424-8872.



APPROXIMATE SCALE

1000 0 1000 FEET



NATIONAL FLOOD INSURANCE PROGRAM

FIRM FLOOD INSURANCE RATE MAP

CITY OF
ST. LOUIS, MISSOURI
INDEPENDENT CITY


PANEL 10 OF 40
(SEE MAP INDEX FOR PANELS NOT PRINTED)

COMMUNITY-PANEL NUMBER
290385 0010 A

EFFECTIVE DATE:
JULY 10, 1979



U.S. DEPARTMENT OF HOUSING
AND URBAN DEVELOPMENT
FEDERAL INSURANCE ADMINISTRATION



270000 0010 H

7/16/79

ST. LOUIS, MO.


RIVER
MILE
• 181

1" = 1,000'

RIVER MILE • 182

CORPORATE LIMITS

MARTIN
LUTHER
KING





STATE OF MISSOURI
OFFICE INFORMATION MEMO

DATE 6/11/92 TIME 3:30 PM

TO Edie
FROM Dorothy Waller
PHONE NO 217-333-7223
DEPARTMENT OR DIVISION ILL Wtr Survey
RECEIVED BY KB

☒ Called/was here to see you ☐ Wants to see you ☐ Will call again
☒ Wants you to call ☐ URGENT ☐ Returned your call
☐ Prepare for my signature ☐ For your information ☐ Review
☐ Take necessary action ☐ For your signature ☐ As requested

REMARKS MESSAGES

Pub. Wtr. Supply Intakes on Miss. River.
SE of St. Louis.
(2) in East St. L. - Illinois American Wtr Co.
T4N-R10W-S.25 (SW corner)
T2N-R10W-S.11 (SE corner of SW 1/4)
(1) in Alton
T5N-R10W-S.4 (SE corner)
none in Illinois (C) (217) 333-5482

MO 995-9002 (3-88)

Surface Wtr. Sect + Sally & Broeren

STATE OF MISSOURI
DEPARTMENT OF NATURAL RESOURCES
MEMORANDUM

DATE: January 5, 1994
TO: Don Falls, Environmental Specialist, HWP, DEQ
FROM: Edith Starbuck, Geologist, DGLS
SUBJECT: Existence of karst near the Mound Street Site

Sinkholes and caves can be found in the Mississippian bedrock within the target area. The sinkholes are represented as closed depressions on the Granite City topographic map. Also, the existence of karst features is discussed in the DGLS publication, "Engineering Geology of St. Louis County, Missouri". The karst aquifer probably does not directly underlie the site, however, and it is not likely to be affected by contaminant migration from the site. If the site is actually on the bedrock residual area, any water that percolates down into it should move toward the alluvial aquifer since groundwater movement is toward the river.

Please let me know if you have any further questions about the site geology (314)368-2136.

ES:kb

RECEIVED
94 JAN 7 AM 11 06
HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RESOURCES

MOUND STREET SITE STRATIGRAPHY

	Stratigraphic Unit	Composition	Thickness (ft.)	Remarks
Quaternary System	Alluvium	Clay, silt, sand, gravel	80	High yield aquifer
Mississippian System	Ste. Genevieve Formation	Silty to sandy limestone	470 - 530	Yields small to moderate quantities of water
	St. Louis Limestone			
	Salem Formation			
	Burlington-Keokuk Limestone	Cherty limestone	240	
	Fern Glen Formation	Red limestone and shale	100	
	Chouteau Group	Limestone, shale and siltstone	0 - 122	
Devonian System	Sulphur Springs Group	Sandstone and limestone	0 - 60	
	Grassy Creek Shale	Carbonaceous Shale	0 - 50	
Silurian System		Cherty limestone	0 - 200	
Ordovician System	Maquoketa Shale	Silty, limey, or dolomitic shale	150	Confining layer

RECEIVED
 JAN 6 1994
 HAZARDOUS WASTE PROGRAM
 MISSOURI DEPARTMENT OF
 NATURAL RESOURCES

----- Header Data -----

Log # 019835 Owner:NORTHWESTERN COOPERAGE CO St:MO Cnty:ST. LOUIS
 Alias: SE SE NE TRS: S02 T45N R07E
 Type well:Private Well Lat.:38,40,23.648N
 Type log: S Long.:90,11,25.660W
 Driller:HAVERSTICK WELL CO Date: / Quad:38090C6
 Driller License No: Confidential:N Release Dt. /
 Logger:C.E. ROBERTSON Date:08/1961
 Elev.: 420 Elev.S Yield: 260 SWL:(a) H2O @:
 T.D.: 80 base: DrDwn: 31 SWL:(b)

Bedrock at: 75 Samples saved:N Int. cored: 0 to 0
 Top Fm.:HOLOCENE ALLUVIUM
 Bot Fm.:MISSISSIPPIAN SYSTEM
 Problems:
 Remarks:

----- Construction Data -----

Log #:019835 Date Completed: /

CASING: Dpth: 59 Diam: 8.00 I/O:0 Sz. Hole: 0.00 Sz. Below: 0.00
 0 0.00
 0 0.00
 0 0.00

GROUT:	Type	Rig	Methd	Dt	Abnd	Plug Date	Top	Bottom
				/		/	0	0

PUMP:	Cap	Type	Set at	TDH	Scrn Typ	Size	Lgth	Slot
	0		0	0		0	0	0

Well Treat	Type	Dev	Typ	Compl	Perf. Interval	Tube Pres.	Oil	Gas
					Top: 0 Bot: 0			

Open Top:HOLOCENE ALLUVIUM
 Formations Bot:MISSISSIPPIAN SYSTEM
 Other data sources:
 Remarks:

----- Stratigraphy Data -----

Log #:	019835	--Lith--	-----Minerals-----							
Top	Base Name	Pr	Sc	Mn	Pri	Oc	Sec	Oc	Mnr	Oc
0	75 HOLOCENE ALLUVIUM	CL	SD	GR		0		0		0
75	80 MISSISSIPPIAN SYSTEM	LS	SD			0		0		0

Printed on 12/30/93 at 10:45:40.

----- Header Data -----

Log # Owner:BELCHER HOTEL St:MO Cnty:ST. LOUIS
 001655 Alias type: Facility ID NE SW SW TRS: S13 T45N R07E
 Alias:010000 Lat.:
 Type well:Noncommunity Public Well Long.:
 Type log: D Quad:UNKNOWN
 Driller: Date: /
 Driller License No: Confidential:N Release Dt. /
 Logger: Date: /
 Elev.: 420 Elev.S Yield: 150 SWL:(a) H2O @:
 T.D.: 2200 base: DrDwn: 000 SWL:(b)

Bedrock at: 0 Samples saved:N Int. cored: 0 to 0
 Top Fm.:
 Bot Fm.:
 Problems:
 Remarks:

----- Construction Data -----

Log #:001655 Date Completed:09/1951

CASING: Dpth: 80 Diam:160.0 I/O:0 Sz. Hole: 0.00 Sz. Below: 0.00
 0 0.00
 0 0.00
 0 0.00

GROUT:	Type	Rig	Methd	Dt Abnd	Plug Date	Top	Bottom
				/	/	0	0

PUMP:	Cap	Type	Set at	TDH	Scrn Typ	Size	Lgth	Slot
	0		0	0		0	0	0

Well Treat	Type Dev	Typ Compl	Perf. Interval	Tube Pres.	Oil	Gas
			Top: 0 Bot: 0			

Open Top:
 Formations Bot:
 Other data sources:
 Remarks:

----- Stratigraphy Data -----

Log #:	001655	--Lith--		-----Minerals-----					
Top	Base Name	Pr	Sc Mn Pri	Oc	Sec	Oc	Mnr	Oc	
0	230 ST LOUIS LIMESTONE	LS	SH	0		0		0	
230	350 SALEM FORMATION	LS	CH	0		0		0	
350	380 UNKNOWN	SH		0		0		0	
380	460 WARSAW FORMATION	LS	SH	0		0		0	
460	630 KEOKUK-BURLINGTON LS. UNDIFF	LS	SH	0		0		0	
630	720 FERN GLEN FORMATION	LS	SH CH	0		0		0	
720	760 KINDERHOOK SHALE	SH		0		0		0	
760	880 SILURIAN SYSTEM	LS		0		0		0	
880	1040 MAQUOKETA SHALE	SH	LS	0		0		0	
1040	1180 KIMMSWICK LIMESTONE	LS		0		0		0	
1180	1240 DECORAH GROUP	LS	CH	0		0		0	
1240	1370 PLATTIN LIMESTONE	LS		0		0		0	
1370	1502 JOACHIM DOLOMITE	SH	LS	0		0		0	
1502	1640 ST. PETER-EVERTON FMS. UNDIFF	SS		0		0		0	
1640	2200 CAMBRIAN SYSTEM	SS	LS	0		0		0	

----- Header Data -----

Log # Owner: CUPPLES COMPANY St: MO Cnty: ST. LOUIS
 003616 SE NE NW TRS: S02 T45N R07E
 Alias: Lat.:
 Type well: Private Well Long.:
 Type log: S Quad: UNKNOWN
 Driller: WISE Date: 05/1936
 Driller License No: Confidential: N Release Dt. /
 Logger: GROHSKOPF Date: /
 Elev.: 421 Elev.S Yield: 15 SWL:(a) H2O @:
 T.D.: 885 base: DrDwn: 0 SWL:(b)

Bedrock at: 0 Samples saved: N Int. cored: 0 to 0
 Top Fm.: ST LOUIS LIMESTONE
 Bot Fm.: SILURIAN SYSTEM
 Problems:
 Remarks:

----- Stratigraphy Data -----

Log #: 003616		--Lith--		-----Minerals-----				
Top	Base Name	Pr	Sc Mn Pri	Oc	Sec	Oc	Mnr	Oc
0	210 ST LOUIS LIMESTONE	LS	SH	0		0		0
210	325 SALEM FORMATION	LS	CH SH	0		0		0
325	435 WARSAW FORMATION	SH	LS CH	0		0		0
435	595 KEOKUK-BURLINGTON LS. UNDIFF	CH	LS	0		0		0
595	700 FERN GLEN FORMATION	CH	LS SH	0		0		0
700	735 CHOATEAU GROUP	LS	CH	0		0		0
735	755 CHATTANOOGA SHALE	SH		0		0		0
755	885 SILURIAN SYSTEM	LS	SD DL	0		0		0

Printed on 12/30/93 at 10:47:17.

----- Header Data -----

Log # 002748 Owner: FISHER CHEMICAL CO St: MO Cnty: ST. LOUIS
 Alias: NW SE SE TRS: S02 T45N R07E
 Type well: Private Well Lat.:
 Type log: S Long.:
 Driller: WISE Quad: UNKNOWN
 Driller License No: Date: 08/1933 Confidential: N Release Dt. /
 Logger: GLEASON Date: /
 Elev.: 430 Elev. S Yield: 30 SWL: (a) H2O @:
 T.D.: 210 base: DrDwn: 150 SWL: (b)
 Bedrock at: 45 Samples saved: N Int. cored: 0 to 0
 Top Fm.: ST LOUIS LIMESTONE
 Bot Fm.: ST LOUIS LIMESTONE
 Problems:
 Remarks:

----- Construction Data -----

Log #: 002748 Date Completed: 08/1933

CASING: Dpth: 30 Diam: 8.00 I/O: 0 Sz. Hole: 0.00 Sz. Below: 8.00
 0 0.00
 0 0.00
 0 0.00

GROUT:	Type	Rig	Methd	Dt	Abnd	Plug	Date	Top	Bottom
				/		/		0	0

PUMP:	Cap	Type	Set at	TDH	Scrn	Typ	Size	Lgth	Slot
	0		0	0			0	0	0

Well Treat	Type	Dev	Typ	Compl	Perf.	Interval	Tube	Pres.	Oil	Gas
					Top:	0 Bot: 0				

Open Top: ST LOUIS LIMESTONE
 Formations Bot: ST LOUIS LIMESTONE
 Other data sources:
 Remarks:

----- Stratigraphy Data -----

Log #:	002748	--Lith--		-----Minerals-----						
Top	Base Name	Pr	Sc	Mn	Pri	Oc	Sec	Oc	Mnr	Oc
45	210 ST LOUIS LIMESTONE	LS	CH			0		0		0

Printed on 12/30/93 at 10:46:32.

STATE OF MISSOURI
DEPARTMENT OF NATURAL RESOURCES
MEMORANDUM

DATE: January 5, 1994
TO: Don Falls, Environmental Specialist, HWP, DEQ
FROM: Edith Starbuck, Geologist, DGLS
SUBJECT: Existence of karst near the Mound Street Site

Sinkholes and caves can be found in the Mississippian bedrock within the target area. The sinkholes are represented as closed depressions on the Granite City topographic map. Also, the existence of karst features is discussed in the DGLS publication, "Engineering Geology of St. Louis County, Missouri". The karst aquifer probably does not directly underlie the site, however, and it is not likely to be affected by contaminant migration from the site. If the site is actually on the bedrock residual area, any water that percolates down into it should move toward the alluvial aquifer since groundwater movement is toward the river.

Please let me know if you have any further questions about the site geology (314)368-2136.

ES:kb

RECEIVED
'94 JAN 7 AM 11 06
HAZARDOUS WASTE PROGRAM
MISSOURI DEPARTMENT OF
NATURAL RESOURCES

SOKKIA™

LEVEL
BOOK

MOUND STREET PCB

ST LOUIS, MO

CERCLIS ID NO M015009B682

NO. 1315250

1

TI
50
ar
pr

② Site Recon visit - Dec 6, 1995

0700 Leave SUE Overland Park, KS Office

1100 Arrive SUE St Louis Office

pick up Kevin Harries

1130 Leave SUE St Louis Office

1200 arrive site

begin making site schematic

1215 Herman arrives at site

interview him (McKinley/iron rep)


1230 Herman left site

temperature 30's

mostly cloudy, slight breeze

Michael W. McCurdy
12/6/95

Map A ③



Michael W. McCurdy
12/6/95

④

- 12:32 ① looking north at south
end of property
- 12:32 ② looking north along gravel
road
- 12:33 ③ looking NNE toward flood wall
- 12:34 ④ looking south at north end
of property
- 12:35 ⑤ looking east from west side
- 12:37 ⑥ looking SSE from west side
- 12:38 ⑦ abandoned gravel elevators
to N (TRRA property)

Herman Gollman interview 12:15-12:30

property size is approx 1.5 acres

basement may be as deep as 12-14'

drops into the basement -

don't know if removed

concrete wall or floor

deded abandoned pump house

to city for bike path

own since property east of

site (between gravel road &

flood wall)

property originally purchased from

UE for salvage of equipment

no other operations conducted

at the site

[see map on preceding page
for picture location
and viewing direction]

Michael W. McLundy
12/6/95

⑤

Michael W. McLundy
12/6/95

⑧

could not locate RW 12 & 11

12:58

⑬

looking west at well

from Corps map
found identified MHs from

Corps map
WE MH abandoned
other MH abandoned

inlet F of Corp map is

for surface runoff -

some runoff from site may

enter this storm drain -

however, it appears most

surface runoff would travel

east & south

noted a dog in the Petroleum

Fuel & Terminal main yard


12:59

⑭

looking NNE at well

Michael W. McLindley
12/6/95


Map C ⑨



Michael W. McLindley
12/6/95

⑩

Map D ⑪



13:07 ⑮ looking nne at abandoned pump house

13:09 ⑯ looking sse at abandoned pump house

Michael W. McCloudy
12/6/95

Michael W. McCloudy
12/6/95

(12)

13:20 leave site

13:55 arrive S/E St Louis Office

drop off Kevin Harris

14:00 leave S/E St Louis Office

18:30 arrive S/E Overland Park, KS

Office

Michael W. McCurdy
12/6/95

(13)

Michael W. McCurdy
4/1/96

**REMEDIAL PLANNING ACTIVITIES AT SELECTED
UNCONTROLLED HAZARDOUS SUBSTANCE DISPOSAL SITES
IN THE ZONE OF REGIONS VI, VII, AND VIII**

U. S. EPA CONTRACT NO. 68-W9-0032

FIELD SAMPLING PLAN

**MOUND STREET PCB SITE
ST. LOUIS, MISSOURI**

Revision 1

Work Assignment No.: 37-7JZZ

March 4, 1996

Prepared for:
U.S. Environmental Protection Agency

Prepared by:
Sverdrup Corporation, Inc.
4400 College Boulevard, Suite 160
Overland Park, Kansas 66211

Reference 25

SOKKIA™

LEVEL
BOOK

MOUND STREET PCB

ST LOUIS, MO

CERCLIS ID No. M00000093682

No. 8152-50

(14)

(15)

Site visit - sample collection

April 1, 1996

1100 leave SVE Overland Park, KS

1600 arrive SVE St. Louis

pick up equipment

April 2, 1996

0700 leave Overland Park for site

0730 arrive site

Sunny day, 70°
windyMichael W. McClundy
4/1/96

Michael W. McClundy 4/2/96

(16)

0730 M. May calibrate HnU

M. McCurdy calibrate

air samplers - see Corps

E&E personnel on-site

Scott Hayes

Audy Mazzeo

Randy Schademann

Air sampling pumps

M. May - PCB (low flow)

R. Schademann - metals (yellow)

A. Mazzeo - VOC

Michael W. McCurdy
4/2/96

Michael W. McCurdy
4/2/96

(17)

(18)

Ed E personnel will
be operating the
geoprobe and decon
of equipment

M. May to log holes
see boring logs

M. May & M. McCurdy to
collect samples

Photo 1 - Probe Point 1

Michael W McCurdy
4/2/96

(19)

850 water level measurement

at south well -

depth at 29.85' *

casing height 3.25'

depth = 26.60'

* top of casing - west side

915

Geoprobe setup

dummy probe to see


what to expect -

hammering required

water in last section

depth at 18'

(Apex)



(Photo 1)

* Location

to south to flood wall

20

930

Sampling tube pushing

hit solid at 18.5'

water in sample tube

- concrete brick in tube

- no reading on flow


no sample

move to corner - south

hole backfilled with grout

not enough water to collect

955



Location

solid at 19.5'

possibly old asphalt

road layer in 0-3'


Michael W McCurdy
4/2/96

Michael W McCurdy
4/2/96

21

(22)

Photo 2 - Sample 101



Probe Point 2

H10

sample at 17'-19' 101 None

~~sample at 17'-19'~~but solid at 20'
moved over 1 1/2' forsecond aliquot at
17-19 feet

Sample 101


Michael W McCurdy
4/2/96Michael W McCurdy
4/2/96

(23)

(24)

Photo 3 - abandoned area
debris rock & concrete
encountered -
no sample collected

Michael W. McCurdy
4/2/96



refusal at ~4'
refusal at ~1'
refusal at ~1'
refusal at 16'
refusal at 14'
attempt sample 10-12
sample collected 2-3"
retrieval - concrete core
no soil

no sample collected

Michael W. McCurdy
4/2/96

(25)


(26)

1215

Photo 4 - abandoned area
no sample collected
rock & debris

Michael W. McCurdy
4/2/96

(27)



refusal at 15'
refusal 12-14 sample
bricks, gravel
~ 6" sample retrieval
moved east to middle of
road

(4)

site

ind *

~ 6" sample
rock gravel
minor sand
no sample

(28)

1307 pack trucks for lunch

1330 leave for lunch

** Stated only one sample was collected at the former building location. We were going to move to the vacant area between the flood wall & site to collect the remaining samples. Requested Dave leave a message on my voice mail at 663-2108.

Michael W. McLindy
4/2/96

(29)

Message with Dave Crawford at EPA *

14:10 arrive site

calibrate sampling pumps

* Stated we had attempted sample collection at the former building location & were having difficulty collecting samples due to concrete, brick & rock in the subsurface.
** (previous page)

Michael W. McLindy
4/2/96


(30)

Photo 5 - Sample 103

Photo 6 - Sample 103

Photo 7 - location of
geoprobe boring
for 102/103

14:20



road

N

sample 16-18' attempt
rocksample
#

Hnu

sample 18-20'

102

none

sample 25'-27'

103

none

refusal at 27'

both samples submitted

Michael W. McCurdy
4/2/96Michael W. McCurdy
4/2/96


(31)

(32)

Photo 8 - sample 100

Photo 9 - location of
100 & 100D

1530

Sample
#H₂O

Sample 25-27 100 none

Sample 25-27 100D none

did not go beyond 27'

1610

Equipment unsate

From decomposed sample
tube after 100 soil -

Sample No. 008

Michael W. McClintock
4/2/96Michael W. McClintock
4/2/96

(33)

34

1700 E&E personnel leave site

1715 S&E personnel leave site

1930

Message from Dave Crawford
that there is not much
else to do except move
to the vacant area for
the samples. No need to
call in morning, but he will
be in if needed.

Michael W. McCurdy
4/2/96

Michael W. McCurdy
4/2/96

35

(36)

April 3, 1996

0700 Equipment pickup
peristaltic pump works
on AC when plugged in

0830 Arrive site
E&E already present

Landy Schademann }
Scott Hayes } E&E
Andy Mazzeo } already
on-site

Sunny day, 70°F
windy

Michael W. McCurdy
4/3/96

(37)

Michael W. McCurdy
4/3/96

(38)


Photo 10 - South of site

Photo 11 - Sample 104
location

Photo 12 - Sample 104
location

Michael W McCurdy
4/5/96

840



sample 25'-27'

Sample Hau
104 none

930

Randy to hotel to pick
up shipped pump
Mike May to call Wally
to deliver another
pump

Michael W McCurdy
4/5/96

(39)

(40)

845

Water sample from
south wellplug in pump to battery
on truck - pump does not
workE&E pump to arrive this
morning

915

Field Blank 003

calibrate YSI meter
pH onlyMichael W Mc Cundy
4/8/96

(41)

Michael W Mc Cundy
4/8/96

(42)

Photo 13 - Equipment for well
sampling water level
meter, YSI & pump
at North well

Photo 14 - Sampling of north
well

Note:

pumpers nearing
the maximum range
of the peristaltic
type pump
south well pump
TAT Engineering
Model 410-660B
Series A-93

1010 Randy & Mike return with E&E
pump

1020 South well

top of casing 29.32'

casing height 3.25'

water level 26.07 bgs

well depth 49.31

casing height 3.25

bottom of well 46.06 bgs

37' tubing

pumping began south well

	T.C	Cond. in $\mu\text{mhos/cm}$	pH	
1044	19.2	0.948	6.84	initial

1055	19.5	0.830	6.98	after 5 min
------	------	-------	------	----------------

1106	19.8	0.936	6.95	"
------	------	-------	------	---

1122	19.9	0.935	6.98	"
------	------	-------	------	---

pump rate is approximately 0.03 gpm
Michael W. McCurdy 4/5/96

(43)

(44)

1128 South well


Photo 15 - South well

top of casing 29.58 ft

sample began 001

001D

Photo 16 - South well

approximately 1.4 gallons
removed during purgingPhoto 17 - From south well
looking toward
north wellwater appears clear, no
visible sediment or
suspended matterPhoto 18 - from north well
looking toward
south well


slight petroleum odor

Michael W. McCurdy
4/3/96Michael W. McCurdy
4/3/96

(45)

(46)

Photo 13 - Pump & YSI
setup at North
well



Note: purging near the
limit of the
peristaltic type pump

Photo 14 - North well

Michael W. McClintock
4/3/96

(47)

1130 north well

top of casing 28.43 north
casing height 3.75 side
water level 24.68 bgs

well depth 51.02

casing height 3.75

well bottom 47.27 bgs

39' tubing

1148

pumping at north well

	T °C	cond. μ S/cm	PH	
1152	18.6	.963	6.75	initial
1203	18.8	.958	6.80	clear, no solids
1214	19.7	.963	6.78	"

pumping rate is approx. 0.06 gpm
Michael W. McClintock 4/3/96

(48)

North well water -
 appears clear
 no visible suspended
 matter or sediment
 slight petroleum odor

Michael W McCurdy
 4/3/96

1215 to north well
 top of casing 28.54

sample begun 002
 approx. 1.4 gallons removed by purge

1245 sample north well
 completed


B10 switch pumps at ^{south} ~~north~~ well

1335 sampling 001/001D
 completed

Michael W McCurdy
 4/3/96

(49)

(50)



1345 leave site

1445 arrive S.E. St Louis office
drop off equipment

Photo 19 - Sampled area

1515 leave S.E. St Louis office

Photo 20 - Sampled area

Photo 21 - Sampled area

2015 arrive S.E. overland park

Photo 22 - Sampled area




Photo 23 - Mississippi River

Photo 24 - Water intake in IL

Photo 25 - Mississippi River

Michael W McCurdy
4/3/96

(51)

Michael W McCurdy
4/3/96

(52)

April 4, 1996

10:30 Deliver samples to
EPA at Funston Rd
in Kansas City, KS

11:30 Arrive EPA

End of Log Book

Michael W McCurdy
4/4/96

Michael W McCurdy
4/4/96

(53)



DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
1222 SPRUCE STREET
ST. LOUIS, MISSOURI 63103-2833
27 November 1995



REPLY TO
ATTENTION OF
Engineering Division
Geotechnical Branch

Reference 26

Mr. Mike May
Sverdrup Environmental, Inc.
4400 College Blvd., Suite 160
Overland Park, KS 66211

RE: Request for monitoring well maps, analytical data,
well installation data, Mound Street PCB site, St.
Louis, MO; Sverdrup Project No. 010865-37303


Dear Mr. May:

As you requested, please find enclosed maps of the
construction of the St. Louis Floodwall, Reach 3, which
contains Mound Street PCB site.

Please note that there are no relief wells indicated
parallel with your site, the nearest wells are located
to the north of Mound Street. I have not been able to
locate any additional relief well information for the
site area. Also, please note that there are a few
manholes parallel with your site. These might be
mistaken for relief wells. I have enclosed
construction details of these manholes.

The sponsor, St. Louis Metropolitan Sewer District, has
maintenance responsibility for the relief wells and
manholes along the floodwall.


If you require additional information of the St. Louis
Floodwall, please call me at (314) 331-8444.


Catherine W. Fox
Geology Section

— Soil survey of

Reference 27

St. Louis County and St. Louis City, Missouri



United States Department of Agriculture
Soil Conservation Service
In cooperation with
Missouri Agricultural Experiment Station

U.S. Department of Commerce
Economics and Statistics Administration
BUREAU OF THE CENSUS

1990 CPH-1-27

CENSUS '90



1990 Census of
Population and Housing
Summary Population and
Housing Characteristics
Missouri

Reference 28




Table 5. Household, Family, and Group Quarters Characteristics: 1990—Con.


(For definitions of terms and meanings of symbols, see text)

State County County Subdivision Place	Family households					Nonfamily households				Persons per—		Persons in group quarters		
	Persons in households	All house- holds	Total	Married- couple family	Female house- holder, no husband present	Total	Householder living alone			Household	Family	Total	Institu- tionalized persons	Other per- sons in group quarters
							Total	65 years and over						
								Total	Female					
St. Charles County—Con														
Zumbelt township	11 415	4 480	3 000	2 489	382	1 480	1 219	232	185	2 55	3 17	181	170	11
St. Charles city (pt.)	7 947	3 359	2 048	1 679	271	1 311	1 092	203	160	2 37	3 08	181	170	11
St. Peters city (pt.)	4	1	1	1	—	—	—	—	—	4 00	4 00	—	—	—
St. Clair County	8 267	3 499	2 441	2 148	222	1 058	986	608	478	2 36	2 88	190	190	—
Appleton township	1 516	666	419	364	49	247	232	155	130	2 28	2 96	68	68	—
Appleton City city	1 212	562	331	281	44	231	218	147	124	2 16	2 89	68	68	—
Butler township	1 249	547	363	306	41	184	167	114	93	2 28	2 81	96	96	—
Lowry City city	627	297	172	132	32	125	115	93	79	2 11	2 75	96	96	—
Center township	203	77	60	51	3	17	15	7	3	2 64	2 98	—	—	—
Chalk Level township	150	58	44	38	4	14	12	6	5	2 59	3 02	—	—	—
Collins township	604	236	182	156	22	54	50	28	25	2 56	2 98	—	—	—
Collins village	144	60	39	30	9	21	21	17	16	2 40	3 13	—	—	—
Dallas township	326	129	102	94	4	27	25	12	10	2 53	2 88	—	—	—
Gerster town	40	16	10	9	—	6	6	2	2	2 50	3 30	—	—	—
Doyal township	496	203	149	139	8	54	52	28	18	2 44	2 94	—	—	—
Vista village	50	24	17	17	—	7	7	4	3	2 08	2 53	—	—	—
Jackson township	260	114	80	76	3	34	30	17	11	2 28	2 75	—	—	—
Manegaw township	285	106	85	80	3	21	19	11	10	2 69	3 07	—	—	—
Osage township	204	80	62	56	4	18	16	6	5	2 55	2 94	—	—	—
Osceola township	1 403	650	403	335	57	247	238	153	118	2 16	2 81	26	26	—
Osceola city	729	387	197	155	40	190	187	127	101	1 88	2 68	26	26	—
Polk township	179	76	59	52	4	17	17	9	7	2 36	2 73	—	—	—
Roscoe township	503	211	162	147	10	49	47	27	18	2 38	2 75	—	—	—
Roscoe village	100	46	32	28	3	14	14	7	6	2 17	2 56	—	—	—
Speedwell township	437	177	137	127	7	40	35	18	13	2 47	2 80	—	—	—
Taber township	212	78	59	56	2	19	19	11	7	2 72	3 27	—	—	—
Washington township	240	91	75	71	1	16	12	6	5	2 64	2 87	—	—	—
Ste. Genevieve County	15 792	5 707	4 416	3 878	374	1 291	1 153	625	476	2 77	3 21	245	181	64
Beauvais township	1 723	600	465	405	39	135	119	69	50	2 87	3 35	49	49	49
St. Mary city	412	174	111	80	20	63	58	34	25	2 37	3 02	49	49	49
Jackson township	2 629	936	747	672	50	189	166	85	60	2 81	3 19	—	—	—
Bloomdale city	353	142	102	92	5	40	39	28	23	2 49	3 04	—	—	—
Ste. Genevieve township	8 524	3 154	2 375	2 064	230	779	707	392	317	2 70	3 19	183	181	2
Rosky Ridge village (pt.)	56	29	19	19	—	10	9	4	2	1 93	2 37	—	—	—
Ste. Genevieve city	4 364	1 793	1 212	989	183	581	536	308	260	2 43	3 04	47	47	—
Saline township	887	311	252	230	14	59	54	30	19	2 85	3 21	—	—	—
Union township	2 029	706	577	507	41	129	107	49	30	2 87	3 18	13	—	13
Rosky Ridge village (pt.)	306	127	93	83	6	34	26	9	4	2 41	2 76	—	—	—
St. Francois County	45 725	17 670	13 101	10 871	1 788	4 569	4 084	2 225	1 809	2 59	3 04	3 179	2 832	347
Big River township	1 435	550	433	379	36	117	88	45	34	2 61	2 90	—	—	—
Iron township	2 899	1 105	830	686	117	275	252	161	123	2 62	3 06	22	11	11
Bismarck city	1 557	604	441	355	69	163	152	104	83	2 58	3 06	22	11	11
Iron Mountain Lake city	632	240	174	141	28	66	60	35	23	2 63	3 11	—	—	—
Liberty township	1 482	546	450	409	27	96	93	50	30	2 71	3 04	—	—	—
Marion township	1 495	537	443	403	27	94	70	23	12	2 78	3 03	—	—	—
Pendleton township	2 255	823	654	565	64	169	150	84	47	2 74	3 10	83	59	24
Perry township	7 499	2 882	2 193	1 865	251	689	621	379	310	2 60	3 02	111	100	11
Bonne Terre city	3 819	1 474	1 037	819	180	437	405	264	228	2 59	3 17	52	41	11
Flat River city (pt.)	—	—	—	—	—	—	—	—	—	—	—	59	59	—
Leadwood city (pt.)	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Randolph township	8 841	3 297	2 536	2 092	361	761	669	375	310	2 68	3 10	—	—	—
Desloge city (pt.)	3 714	1 461	1 074	881	155	387	340	185	153	2 54	3 01	—	—	—
Elvins city (pt.)	1 137	417	324	262	56	93	85	49	39	2 73	3 13	—	—	—
Flat River city (pt.)	32	13	12	11	1	1	1	1	1	2 46	2 58	—	—	—
Leadwood city (pt.)	1 247	448	358	282	62	90	84	52	45	2 78	3 17	—	—	—
Rivermines village (pt.)	62	24	20	16	2	4	3	2	2	2 58	2 80	—	—	—
St. Francois township	19 819	7 930	5 562	4 472	905	2 368	2 141	1 108	943	2 50	3 03	2 963	2 662	301
Desloge city (pt.)	331	130	101	85	13	29	27	8	7	2 55	2 95	105	105	—
Elvins city (pt.)	254	94	68	52	12	26	18	10	8	2 70	3 21	—	—	—
Esther city	1 071	422	294	210	69	128	116	63	58	2 54	3 07	—	—	—
Farmington city	8 927	3 749	2 522	2 079	378	1 227	1 136	610	522	2 38	2 98	2 671	2 557	114
Flat River city (pt.)	4 717	1 871	1 286	961	278	585	530	297	258	2 52	3 08	15	—	15
Leadington city	201	90	60	44	15	30	29	10	7	2 23	2 73	—	—	—
Rivermines village (pt.)	345	120	90	71	12	30	24	14	10	2 88	3 31	52	—	52
St. Louis County	975 815	380 110	270 421	219 468	40 657	109 689	93 532	35 078	28 674	2 57	3 10	17 714	12 586	5 128
Airport township	33 097	13 211	8 751	5 797	2 407	4 460	3 804	1 319	1 046	2 51	3 11	182	151	31
Bel-Ridge village (pt.)	215	58	51	25	19	7	5	1	1	3 71	3 80	—	—	—
Berkeley city (pt.)	10 213	3 596	2 701	1 608	910	895	769	247	190	2 84	3 31	27	16	11
Breckenridge Hills village (pt.)	701	281	203	110	83	78	55	13	7	2 49	2 84	—	—	—
Brigdeton city (pt.)	883	487	207	130	57	280	218	31	23	1 81	2 52	—	—	—
Cool Valley city (pt.)	6	2	1	—	—	1	1	1	1	3 00	5 00	100	100	—
Edmundson village	1 111	429	288	205	65	141	112	43	33	2 59	3 18	—	—	—
Kinloch city (pt.)	2 451	788	554	167	348	234	216	123	92	3 11	3 89	—	—	—
St. Ann city (pt.)	11 525	5 213	3 044	2 237	628	2 169	1 868	632	508	2 21	2 89	55	35	20
St. John city (pt.)	1 591	616	451	350	77	165	138	58	47	2 58	3 04	—	—	—
Woodson Terrace city	4 362	1 728	1 243	960	218	485	418	168	143	2 52	2 99	—	—	—
Bonhomme township	37 258	14 934	10 452	8 788	1 330	4 482	3 976	2 053	1 710	2 49	3 06	638	582	56
Des Peres city (pt.)	508	152	142	136	2	10	8	2	—	3 34	3 46	—	—	—
Fenton city (pt.)	3 290	1 103	955	849	74	148	128	47	32	2 98	3 23	56	56	—
Glendale city (pt.)	1	1	—	—	—	1	1	—	—	1 00	—	—	—	—
Kirkwood city	27 002	11 212												

Table 5. Household, Family, and Group Quarters Characteristics: 1990—Con.

[For definitions of terms and meanings of symbols see text]

State County County Subdivision Place	Persons in households		Family households			Nonfamily households				Persons per—		Persons in group quarters			
			Total	Married couple family	Female house- holder, no husband present	Total	Householder living alone		Total	Female	Household	Family	Total	Insti- tutionalized persons	Other per- sons in group quarters
							Total	65 years and over							
Worth County—Cor.	229	89	66	59	5	23	18	13	13	2 57	3 03	—	—	—	
Middlefork township	103	37	27	24	2	10	7	5	5	2 78	3 33	—	—	—	
Worth town	183	81	57	50	6	24	22	14	7	2 26	2 70	—	—	—	
Smith township	58	32	16	14	2	16	15	11	5	1 81	2 44	—	—	—	
Allendale town	485	215	146	131	7	69	65	46	37	2 26	2 80	—	—	—	
Union township	174	91	49	44	4	42	42	34	28	1 91	2 67	—	—	—	
Sheridan town	16 558	6 510	4 725	4 059	518	1 785	1 679	998	780	2 54	3 06	200	199	1	
Wright County	893	321	255	227	21	66	58	26	21	2 78	3 20	—	—	—	
Boone township	510	177	143	127	12	34	32	13	10	2 88	3 26	—	—	—	
Brush Creek township	1 061	400	310	261	34	90	86	56	44	2 65	3 09	—	—	—	
Clark township	389	151	106	86	18	45	43	30	26	2 58	3 19	—	—	—	
Norwood city (pt.)	382	155	122	106	9	33	29	14	11	2 46	2 80	—	—	—	
Elk Creek township	1 051	381	292	256	26	89	81	46	32	2 76	3 22	—	—	—	
Gasconade township	108	48	29	23	5	19	17	12	9	2 25	3 00	—	—	—	
Hartville city (pt.)	1 061	452	292	256	28	160	154	111	87	2 35	3 03	7	7	—	
Hart township	380	206	93	70	18	113	112	86	68	1 84	2 83	7	7	—	
Hartville city (pt.)	533	189	154	134	15	35	34	16	12	2 82	3 14	—	—	—	
Montgomery township	5 569	2 382	1 575	1 292	236	807	767	466	376	2 34	2 95	129	129	—	
Mountain Grove township	4 141	1 860	1 158	916	208	702	667	416	341	2 23	2 89	27	27	—	
Mountain Grove city (pt.)	60	26	17	15	1	9	9	4	3	2 31	3 00	—	—	—	
Nowood city (pt.)	2 638	1 011	730	619	94	281	258	156	120	2 61	3 15	64	63	1	
Pleasant Valley township	1 428	587	376	298	70	211	194	125	103	2 43	3 14	1	—	1	
Mansfield city	1 045	393	314	285	19	79	77	46	36	2 66	3 04	—	—	—	
Union township	550	194	154	144	5	40	37	16	12	2 84	3 25	—	—	—	
Van Buren township	1 265	455	384	352	19	71	66	32	19	2 78	3 03	—	—	—	
Wood township	7	1	1	—	—	—	—	—	—	7 00	7 00	—	—	—	
Mountain Grove city (pt.)	385 916	164 931	90 945	50 557	33 864	73 986	64 677	26 519	20 788	2 34	3 21	10 769	5 900	4 869	
St. Louis city															




CLIMATIC ATLAS OF THE UNITED STATES

1973



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 7
25 FUNSTON ROAD
KANSAS CITY, KANSAS 66115



Sverdrup Environmental, Inc.

May 3 1996

DATE:

SUBJECT: Data Transmittal for Activity #: DCICY
Site Description: Mound Street PCBs

FROM: Andrea Jirka, Program Manager RDJ-CJ
Regional Laboratory, Environmental Services Division

TO: Dave Crawford
SWPR

Attached is the data transmittal for the above-referenced site. The data contained in this transmittal have been approved by the Regional Laboratory. This should be considered a Partial or X Complete data transmittal (completes transmittal of). The Project Leader should notify the Regional Laboratory with 14 days of any changes in the LAST analytical database. If you have any questions, comments, or data changes, please contact Dee Simmons at 551-5129.

Attachment

cc: Analytical Data File

Superfund



Guidance for Performing Site Inspections Under CERCLA


Reference 31

includes revised

C-33

C-44

Interim Final



United States
Environmental Protection
Agency
Superfund

Office of Emergency and
Remedial Response
Washington, DC 20460

Publication
September 1995



Superfund Chemical Data Matrix

Reference 32

Reference 33

The Hazard Ranking System Guidance Manual

Interim Final

Hazardous Site Evaluation Division
Office of Solid Waste and Emergency Response
U.S. Environmental Protection Agency
Washington, DC 20460

Friday
December 14, 1990

Reference 35

Part II

Environmental Protection Agency

40 CFR Part 300

Hazard Ranking System; Final Rule